

23W0013 - CMP REPAIR, BOLEN DR. - CITY OF PASO



MGE Underground, Inc.

Post Office Box 4189

Paso Robles, CA 93447

Contact: jlundy@mgeunderground.com

Phone: 805-238-3510

Fax: 805-238-1975

Quote To: Kevin Wells - City of Paso

Job Name: 23W0013

Address: 715 Bolen Dr.
Paso Robles, CA

Date of Plans:

Email: kwells@prcity.com

Phone:

Fax:

Bid Date: 05/09/23

Thank you for considering our proposal.

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	SINK HOLE - CMP REPAIR	1.00	LS	297,893.00	297,893.00
GRAND TOTAL					\$297,893.00

NOTES:

PROJECT SCOPE CLARIFICATIONS:

MGE, with support of Sancon Technologies, will provide manpower, equipment, and material to complete storm drain rehabilitation on Bolen Dr.

Proposal includes:

MGE & Sancon to use confined space entry procedures and equipment.

(Access points (1) West of Bolen, Storm drain export creek access, (1) residents back yard, 36" CMP grate access) to clean debris in 510' of CMP storm drain, repair damaged areas in CMP, fill voids in CMP, and prep 510' for CIPP liner installation.

Once prep is complete, CMP will be confirmed its ready for liner with video verification. Once verified and measured, the liner will be ordered and customized for this project. (Liner lead time is 2-4 weeks.)

36" x 13.5mm x 510' of Liner will be installed, accessing from the points mentioned above, and cured in place with polyester resin.

Once liner process is complete, MGE will complete backfilling the sinkhole at 715 Bolen Dr. Sink hole will be backfilled with 2-sack slurry and topsoil.

LIFESPAN: Expectancy of CMP Rehabilitation Liner - 50 years.

PROJECT TIMELINE:

Clean / Prep CMP expectancy: 5 days

(2 - 4-week lead time for liner to be customized)

Liner installation & cure: 1 day.

Backfill sink hole: 1 day.

SUBCONTRACTOR:

Sancon Technologies, Inc.

STATE CONTRACTORS LICENSE #774055

DIR REGISTRATION # 1000008879

INCLUSIONS:

-All required labor, equipment, tooling, and materials, unless specifically excluded.

-All work to be performed per the plans provided to MGE and the standard specifications applicable at the time of bid.

Attachment 2

EXCLUSIONS/CLARIFICATIONS:

- Unforeseen Conditions including groundwater, rock, hardpan, unmarked and/or unknown utilities, flooding, hazardous materials, unsuitable onsite materials. (Please note: MGE shall make every reasonable effort to determine soil conditions prior to bid submission. However, any increase in job cost, directly or indirectly, that is due to the unforeseen conditions shall be considered out of scope and MGE reserves the right to increase the contract amount accordingly.)
- Any and all considerations for environmental, biological, or archeological monitoring and any cost associated with such regulatory agencies
- Utilities or work not indicated on the bid plans or acknowledged in the bid specifications.
- Additional mobilizations (except for MGE's convenience)
- Land owner access agreements
- Survey and staking
- Soils and compaction testing
- Permits / Permitting fees
- Bonding
- SWPPP
- Erosion Control
- Additional repair beyond the 510' planned rehabilitation
- Hard scape repairs
- Any and all work associated with PGE power pole and overhead lines.

TERMS:

- Proposal valid for 30 days. Pricing may be subject to material price increases beyond MGE's control.
- Progress billing cycle shall be no more than monthly.
- Payment to be made within 30 days of invoice. Finance charges of 1.5% per month shall be applied to all past due balances.

CUSTOMER ACCEPTANCE:

Firm: _____

Title: _____

Print Name: _____

Signed: _____ Date: _____

Please return the signed original.