#### CALIFORNIA ENVIRONMENTAL QUALITY ACT ENVIRONMENTAL INITIAL STUDY CHECKLIST FORM Public Review Period May 12, 2023 – June 2, 2023

Recirculation

1. PROJECT TITLE: Peterbilt Service Center (P22-0017)

Billboard Sign (P23-0019)

**Entitlements:** Development Plan (PD22-02) for a Peterbilt

Sales and Service Center

Conditional Use Permit (CUP22-16) for a

highway-oriented sign

Rezone (RZN22-03) to expand the Highway-

Oriented Sign overlay district

Conditional Use Permit (CUP23-03) for a

billboard sign

2. LEAD AGENCY: City of Paso Robles

> 1000 Spring Street Paso Robles, CA 93446

**Contact:** Katie Banister Phone: (805) 237-3970

**Email:** kbanister@prcity.com

3. PROJECT LOCATION: 2805 Theatre Drive

> Paso Robles, CA 93446 APN: 009-851-022

4. PROJECT PROPONENTS:

**Proponent:** Archer Paso Robles, LLC

**Contact:** Pamela Jardini Phone: 805-801-0453

**Email:** planningsolutions@charter.net

**Proponent:** Outfront Media, LLC **Contact:** Armen Devejian 559-389-8166 Phone:

**Email:** devejian@adeinc.biz

5. GENERAL PLAN DESIGNATION: Regional Commercial (RC)

6. **ZONING:** Commercial Highway with Planned

Development Overlay (C2 PD)

7. PROJECT DESCRIPTION: Development plan for the construction of a

25,000 square-foot semi-truck service, parts retailer, and sales dealership. Expansion of the Highway-Oriented Sign overlay district, and new highway-oriented sign. New billboard sign to replace an existing billboard sign.

8. ENVIRONMENTAL SETTING:

The 6.6-acre property is nearly level. The site is undeveloped except for existing frontage improvements and an existing billboard sign. Vegetation is a mix of non-native herbaceous plants and several native oak trees. The Salinas River is located approximately 4,000 feet to the east of the property (east of Highway 101). The property is at the southern boundary of the city. Properties to the north are developed with commercial uses. Properties to the south are developed with residential uses. The property to the west is currently undeveloped, but is entitled for a mini-storage development. A low-density residential neighborhood is located further to the west. Highway 101 is located to the east of the property.

- 9. OTHER AGENCIES WHOSE APPROVAL IS REQUIRED (AND PERMITS NEEDED):

  None
- 10. Have California Native American tribes traditionally and culturally affiliated with the project area requested consultation pursuant to Public Resources Code section 21080.3.1? If so, is there a plan for consultation that includes, for example, the determination of significance of impacts to tribal cultural resources, procedures regarding confidentiality, etc.?

#### ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED:

The environmental factors checked below would be potentially affected by this project, involving at least one impact that is a "Potentially Significant Impact" as indicated by the checklist on the following pages. Aesthetics Agriculture / Forestry  $\boxtimes$ Air Quality  $\boxtimes$ Resources  $\boxtimes$ **Biological Resources Cultural Resources** Energy X Geology/Soils  $\boxtimes$ Greenhouse Gas  $\boxtimes$ Hazards & Hazardous  $\boxtimes$ **Emissions** Materials Hydrology/Water Quality Land Use / Planning Mineral Resources Population / Housing Noise **Public Services**  $\boxtimes$ **Transportation** Tribal Cultural Recreation Resources Utilities / Service Systems Wildfire Mandatory Findings of Significance **DETERMINATION:** (To be completed by the Lead Agency) On the basis of this initial evaluation: I find that the proposed project COULD NOT have a significant effect on the environment, and a NEGATIVE DECLARATION will be prepared.  $\boxtimes$ I find that although the proposed project could have a significant effect on the environment, there will not be a significant effect in this case because revisions in the project have been made by or agreed to by the project proponent. A MITIGATED NEGATIVE DECLARATION will be prepared. I find that the proposed project MAY have a significant effect on the environment, and an ENVIRONMENTAL IMPACT REPORT is required. I find that the proposed project MAY have a "potentially significant impact" or "potentially significant unless mitigated" impact on the environment, but at least one effect 1) has been adequately analyzed in an earlier document pursuant to applicable legal standards, and 2) has been addressed by mitigation measures based on the earlier analysis as described on attached sheets. An ENVIRONMENTAL IMPACT REPORT is required, but it must analyze only the effects that remain to be addressed. I find that although the proposed project could have a significant effect on the environment, because all potentially significant effects (a) have been analyzed adequately in an earlier EIR or NEGATIVE DECLARATION pursuant to applicable standards, and (b) have been avoided ıs d.

DECLARATION, including revision ed project, nothing further is required
May 12, 2023
Date

#### **EVALUATION OF ENVIRONMENTAL IMPACTS:**

- 1. A brief explanation is required for all answers except "No Impact" answers that are adequately supported by the information sources a lead agency cites in the parentheses following each question. A "No Impact" answer is adequately supported if the referenced information sources show that the impact simply does not apply to projects like the one involved (e.g., the project falls outside a fault rupture zone). A "No Impact" answer should be explained where it is based on project-specific factors as well as general standards (e.g., the project will not expose sensitive receptors to pollutants, based on a project-specific screening analysis).
- 2. All answers must take account of the whole action involved. Answers should address off-site as well as on-site, cumulative as well as project-level, indirect as well as direct, and construction as well as operational impacts.
- 3. "Once the lead agency has determined that a particular physical impact may occur, then the checklist answers must indicate whether the impact is potentially significant, less than significant with mitigation, or less than significant. "Potentially Significant Impact" is appropriate if there is substantial evidence that an effect may be significant. If there are one or more "Potentially Significant Impact" entries when the determination is made, an EIR is required.
- 4. "Negative Declaration: Less Than Significant With Mitigation Incorporated" applies where the incorporation of mitigation measures has reduced an effect from ""Potentially Significant Impact" to a "Less Than Significant Impact." The lead agency must describe the mitigation measures, and briefly explain how they reduce the effect to a less than significant level (mitigation measures from "Earlier Analyses," as described in (5) below, may be cross-referenced).
- 5. Earlier analyses may be used where, pursuant to the tiering, program EIR, or other CEQA process, an effect has been adequately analyzed in an earlier EIR or negative declaration. Section 15063(c)(3)(D). In this case, a brief discussion should identify the following:
  - a. Earlier Analysis Used. Identify and state where they are available for review.
  - b. Impacts Adequately Addressed. Identify which effects from the above checklist were within the scope of and adequately analyzed in an earlier document pursuant to applicable legal standards, and state whether such effects were addressed by mitigation measures based on the earlier analysis.
  - c. Mitigation Measures. For effects that are "Less than Significant with Mitigation Measures Incorporated," describe the mitigation measures which were incorporated or refined from the earlier document and the extent to which they address site-specific conditions for the project.

Lead agencies are encouraged to incorporate into the checklist references to information sources for potential impacts (e.g., general plans, zoning ordinances). Reference to a previously prepared or outside document should, where appropriate, include a reference to the page or pages where the statement is substantiated.

Supporting Information Sources: A source list should be attached, and other sources used or individuals contacted should be cited in the discussion.

The explanation of each issue should identify:

- a. the significance criteria or threshold, if any, used to evaluate each question; and
- b. the mitigation measure identified, if any, to reduce the impact to less than significance

Less Than Significant with Mitigation Incorporated Attachment 9
Significant Impact
Impact

<b>I.</b> A	. AESTHETICS: Would the project:								
a.	Have a substantial adverse effect on a scenic vista?								
	Discussion: The site is located at the southern boundary of the city adjacent to the southern Highway 101 Gateway to the City. The General Plan Conservation Element identifies the full length of Highway 101 as a visual corridor, where "development shall be designed to make a positive visual impression" and "Billboards shall be limited in number". Action Item 2 of General Plan Land Use Element Policy LU-2B includes "Enhancing views along highways, roads, streets, and rail corridors with landscaping, building setbacks, enhanced architecture and signage/monuments." The project would include the demolition of an existing billboard and development of the site with a commercial building, a highway-oriented sign, and a replacement billboard sign. The design of the building has been reviewed by the City Development Review Committee and is similar to the architecture of other vehicle dealerships in the vicinity.								
	The existing billboard is located about 5 feet from the pavement of Theatre Drive (and if not removed, wou have been over the sidewalk that will be constructed with this project). The sign is 22 feet tall with 400 square feet of sign area facing south and 600 square feet of sig area facing north. The replacement billboard would be located 35 feet further west from Theatre Drive and Highway 101. It would have reduced sign are with 300 square feet facing each north and south, but its height would be increased to 30 feet. Although it i proposed to be taller, the replacement billboard would have less sign area and be further away from Highway 101. Considering all these factors together, the aesthetic impact of the new billboard to the Highway 101 visual corridor will be comparable to the aesthetic impact of the existing billboard. In addition, the billboard is subject to a conditional use permit and the Planning Commission and/or City Council may add additional conditions to further ensure the billboard is compatible with the neighboring area and City plans and policies. With the following mitigation measure implemented, the billboard will have a less than significant impact:				ith 400 ent billboard ced sign area lthough it is om Highway away 101 the billboard d additional and policies.				
	Mitigation Measure AES-1 would require sh visible from adjacent roadways or properties			d, so the light so	urce is not				
	The project includes a request to erect a freeway-oriented sign for Peterbilt (the proposed onsite business). This sign would add an additional sign visible and readable from the highway. The sign is similar in scale and design to signs for other car dealerships on Theatre Drive, namely Kia (with a 28-foot-tall sign) and Chevrolet (with an approximately 30-foot-tall sign). The proposed freeway-oriented sign requires rezoning expand the Highway-Oriented Sign overlay district to the subject property and approval of a conditional us permit to ensure compatibility of the sign with the neighborhood. The highway-oriented sign will have a least than significant aesthetic impact when the following mitigation measures are implemented.								
	Mitigation Measure AES-2 would require the maximum of 30 feet in height.	e proposed freewa	y-oriented sign fo	or Peterbilt to be	limited to a				
	Mitigation Measure AES-3 would require an southern portion of the lot be collocated with				ped on the				
	Mitigation Measure AES-4 would require lar	ndscaping and stre	et trees along the	entire property f	rontage.				
b.	Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?			$\boxtimes$					

Discussion: The property includes several mature native oak trees, which will be retained with the project. Three 4-inch diameter oak saplings are proposed for removal. These trees fall below the size protected by the

Less Than **Significant** with Mitigation **Incorporated**  Attachment 9 **Impact** 

**Significant Impact** 

Oak Tree Preservation Ordinance. The impact is less than significant. Substantially degrade the existing visual character or quality of public views of the site and its surroundings? (Public views are those that are experienced from publicly П  $\boxtimes$ accessible vantage point). If the project is in an urbanized area, would the project conflict with applicable zoning and other regulations governing scenic quality? Discussion: This site is in an urbanized area visible from Highway 101, Theatre Drive and Nutwood Circle. The proposed design of the development is in keeping with other commercial developments in the vicinity including Kia and Chevrolet dealerships, vehicle repair shops, and an RV sales use. d. Create a new source of substantial light or  $\boxtimes$ glare which would adversely affect day or nighttime views in the area? Discussion: Electronic reader copy is prohibited on billboard signs. Standard conditions of approval and Mitigation Measure AES-1 require any exterior lights to be shielded to prevent offsite glare, so the impact will be less than significant. II. AGRICULTURE AND FOREST RESOURCES: In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Dept. of Conservation as an optional model to use in assessing impacts on agriculture and farmland. Would the project: Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared  $\boxtimes$ pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use? Discussion: The site is in an urbanized area and will not have an impact on agricultural resources. The Natural Resources Conservation Service (NRCS) has mapped one soil map unit on the site, the Lockwood channery loam, 0-2 percent slopes<sup>10</sup>, which is prime farmland if irrigated with a land capability class of 3s (severe limitations) when not irrigated, however, the Farmland Mapping and Monitoring Program of the California Resources Agency and the Open Space Element of the Paso Robles General Plan (Figure OS-1, Important Farmland) identify the site as Urban / Built-Up Land<sup>1, 12</sup>. The site is surrounded by urban uses and is not under cultivation, nor has it been for at least 20 years. Conflict with existing zoning for agricultural  $\boxtimes$ use, or a Williamson Act contract? Discussion: The site is not under Williamson Act contract, nor is it currently used for agricultural purposes. Conflict with existing zoning for, or cause  $\boxtimes$ rezoning of, forest, land (as defined in Public

Less Than Significant with Mitigation Incorporated **Attachment 9** Impact

Significant Impact

Resources Code section 12220(g)), timberland (as defined by Public Re

construction phase air quality significance thresholds.

	Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 5114(g))?					
	Discussion: There are no forest land or timberla	and resources w	ithin the City of F	Paso Robles.		
d.	Result in the loss of forest land or conversion of forest land to non-forest use?					
	Discussion: The City of Paso Robles does not c proposed for removal, however the trees are sca				plings are	
e.	Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?					
	Discussion: The site is located within the city project will have no impact on conversion of fa		Robles and surrou	unded by urbaniz	zed uses. The	
ma	AIR QUALITY: Where available, the signific nagement or air pollution control district may be ject:					
a.	Conflict with or obstruct implementation of the applicable air quality plan?					
b.	Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard?					
c.	Expose sensitive receptors to substantial pollutant concentrations?		$\boxtimes$			
	Discussion (a-c): The San Luis Obispo County area is a non-attainment area for the state standards for ozone and suspended particulate matter <sup>9</sup> . The potential for future project development to create adverse air quality impacts falls generally into two categories: short-term (construction-related) and long-term (operational) impacts. The SLO County Air Pollution Control District (APCD) provides guidance for calculating air quality impacts.					
	Projects that do not exceed operational threshol	ds are unlikely	to exceed constru	ction thresholds	as well.	
	The project is the construction of approximately analysis was completed for the project (Attachmexpected to generate an average of 7.86 pounds particulate matter and 0.23 pounds per day of further project is 137 pounds or more of ROG + NO <sub>2</sub> day	ment 3), which is per day of ROugitive dust. Pr	found, during cons G and NOx, 0.23 ojects have a sign	struction, the propounds per day of ificant impact if	oject is of diesel they	

Less Than Significant with Mitigation Incorporated **Significant** 

**Impact Impact** 

#### **Construction Emissions**

Pollutant	Project Average Max	Project Summer Max	Significance Threshold	Significance Determination
$ROG + NO_x$	7.86 lb/day	80.2 lb/day	137 lb/day	Less than significant
Diesel PM	0.23 lb/day	1.81 lb/day	7 lb/day	Less than significant
Fugitive Dust PM <sub>10</sub>	0.23 lb/day	2.76 lb/day (0.5T/quarter)	2.5 T/quarter	Less than significant

The site is approximately 300 feet from the closest residences in the Rancho Paso Mobile Home Park, which are sensitive receptors. Air Quality impacts to sensitive receptors are less than significant with San Luis Obispo Air Pollution Control District standard mitigation measures (AQ-1 through AQ-26) implemented.

**Operations Emissions** 

Pollutant	Project Average	Project Summer Max	Significance Threshold	Significance Determination
$ROG + NO_x$	1.21 lb/day	2.14 lb/day		Less than significant
Diesel PM	0.23	1.81 lb/day	25 lb/day	Less than significant
Fugitive Dust PM <sub>10</sub>	0.01 lb/day	0.01 lb/day		Less than significant

	Operational emissions will have a less than sig	gnificant impact.						
d.	Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?							
	Discussion: According to the SLOAPCD, land uses commonly considered to be potential sources of noxion odorous emissions include painting/coating operations. Mitigation Measure HAZ-1 would prohibit vehicle fursales and painting of vehicles, which would reduce the impact to less than significant.							
IV.	IV. BIOLOGICAL RESOURCES: Would the project:							

a.	Have a substantial adverse effect, either
	directly or through habitat modifications, on
	any species identified as a candidate,
	sensitive, or special status species in local or
	regional plans, policies, or regulations, or by
	the California Department of Fish and Game
	or U.S. Fish and Wildlife Service?

Discussion: The site is disturbed. A manufactured home sales business previously occupied approximately 1.7 acres at the corner with Nutwood Circle. A fenced stormwater basin is located at the northwest corner of the lot. Several soil stockpiles are scattered on the site. Urban uses ring the site except the lots immediately west and northwest of the site, which are undeveloped. Highway 101 is to the east of the property.

 $\boxtimes$ 

A biological resources assessment report was prepared for the project (Attachment 4). No sensitive vegetative communities or designated critical habitats are located on the site. No special status botanical species were

Less Than Significant with Mitigation Incorporated **Attachment 9** 

Significant Impact Impact

observed during a site survey, which occurred in March, which is part of the typical blooming period for potentially occurring species in the region. Three special-status wildlife species have the potential to occur on the site, however none were observed during an onsite survey. Mitigation measures are provided to reduce potential impacts to the northern legless lizard, American badger, and San Joaquin kit fox. Similarly, mitigation measures are provided to protect nesting birds that may be impacted if construction begins between February 1 and August 31.

	•				
b.	Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or US Fish and Wildlife Service?				
	Discussion: There are no riparian or sensitive proposed for removal with the project. Oak tree inches in diameter.				
c.	Have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?				
	Discussion: There are no wetlands on the site.				
d.	Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?  Discussion: There are no creeks or drainages lead	ading to creek	s on the site. The s	□ site is in an urba	⊠ nized area.
e.	Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?				
	Discussion: The project protects the 3 mature o removal, one of which is larger than 6 inches in				
f.	Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?				$\boxtimes$

**Less Than** Significant with Mitigation Incorporated **Attachment 9** Significant

**Impact Impact** 

Discussion: There are no conservation plans adopted for the City of Paso Robles, therefore no impact is expected.

V. (	CULTURAL RESOURCES: Would the project:						
a.	Cause a substantial adverse change in the significance of a historical resource as defined in §15064.5?						
	Discussion (a): The site is undeveloped. No historical resources were identified during an onsite survey of the site conducted in support of the preparation of a cultural resources inventory survey for the site (Attachment 5).						
b.	Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?						
	Discussion (b): No archeological resources have been identified on the site. Mitigation measure CUL-1 would require work to stop should any cultural resources or human remains be identified on the site during construction.						
c.	Disturb any human remains, including those interred outside of formal cemeteries?		$\boxtimes$				
	Discussion (c): No archeological resources have been identified on the site. Mitigation measure CUL-1 would require work to stop should any cultural resources or human remains be identified on the site during construction.						
VI.	ENERGY: Would the project:						
a.	Result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during project construction or operation?						
	Discussion (a): The project would use typical construction techniques and vehicle repair equipment. No wasteful consumption of energy is proposed.						
b.	Conflict with or obstruct a state or local plan for renewable energy or energy efficiency?				$\boxtimes$		
	Discussion (b): The proposed project will not conflict with any adopted plan for renewable energy or energy efficiency.						

#### VII. GEOLOGY AND SOILS: Would the project:

a. Directly or indirectly cause potential

**Less Than** Significant with Mitigation Incorporated Attachment 9
Significant Impact Impact

		mcorporated			
substantial adverse effects, including the risk of loss, injury, or death involving:					
i. Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.					
Discussion: The potential for and mitigation are identified and addressed in the EIR for th fault zones, one on each side of the Salinas R the valley, and grazes the City on its western The San Andreas Fault is on the east side of the City of Paso Robles recognizes these geo to all new development within the City include Fault Zones within City limits.	e 2003 update of t iver Valley. The l boundary, but ha he valley and is si blogic influences i	he General Plan <sup>1</sup> . Rinconada Fault s s been inactive fo tuated about 23 n n the application	There are two k ystem runs on the r approximately niles northeast of of the Uniform B	nown nearby e west side of 11,000 years. Paso Robles. uilding Code	
ii. Strong seismic ground shaking?				$\boxtimes$	
Discussion: The 2003 General Plan EIR identified impacts resulting from ground shaking as less than significant and provided mitigation measures that will be incorporated into the design of all construction projects including adequate structural design over active or potentially active faults. Therefore, there are no expected impacts from seismic ground shaking.					
iii. Seismic-related ground failure, including liquefaction?		$\boxtimes$			
Discussion: The General Plan Safety Elemer classifies the site as high risk. Mitigation M will address specific onsite liquefaction risks	easure GEO-1 wo	ould require a soil	s report for the p		
iv. Landslides?				$\boxtimes$	
Discussion: The General Plan Safety Eleme site has low potential for landslides. Landslid geologic formations not found in proximity to	des are generally a	associated with st	eep slopes and sp	ecific	
Result in substantial soil erosion or the loss of topsoil?					
Discussion: The site is flat with loamy soil. Resources Conservation Service (NRCS) ind erodible 10. Mitigation Measure GEO-2 would designed by a Qualified SWPPP Developer to	icates the site's so d require a Storm	oil is Lockwood sl water Pollution Pr	haly loam, which revention Plan (S	is highly	
Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in					

b.

c.

Less Than
Significant
with
Mitigation
Incorporated

Attachment 9
Significant Impact

Significant Imp
Impact

on- or off-site landslide, lateral spreading, subsidence, liquefaction or collapse? Discussion: See response to items a.iii. and a.iv. above. Mitigation Measures GEO-1 would reduce the impact to less than significant. d. Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code  $\boxtimes$  $\Box$ (1994), creating substantial risks to life or property? Discussion: The Paso Robles Area San Luis Obispo County Soil Survey indicates the Lockwood shaly loam has moderate shrink swell potential. Mitigation Measure GEO-1 would reduce the potential impact to less than significant. Have soils incapable of adequately supporting the use of septic tanks or  $\boxtimes$ alternative waste water disposal systems where sewers are not available for the disposal of waste water? Discussion: The project is required to connect to the City sewer. A 10-inch sewer main is located in Theatre Drive, and is available to the project. Directly or indirectly destroy a unique  $\boxtimes$ paleontological resource or site or unique geologic feature? Discussion: No known paleontological resources or unique geological features are known to exist on the site. No impacts are expected. VIII. GREENHOUSE GAS EMISSIONS: Would the project: Generate greenhouse gas emissions, either  $\boxtimes$ directly or indirectly, that may have a significant impact on the environment? b. Conflict with any applicable plan, policy, or regulation of an agency adopted for the  $\boxtimes$ purpose of reducing the emissions of greenhouse gasses? Discussion: San Luis Obispo Air Pollution Control District Screening Criteria for Project Air Quality Analysis<sup>9</sup>, updated in 2017 indicates Light Industrial uses less than 92,000 square feet in size is not expected to exceed the Greenhouse Gas Numerical Threshold of 1150 MT/year of CO<sub>2</sub>, which was used to meet statewide emission standards required by 2020. Senate Bill 32, adopted in 2016, requires a further 40%

The 2030 Greenhouse Gas Efficient Threshold for Paso Robles is 1.9 MTCO<sub>2e</sub>/Service Population/year (2030 Service Population is estimated at 53,717). Results from the CalEEMod analysis indicate the construction

project will generate 5,929 lb Co<sub>2</sub>/day during construction and 3,782 lb CO<sub>2</sub>/day during operation.

reduction in Greenhouse Gas Emissions by 2030. A 40% reduction in the threshold for CO<sub>2</sub> emissions would imply a 55,200 square-foot or smaller Light Industry use would not exceed the lower threshold. The project is 25,000 square feet of light industrial use. Results from the CalEEMod analysis for the project indicate the

Less Than Significant with Mitigation Incorporated Attachment 9
Significant Impact

Significant I Impact

phase of the project will generate 315 MTCO<sub>2e</sub>. Amortized over 25 years, the construction emissions are 12.6 MTCO<sub>2e</sub>/year. Operational emissions (including the amortized construction emissions) are 638.6 MTCO<sub>2e</sub>/year, or 16.8 MTCO<sub>2e</sub>/SP/year (38 employees estimated by CCTC Transportation Analysis).

Qualitatively, the project is consistent with the following goals and policies of the San Luis Obispo APCD Climate Transportation and Land Use Control Measures:

- L-1 Planning Compact Communities. The project is located within city limits.
- L-3 Balancing Jobs and Housing. The project will create jobs and help to balance the jobs/housing imbalance in northern San Luis Obispo County.
- L-4 Circulation Management and T-2B Regional Public Transit Improvements. The project is located on a regional transit route, RTA Route 9, which has connections to Paso Robles City transit services.
- T-3 Bicycling and Bikeway Enhancements. The project will construct a bike lane along the Theatre Drive frontage.

Mitigation Measure GHG-1 will reduce the impact to less than significant. T

IX.	X. HAZARDS AND HAZARDOUS MATERIALS: Would the project:							
a.	Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?		$\boxtimes$					
	Discussion (a): The proposed project is a semi-truck routine handling of relatively small amounts of haza degreasing solvents, tires, and waste batteries. The enforced by the San Luis Obispo County Department would prevent the project from operating as a service would require the applicant to apply to the SLO Con appropriate for vehicle repair services. These mitigless than significant impact.	ardous materials in handling of these not of Environment are station dispensionally anty Department	ncluding diesel f materials is subj tal Health. Mitig- ing fuel. Mitigat of Environmenta	uel, engine oil, ect to regulation ation Measure Haion Measure Haion Health for per	ns HAZ-1 AZ-2 mits			
b.	Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?							
	Discussion (b): Vehicle repair services have some Mitigation Measure HAZ-1 would prohibit fuel sale significant potential accident hazards. Measure HA County Environmental Health rules, which reduces	es and painting ve Z-2 would requir	hicles, which wo	ould eliminate so omply with SLO	C			
c.	Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?							
	Discussion (a.g.). The project is not within a querte	r mile of any ash	ol The manuact	aahaal ia Tampi	latan			

Discussion (a-c): The project is not within a quarter mile of any school. The nearest school is Templeton Hills Adventist School located approximately 2 miles southwest of the project.

Less Than **Significant** with Mitigation

Attachment 9 **Significant Impact** 

**Impact Incorporated** d. Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section  $\Box$  $\boxtimes$ 65962.5 and, as a result, would it create a significant hazard to the public or the environment? Discussion (d) The proposed project is not listed on the Cortese List compiled by the California Department of Toxic Substances Control<sup>17</sup>. e. For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport  $\boxtimes$ or public use airport, would the project result in a safety hazard or excessive noise for people residing or working in the project area? Discussion (e): The project site is not within the Airport Land Use Plan area. No impact is anticipated. f. Impair implementation of or physically interfere with an adopted emergency  $\boxtimes$ response plan or emergency evacuation plan? Discussion: The City of Paso Robles maintains a Multi-Hazard Emergency Response Plan, most recently updated in 2019. The project is on private land adjacent to an arterial road. The project would not interfere with the plan or impede emergency evacuation. Expose people or structures, either directly  $\boxtimes$ or indirectly, to a significant risk of loss, injury or death involving wildland fires? Discussion: The city does not contain any very-high fire severity zones. The site is in an urbanized area and not adjacent to wildlands. The project would not create a significant impact. X. HYDROLOGY AND WATER QUALITY: Would the project: Violate any water quality standards or waste discharge requirements or otherwise  $\boxtimes$ substantially degrade surface or ground water quality? Discussion: The is subject to stormwater management requirements both during construction and operation. The project will not impact water quality or significantly increase industrial waste discharged to the city sewer. b. Substantially decrease groundwater supplies

or interfere substantially with groundwater recharge such that the project may impede

 $\boxtimes$ 

Less Than
Significant
with
Mitigation
Incorporated

**Attachment 9** 

Significant Impact Impact

sustainable groundwater management of the basin?

Discussion: The project site is within city limits and is currently zoned to allow for highway-oriented commercial uses.

The project is consistent with the 2016 Urban Water Management Plan (UWMP)<sup>5</sup>, which anticipates and plans for buildout of the City. Since the UWMP has accounted for land uses at the project site, the project will have adequate water supply available, and will not further deplete or significantly affect, change or increase water demands planned for use in the basin. The site is not suitable for significant groundwater recharge.

The impact of the project would be less than significant.

c.	Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:				$\boxtimes$		
	<ul> <li>result in a substantial erosion or siltation on- or off-site;</li> </ul>						
	ii) substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or offsite;						
	iii) create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff; or						
	iv) impede or redirect flood flows?						
	Discussion: The site is very flat with no significar and divert runoff from new impervious surfaces to would require a SWPPP be prepared for the project	a stormwater det	tention basin. Mi	tigation Measur			
d.	In flood hazard, tsunami, or seiche zones, risk release of pollutants due to project inundation?						
	Discussion: The project site is outside all local flo The risk of flood is less than significant.	odplains. The sit	te is about 80 feet	above the Salin	nas River.		
e.	Conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan						
	Discussion: The 2011 Central Coast Basin Water Quality Control Plan adopted by the Central Coast Regional Water Quality Control Board <sup>15</sup> provides water quality regulations in the region through controls						

Discussion: The 2011 Central Coast Basin Water Quality Control Plan adopted by the Central Coast Regional Water Quality Control Board<sup>15</sup> provides water quality regulations in the region through controls including waste discharge restrictions and stormwater management. Industrial waste discharges from the project will be managed through the City's Industrial Waste program. The City's Urban Water Master Plan<sup>5</sup> is designed to serve all uses anticipated at full buildout. The City is a Groundwater Sustainability Agency for a portion of the Paso Robles Sub-Basin of the Salinas Basin. The commercial uses proposed by the project are

Less Than Significant with Mitigation Incorporated Attachment 9

Significant Impact Impact

consistent with the Paso Robles Subbasin Groundwater Sustainability Plan<sup>18</sup>. The project does not conflict with the applicable water quality control plan not the sustainable groundwater management plan; impacts would be less than significant.

XI.	LAND USE AND PLANNING: Would the project	ct:			
a.	Physically divide an established community?				$\boxtimes$
	Discussion: The project is a commercial developm Separate neighborhoods are located to the west and physically divided				
b.	Cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect?				
	Discussion: The project is a highway-oriented comdistrict (C-2). As mitigated, the project is not in cadopted for the purpose of avoiding or mitigating a Plan <sup>8</sup> (see discussion in Aesthetics section above), Action Plan.	onflict wit an environ	h any land use plan, j mental effect includir	policy, or regul	ation bles Gateway
XII	. MINERAL RESOURCES: Would the project:				
a.	Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?				
b.	Result in the loss of availability of a locally- important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?				
	Discussion (a-b): No mineral resources are known	to occur	on the site.		
		_		_	_
3777	A NOVED WE THAT I I I I I				
	I. NOISE: Would the project result in:				
a.	Exposure of persons to or generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?				
	Discussion: An Environmental Noise Assessment vinitigation, truck circulation and service departmental lowed by Noise Ordinance <sup>1,4</sup> standards. Mitigati	ıt equipme	nt noise would excee	d the noise exp	oosure

N-2 would require service doors to be closed in service bays facing south and west when air hammers are in

Less Than Significant with Mitigation Incorporated Attachment 9
Significant Impact

Significant Impact

use, and Measure N-3 would prohibit use of air hammers and hydraulic lifts outside the building.

Public address (PA) systems are common to vehicle repair uses; however, the project description does state whether a PA system is proposed. Mitigation Measure N-4 would require any PA system proposed in the future to be designed to meet noise limitations.

As mitigated, the project is not expected to create noise beyond what is permitted by the City Noise Element and Noise Ordinance so the impact would be less than significant. b. Generation of excessive groundborne  $\boxtimes$ vibration or groundborne noise levels? Discussion: Groundborne noise and vibration is expected only during construction of the project, however it will be short-lived and only during allowed construction hours (7am and 7pm, Monday-Saturday). The expected impact is less than significant. c. For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, П  $\bowtie$ within two miles of a public airport or public use airport, would the project expose people residing or working in the project area to excessive noise levels? Discussion: The project site is not within the Airport Land Use Plan area. No significant noise impact from the airport is expected. XIV. POPULATION AND HOUSING: Would the project: a. Induce substantial population growth in an area, either directly (for example, by  $\boxtimes$ proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)? b. Displace substantial numbers of existing  $\boxtimes$ housing, necessitating the construction of replacement housing elsewhere? Discussion (a-b): The project is on an infill site near the southern boundary of the City. Sewer is currently available to the site, however City water service will be extended to serve the project. Water service is currently available to adjacent residential neighborhoods outside the City from the Walnut Hills Mutual Water Company and Templeton Community Services District. City services are not available outside the City and due to current availability of water in the existing developments located in the County, the extension of the water main will not induce population growth. The project will not displace any existing housing. XV. PUBLIC SERVICES: Would the project:  $\boxtimes$ Result in substantial adverse physical

#### Attachment 9 **Potentially** Less Than **Significant Significant Significant Impact Impact** with **Impact** Mitigation **Incorporated** impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times, or other performance objectives for any of the public services? Fire protection? Police protection? Schools? Parks? X Other public facilities? Discussion: The project is not expected to significant increase demands on the fire and police departments because it is a light industrial use. No significant increase in demand on school, parks and other public facilities is expected by commercial uses. The proposed project is subject to development impact fees and school fees, which address the incremental increase in demand on public services caused by the project. XVI. RECREATION Would the project increase the use of existing neighborhood and regional parks or $\boxtimes$ other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated? Does the project include recreational facilities or require the construction or $\boxtimes$ expansion of recreational facilities which might have an adverse physical effect on the environment? Discussion (a-b): The project is a light industrial / commercial project, which will not create a significant demand on existing parks. No new parks are proposed as a part of the project. XVII. TRANSPORTATION: Would the project: Conflict with a program, plan, ordinance or policy addressing the circulation system, $\boxtimes$ including transit, roadway, bicycle and pedestrian facilities?

Discussion: The project includes the widening of Theatre Drive, which is identified in the Circulation Plan plan as an undivided arterial. Widening will accommodate two travel lanes, bikes lanes and a center turn lane consistent with City standards.

		Potentially Significant Impact	Less Than Significant with Mitigation Incorporated	Atstach Significant Impact	Iment Impact
b.	Conflict or be inconsistent with CEQA Guidelines § 15064.3, subdivision (b)?				
	Discussion: A transportation analysis was con project will have a less than significant impact Transportation Impact Analysis Guidelines thr have a significant impact if the work VMT per on the SLOCOG Travel Demand Model, the p threshold of significance.	on vehicle miles esholds, which is employee excee	s traveled (VMT) ndicate, "Office a eds 85 percent of t	based on the City nd industrial pro the regional avera	y's 2022 lects may age". Based
c.	Substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?			$\boxtimes$	
	Discussion: The project is located on a straight restricted to on and off ramps, there are limited analysis states, "Collision data was obtained fr (SWITRS) for Templeton CHP and City police and 2021. One injury collision occurred near R No collisions occurred at or near Nutwood Cirrecommendations."  The project is expected to add 178 daily trips, which is a less than significant impact consister Guidelines.	d conflict points on the Statewid e on Theatre Drivanch Paso Road cle. There are not all in the peak m	on the street. The e Integrated Traff ve in the vicinity when a bicycle very observed collision orning hour and 4	e project transportic Records Syste of the project between traveling the on patterns and notes in the peak PM	tation m ween 2017 wrong way.
d.	Result in inadequate emergency access?				
	Discussion: The project has been reviewed by will not impede emergency access, and is designed to City emergency access standards.				
	VIII. TRIBAL CULTURAL RESOURCES				
a.	Would the project cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code § 21074 as either a site, feature, place, cultural landscape that is geographically defined in terms of the size and scope of the landscape, sacred place, or object with cultural value to a California Native American tribe, and that is:				
	i) Listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k), or				
	ii) A resource determined by the lead agency, in its discretion and supported by				

Less Than
Significant
with
Mitigation
Incorporated

Attachment 9
Significant Impact
Impact

substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code § 5024.1. In applying the criteria set forth in subdivision (c) of Public Resource Code § 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe.

Discussion: No Tribal Cultural Resources were identified during an onsite survey of the site, nor in archival research conducted in support of the preparation of a cultural resources inventory survey for the site (Attachment 5).

ΧIJ	K. UTILITIES AND SERVICE SYSTEMS: Woul	d the project:			
a.	Require or result in the relocation or construction of new or expanded water, wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?				
	Discussion: The project will have an incremental be Local planning for sewer and water utilities has ant commercial development on this site.				ties.
b.	Have sufficient water supplies available to serve the project and reasonably foreseeable future development during normal, dry and multiple dry years?			$\boxtimes$	
	Discussion: The project site is within the City lime. Local planning for water supplies for buildout of the proposed use is not a substantial user of water.				
	The City's municipal water supply is composed of allocation of the Salinas River underflow, and a suproject. The 2015 Urban Water Management Plan households and commercial users at build out. Water impacts to groundwater supplies are less than significant to the composition of t	urface water allocated (UWMP) <sup>5</sup> indicated the use for this pro	ation from the Nates there is adequ	acimiento Lake late capacity to	e pipeline serve all
c.	Result in a determination by the wastewater treatment provider, which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?				

Discussion: The project is not a significant water user or wastewater producer; no significant increase in

Less Than **Significant** with Mitigation Incorporated **Impact** 

Significant **Impact** 

wastewater production is expected. The City's Sewer System Management Plan (SSMP)<sup>6</sup> identifies system upgrades needed to accommodate buildout of the city. Development impact fees and sewer rates are adopted to address the proportionate share of impact of each development project on the sewer system.

d.	Generate solid waste in excess of state or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?				
	Discussion: The City's Landfill Master Plan <sup>21</sup> in projected waste generated within the city until a subject to diversion requirements for recyclable city's ability to attain solid waste reduction goal	at least 2051. E	Both construction ar	nd residential w	astes are
e.	Comply with federal, state, and local management and reduction statutes and regulations related to solid waste?				$\boxtimes$
	Discussion: The proposed project will be requireduction statutes and regulations.	red to comply	with federal, state, a	and local manag	gement and
	<b>A. WILDFIRE.</b> If located in or near state responserity zones, would the project:	ibility areas or	lands classified as	very high fire h	azard
a.	Substantially impair an adopted emergency response plan or emergency evacuation plan?				
b.	Due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose project occupants to pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?				
С.	Require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?				
d.	Expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?				$\boxtimes$
	Discussion: The project is not near a state respo	nsibility area o	or lands classified a	s verv high fire	hazard

Discussion: The project is not near a state responsibility area or lands classified as very high fire hazard severity zone. The site is near the boundary of the City, but is surrounded by urban uses.

Less Than
Significant
with
Mitigation
Incorporated

Attachment 9
Significant Impact

**Impact** 

#### XXI. MANDATORY FINDINGS OF SIGNIFICANCE

a.	Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?				
	Discussion: The project is located on an infill site established on adjacent properties to the north. T migration corridor. The site does not contain sign	he site does	not support signifi	cant habitat or co	ontribute a
b.	Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?				
	Discussion: The project is located within the City significant impacts to the environment. The project that would have a significant impact.				
c.	Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?			$\boxtimes$	
	Discussion: While vehicle repair does include the will have a less than significant impact on human		of some hazardous	substances, with	n mitigation it

#### EARLIER ANALYSIS AND BACKGROUND MATERIALS.

Earlier analyses may be used where, pursuant to tiering, program EIR, or other CEQA process, one or more effects have been adequately analyzed in an earlier EIR or negative declaration. Section 15063 (c)(3)(D).

Documents utilized in this analysis and background / explanatory materials:

Reference #	<b>Document Title</b>	Available for Review at:
1	City of Paso Robles General Plan	City of Paso Robles Community Development Department 1000 Spring Street Paso Robles, CA 93446
		https://www.prcity.com/313/Gen eral-Plan
2	City of Paso Robles Environmental Impact Report for General Plan Update	City of Paso Robles
3	2007 Airport Land Use Plan	https://www.prcity.com/354/Air port-Land-Use-Plan
4	City of Paso Robles Municipal Code	https://library.municode.com/ca/ el_paso_de_robles/codes/code_o f_ordinances
5	City of Paso Robles Urban Water Management Plan 2016	City of Paso Robles
		https://www.prcity.com/Docume ntCenter/View/14827/Urban- Water-Management-Plan-PDF
6	City of Paso Robles Sewer System Management Plan	City of Paso Robles
		https://www.prcity.com/Docume ntCenter/View/15356/Sewer- System-Management-Plan- PDF?bidId=
7	City of Paso Robles Standard Conditions of Approval for New Development	City of Paso Robles
8	City of Paso Robles Gateway Plan: Design Standards, 2008	https://www.prcity.com/Docume ntCenter/View/14730/Gateway- Plan-Design-Standards- PDF?bidId=
9	San Luis Obispo County Air Pollution Control District Guidelines for Impact Thresholds	https://www.slocleanair.org/rule s-regulations/land-use-ceqa.php
10	USDA, Natural Resources Conservation Service,	NRCS Offices

	Soil Survey of San Luis Obispo County, Paso Robles Area, 1983	Templeton, CA 93446 https://websoilsurvey.nrcs.usda.g ov/app/WebSoilSurvey.aspx
11	Regional Transportation Plan, San Luis Obispo Council of Governments, 2019	https://slocog.org/2019RTP
12	Farmland Mapping and Monitoring Program California Resources Agency	https://www.conservation.ca.gov /dlrp/fmmp
13	Siting, Design, Operation and Maintenance of Onsite Wastewater Treatments Systems (OWTS) Policy California Water Boards	https://www.waterboards.ca.gov/ water_issues/programs/owts/
14	Underground Storage Tank Program California Water Boards	https://www.waterboards.ca.gov/ water_issues/programs/ust/
15	Water Quality Control Plan for the Central Coast Basin Central Coast Regional Water Quality Control Board	https://www.waterboards.ca.gov/centralcoast/publications_forms/publications/basin_plan/#:~:text = The%20Water%20Quality%20Control%20Plan,including%20surface%20waters%20and%20groundwater.
16	Post-Construction Stormwater Management Requirements for Development Projects in the Central Coast Central Coast Regional Water Quality Control Board	https://www.waterboards.ca.gov/ centralcoast/water_issues/progra ms/stormwater/docs/lid/lid_hydr omod_charette_index.html
17	Cortese List California Department of Toxic Substance Control	https://www.envirostor.dtsc.ca.g ov/public/map/
18	Paso Robles Groundwater Basin Management Plan City of Paso Robles	https://www.prcity.com/Docume ntCenter/View/15348/Groundwa ter-Basin-Management-Plan- PDF?bidId=
19	Purple Belt Plan City of Paso Robles	https://www.prcity.com/Docume ntCenter/View/31945/Purple- Belt-Plan-PDF
20	Busch, Lawrence L. and Miller, Russel V. 2011. Updated Mineral Land Classification Map for the Concrete-Grade Aggregates in the San Luis Obispo-Santa Barbara Production-Consumption Region, California – North Half.	
21	Master Plan of Sustainable Opportunities at the Paso Robles  Landfill  City of Paso Robles	https://www.prcity.com/Docume ntCenter/View/15350/Landfill- Master-Plan-PDF?bidId=

#### **Attachments:**

- 1. Vicinity Map
- 2. Project Plans
- 3. CalEEmod Report
- 4. Biological Resources Assessment Report
- 5. Cultural Resources Inventory Survey
- 6. Transportation Analysis
- 7. Environmental Noise Assessment
- 8. Mitigation Monitoring and Reporting Plan

# Attachment 9 Attachment 1 Vicinity Map





### Peterbilt v2 Detailed Report

#### **Table of Contents**

- 1. Basic Project Information
  - 1.1. Basic Project Information
  - 1.2. Land Use Types
  - 1.3. User-Selected Emission Reduction Measures by Emissions Sector
- 2. Emissions Summary
  - 2.1. Construction Emissions Compared Against Thresholds
  - 2.2. Construction Emissions by Year, Unmitigated
  - 2.3. Construction Emissions by Year, Mitigated
  - 2.4. Operations Emissions Compared Against Thresholds
  - 2.5. Operations Emissions by Sector, Unmitigated
  - 2.6. Operations Emissions by Sector, Mitigated
- 3. Construction Emissions Details
  - 3.1. Site Preparation (2023) Unmitigated
  - 3.2. Site Preparation (2023) Mitigated

### Peterbil V2 Detailed Report 1/19/2022

- 3.3. Grading (2023) Unmitigated
- 3.4. Grading (2023) Mitigated
- 3.5. Building Construction (2023) Unmitigated
- 3.6. Building Construction (2023) Mitigated
- 3.7. Building Construction (2024) Unmitigated
- 3.8. Building Construction (2024) Mitigated
- 3.9. Paving (2024) Unmitigated
- 3.10. Paving (2024) Mitigated
- 3.11. Architectural Coating (2024) Unmitigated
- 3.12. Architectural Coating (2024) Mitigated
- 4. Operations Emissions Details
  - 4.1. Mobile Emissions by Land Use
    - 4.1.1. Unmitigated
    - 4.1.2. Mitigated
  - 4.2. Energy
    - 4.2.1. Electricity Emissions By Land Use Unmitigated
    - 4.2.2. Electricity Emissions By Land Use Mitigated

### Peterbil Attachment 9/2022

- 4.2.3. Natural Gas Emissions By Land Use Unmitigated
- 4.2.4. Natural Gas Emissions By Land Use Mitigated
- 4.3. Area Emissions by Source
  - 4.3.2. Unmitigated
  - 4.3.1. Mitigated
- 4.4. Water Emissions by Land Use
  - 4.4.2. Unmitigated
  - 4.4.1. Mitigated
- 4.5. Waste Emissions by Land Use
  - 4.5.2. Unmitigated
  - 4.5.1. Mitigated
- 4.6. Refrigerant Emissions by Land Use
  - 4.6.1. Unmitigated
  - 4.6.2. Mitigated
- 4.7. Offroad Emissions By Equipment Type
  - 4.7.1. Unmitigated
  - 4.7.2. Mitigated

### Peterbia v2-Detailed Report 1/19/2022

- 4.8. Stationary Emissions By Equipment Type
  - 4.8.1. Unmitigated
  - 4.8.2. Mitigated
- 4.9. User Defined Emissions By Equipment Type
  - 4.9.1. Unmitigated
  - 4.9.2. Mitigated
- 4.10. Soil Carbon Accumulation By Vegetation Type
  - 4.10.1. Soil Carbon Accumulation By Vegetation Type Unmitigated
  - 4.10.2. Above and Belowground Carbon Accumulation by Land Use Type Unmitigated
  - 4.10.3. Avoided and Sequestered Emissions by Species Unmitigated
  - 4.10.4. Soil Carbon Accumulation By Vegetation Type Mitigated
  - 4.10.5. Above and Belowground Carbon Accumulation by Land Use Type Mitigated
  - 4.10.6. Avoided and Sequestered Emissions by Species Mitigated
- 5. Activity Data
  - 5.1. Construction Schedule
  - 5.2. Off-Road Equipment
    - 5.2.1. Unmitigated

### Peterbil Attachment 9/2022

- 5.2.2. Mitigated
- 5.3. Construction Vehicles
  - 5.3.1. Unmitigated
  - 5.3.2. Mitigated
- 5.4. Vehicles
  - 5.4.1. Construction Vehicle Control Strategies
- 5.5. Architectural Coatings
- 5.6. Dust Mitigation
  - 5.6.1. Construction Earthmoving Activities
  - 5.6.2. Construction Earthmoving Control Strategies
- 5.7. Construction Paving
- 5.8. Construction Electricity Consumption and Emissions Factors
- 5.9. Operational Mobile Sources
  - 5.9.1. Unmitigated
  - 5.9.2. Mitigated
- 5.10. Operational Area Sources
  - 5.10.1. Hearths

### Peterbia v2-Detailed Report 1/19/2022

- 5.10.1.1. Unmitigated
- 5.10.1.2. Mitigated
- 5.10.2. Architectural Coatings
- 5.10.3. Landscape Equipment
- 5.10.4. Landscape Equipment Mitigated
- 5.11. Operational Energy Consumption
  - 5.11.1. Unmitigated
  - 5.11.2. Mitigated
- 5.12. Operational Water and Wastewater Consumption
  - 5.12.1. Unmitigated
  - 5.12.2. Mitigated
- 5.13. Operational Waste Generation
  - 5.13.1. Unmitigated
  - 5.13.2. Mitigated
- 5.14. Operational Refrigeration and Air Conditioning Equipment
  - 5.14.1. Unmitigated
  - 5.14.2. Mitigated

### Peterbil V2 Detailed Report 1/19/2022

- 5.15. Operational Off-Road Equipment
  - 5.15.1. Unmitigated
  - 5.15.2. Mitigated
- 5.16. Stationary Sources
  - 5.16.1. Emergency Generators and Fire Pumps
  - 5.16.2. Process Boilers
- 5.17. User Defined
- 5.18. Vegetation
  - 5.18.1. Land Use Change
    - 5.18.1.1. Unmitigated
    - 5.18.1.2. Mitigated
  - 5.18.1. Biomass Cover Type
    - 5.18.1.1. Unmitigated
    - 5.18.1.2. Mitigated
  - 5.18.2. Sequestration
    - 5.18.2.1. Unmitigated
    - 5.18.2.2. Mitigated

### Peterbil Attachment 9/2022

- 6. Climate Risk Detailed Report
  - 6.1. Climate Risk Summary
  - 6.2. Initial Climate Risk Scores
  - 6.3. Adjusted Climate Risk Scores
  - 6.4. Climate Risk Reduction Measures
    - 6.4.1. Wildfire
    - 6.4.2. Drought
- 7. Health and Equity Details
  - 7.1. CalEnviroScreen 4.0 Scores
  - 7.2. Healthy Places Index Scores
  - 7.3. Overall Health & Equity Scores
  - 7.4. Health & Equity Measures
  - 7.5. Evaluation Scorecard
- 8. User Changes to Default Data

### 1. Basic Project Information

#### 1.1. Basic Project Information

Data Field	Value
Project Name	Peterbilt v2
Lead Agency	_
Land Use Scale	Project/site
Analysis Level for Defaults	County
Windspeed (m/s)	3.00
Precipitation (days)	15.6
Location	35.57808909727966, -120.69854418153587
County	San Luis Obispo
City	Paso Robles
Air District	San Luis Obispo County APCD
Air Basin	South Central Coast
TAZ	3309
EDFZ	6
Electric Utility	Pacific Gas & Electric Company
Gas Utility	Southern California Gas

#### 1.2. Land Use Types

Land Use Subtype	Size	Unit	Lot Acreage	Building Area (sq ft)	Landscape Area (sq ft)	Special Landscape Area (sq ft)	Population	Description
General Light Industry	11.0	1000sqft	0.25	11,000	40,394	_	_	Truck service
Automobile Care Center	14.0	1000sqft	0.32	14,000	1.00	_	_	Sales

### Peterbil V2 Detailed Report 9/19/2022

Parking Lot	3.00	Acre	3.00	0.00	1.00	_	_	Parking
· ·								· ·

#### 1.3. User-Selected Emission Reduction Measures by Emissions Sector

Sector	#	Measure Title
Construction	C-2*	Limit Heavy-Duty Diesel Vehicle Idling
Construction	C-10-A	Water Exposed Surfaces
Construction	C-10-C	Water Unpaved Construction Roads
Construction	C-11	Limit Vehicle Speeds on Unpaved Roads
Construction	C-12	Sweep Paved Roads
Transportation	T-33*	Locate Project near Bike Path/Bike Lane
Water	W-5	Design Water-Efficient Landscapes
Natural	N-2	Expand Urban Tree Planting

<sup>\*</sup> Qualitative or supporting measure. Emission reductions not included in the mitigated emissions results.

#### 2. Emissions Summary

#### 2.1. Construction Emissions Compared Against Thresholds

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

		(112)	.,	ily, tolliyi					J,	J	,							
Un/Mit.	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	4.78	40.4	39.8	36.1	0.06	1.81	2.76	3.75	1.66	0.51	1.68	_	5,778	5,778	0.27	0.47	5.62	5,929
Mit.	4.78	40.4	39.8	36.1	0.06	1.81	2.76	3.75	1.66	0.51	1.68	_	5,778	5,778	0.27	0.47	5.62	5,929
% Reduced	_	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

	4.50	4.00	40.0	40.0	0.00	0.55	0.00	0.00	0.54	0.00	0.50		0.540	0.540	0.40	0.04	0.04	0.504
Unmit.	1.56	1.30	12.0	13.6	0.02	0.55	0.08	0.63	0.51	0.02	0.53	_	2,548	2,548	0.10	0.04	0.01	2,561
Mit.	1.56	1.30	12.0	13.6	0.02	0.55	0.08	0.63	0.51	0.02	0.53	_	2,548	2,548	0.10	0.04	0.01	2,561
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.69	2.59	5.27	6.31	0.01	0.23	0.08	0.27	0.21	0.02	0.22	_	1,171	1,171	0.05	0.02	0.10	1,177
Mit.	0.69	2.59	5.27	6.31	0.01	0.23	0.08	0.27	0.21	0.02	0.22	_	1,171	1,171	0.05	0.02	0.10	1,177
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.13	0.47	0.96	1.15	< 0.005	0.04	0.01	0.05	0.04	< 0.005	0.04	_	194	194	0.01	< 0.005	0.02	195
Mit.	0.13	0.47	0.96	1.15	< 0.005	0.04	0.01	0.05	0.04	< 0.005	0.04	_	194	194	0.01	< 0.005	0.02	195
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

### 2.2. Construction Emissions by Year, Unmitigated

Year	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily - Summer (Max)	_	-	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	4.78	4.03	39.8	36.1	0.06	1.81	2.76	3.75	1.66	0.51	1.68	_	5,778	5,778	0.27	0.47	5.62	5,929
2024	1.49	40.4	11.4	13.5	0.02	0.50	0.11	0.57	0.46	0.03	0.48	_	2,548	2,548	0.10	0.04	0.55	2,562
Daily - Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	1.56	1.30	12.0	13.6	0.02	0.55	0.08	0.63	0.51	0.02	0.53	_	2,548	2,548	0.10	0.04	0.01	2,561
2024	1.49	1.24	11.4	13.5	0.02	0.50	0.08	0.57	0.46	0.02	0.48	_	2,546	2,546	0.10	0.04	0.01	2,559

Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	0.44	0.37	3.52	3.73	0.01	0.16	0.08	0.24	0.15	0.02	0.16	_	719	719	0.03	0.02	0.10	725
2024	0.69	2.59	5.27	6.31	0.01	0.23	0.04	0.27	0.21	0.01	0.22	_	1,171	1,171	0.05	0.02	0.10	1,177
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	0.08	0.07	0.64	0.68	< 0.005	0.03	0.01	0.04	0.03	< 0.005	0.03	_	119	119	< 0.005	< 0.005	0.02	120
2024	0.13	0.47	0.96	1.15	< 0.005	0.04	0.01	0.05	0.04	< 0.005	0.04	_	194	194	0.01	< 0.005	0.02	195

### 2.3. Construction Emissions by Year, Mitigated

			,	J, J					<b>,</b>									
Year	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily - Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	4.78	4.03	39.8	36.1	0.06	1.81	2.76	3.75	1.66	0.51	1.68	_	5,778	5,778	0.27	0.47	5.62	5,929
2024	1.49	40.4	11.4	13.5	0.02	0.50	0.11	0.57	0.46	0.03	0.48	_	2,548	2,548	0.10	0.04	0.55	2,562
Daily - Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	1.56	1.30	12.0	13.6	0.02	0.55	0.08	0.63	0.51	0.02	0.53	_	2,548	2,548	0.10	0.04	0.01	2,561
2024	1.49	1.24	11.4	13.5	0.02	0.50	0.08	0.57	0.46	0.02	0.48	_	2,546	2,546	0.10	0.04	0.01	2,559
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	0.44	0.37	3.52	3.73	0.01	0.16	0.08	0.24	0.15	0.02	0.16	_	719	719	0.03	0.02	0.10	725
2024	0.69	2.59	5.27	6.31	0.01	0.23	0.04	0.27	0.21	0.01	0.22	_	1,171	1,171	0.05	0.02	0.10	1,177
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2023	0.08	0.07	0.64	0.68	< 0.005	0.03	0.01	0.04	0.03	< 0.005	0.03	_	119	119	< 0.005	< 0.005	0.02	120
2024	0.13	0.47	0.96	1.15	< 0.005	0.04	0.01	0.05	0.04	< 0.005	0.04	_	194	194	0.01	< 0.005	0.02	195

## 2.4. Operations Emissions Compared Against Thresholds

Un/Mit.	TOG	ROG	NOx	CO	SO2	PM10E			PM2.5E			BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.98	1.68	0.46	2.76	< 0.005	_	_	_	_	_	_	43.6	_	_	4.51	0.04	2,905	_
Mit.	0.98	1.68	0.46	2.76	< 0.005	_	_	_	_	_	_	43.6	_	_	4.51	0.04	2,905	_
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.76	1.47	0.47	2.04	< 0.005	_	_	_	_	_	_	43.6	_	_	4.51	0.04	2,905	_
Mit.	0.76	1.47	0.47	2.04	< 0.005	_	_	_	_	_	_	43.6	_	_	4.51	0.04	2,905	_
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.21	0.92	0.29	1.22	< 0.005	_	_	_	_	_	_	43.6	_	_	4.46	0.03	2,905	_
Mit.	0.21	0.92	0.29	1.22	< 0.005	_	_	_	_	_	_	43.6	_	_	4.46	0.03	2,905	_
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.04	0.17	0.05	0.22	< 0.005	_	_	_	_	_	_	7.21	_	_	0.74	< 0.005	481	_
Mit.	0.04	0.17	0.05	0.22	< 0.005	_	_	_	_	_	_	7.21	_	_	0.74	< 0.005	481	_
% Reduced	_	_	_	_	_	_	_	_	_	_	_	_	_	_	< 0.5%	< 0.5%	_	_

### 2.5. Operations Emissions by Sector, Unmitigated

Sector	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.75	0.74	0.17	1.43	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	64.9	64.9	0.03	0.01	0.15	70.2
Area	0.19	0.92	0.01	1.09	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.47	4.47	< 0.005	< 0.005	_	4.49
Energy	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	759	759	0.10	0.01	_	764
Water	_	_	_	_	_	_	_	_	_	_	_	7.40	12.9	20.3	0.76	0.02	_	44.7
Waste	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.98	1.68	0.46	2.76	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	43.6	NaN	NaN	4.51	0.04	2,905	NaN
Daily, Winter (Max)	_		_			_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.73	0.71	0.19	1.81	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	64.6	64.6	0.04	0.02	< 0.005	70.4
Area	_	0.74	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-
Energy	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	759	759	0.10	0.01	_	764
Water	_	_	_	_	_	_	_	_	_	_	_	7.40	12.9	20.3	0.76	0.02	_	44.7
Waste	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.76	1.47	0.47	2.04	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	43.6	NaN	NaN	4.51	0.04	2,905	NaN
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Mobile	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Area	0.17	0.91	0.01	0.98	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.04	4.04	< 0.005	< 0.005	_	4.06
Energy	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	697	697	0.09	0.01	_	701
Water	_	_	_	_	_	_	_	_	_	_	_	7.40	12.9	20.3	0.76	0.02	_	44.7
Waste	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Vegetatio n	_	_	_	_	-	NaN	NaN	NaN	NaN	NaN	NaN	-	NaN	NaN	_	-	_	NaN
Total	0.21	0.92	0.29	1.22	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	43.6	NaN	NaN	4.46	0.03	2,905	NaN
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Area	0.03	0.17	< 0.005	0.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	0.67	0.67	< 0.005	< 0.005	_	0.67
Energy	0.01	< 0.005	0.05	0.04	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	115	115	0.01	< 0.005	_	116
Water	_	_	_	_	_	_	_	_	_	_	_	1.22	2.13	3.35	0.13	< 0.005	_	7.40
Waste	_	_	_	_	_	_	_	_	_	_	_	5.99	0.00	5.99	0.60	0.00	_	21.0
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	481	481
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.04	0.17	0.05	0.22	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	7.21	NaN	NaN	0.74	< 0.005	481	NaN

### 2.6. Operations Emissions by Sector, Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Sector	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	всо2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.75	0.74	0.17	1.43	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	64.9	64.9	0.03	0.01	0.15	70.2
Area	0.19	0.92	0.01	1.09	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.47	4.47	< 0.005	< 0.005	_	4.49
Energy	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	759	759	0.10	0.01	_	764

15 / 81

# Peterbi**Attachmen 1**/19/2022

Water	_	_			_	_	_	_	_	_	_	7.40	12.2	19.6	0.76	0.02	_	44.1
Waste	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.98	1.68	0.46	2.76	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	43.6	NaN	NaN	4.51	0.04	2,905	NaN
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.73	0.71	0.19	1.81	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	64.6	64.6	0.04	0.02	< 0.005	70.4
Area	_	0.74	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Energy	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	759	759	0.10	0.01	_	764
Water	_	_	_	_	_	_	_	_	_	_	_	7.40	12.2	19.6	0.76	0.02	_	44.1
Waste	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.76	1.47	0.47	2.04	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	43.6	NaN	NaN	4.51	0.04	2,905	NaN
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_	_
Mobile	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Area	0.17	0.91	0.01	0.98	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.04	4.04	< 0.005	< 0.005	_	4.06
Energy	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	697	697	0.09	0.01	_	701
Water	_	_	_	_	_	_	_	_	_	_	_	7.40	12.2	19.6	0.76	0.02	_	44.1
Waste	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.21	0.92	0.29	1.22	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	43.6	NaN	NaN	4.46	0.03	2,905	NaN
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Mobile	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Area	0.03	0.17	< 0.005	0.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	0.67	0.67	< 0.005	< 0.005	_	0.67
Energy	0.01	< 0.005	0.05	0.04	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	115	115	0.01	< 0.005	_	116
Water	_	_	_	_	_	_	_	_	_	_	_	1.22	2.02	3.25	0.13	< 0.005	_	7.30
Waste	_	_	_	_	_	_	_	_	_	_	_	5.99	0.00	5.99	0.60	0.00	_	21.0
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	481	481
Vegetatio n	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Total	0.04	0.17	0.05	0.22	< 0.005	NaN	NaN	NaN	NaN	NaN	NaN	7.21	NaN	NaN	0.74	< 0.005	481	NaN

### 3. Construction Emissions Details

#### 3.1. Site Preparation (2023) - Unmitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		3.95	39.7	35.5	0.05	1.81	_	1.81	1.66	_	1.66	_	5,295	5,295	0.21	0.04	_	5,314
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.05	0.54	0.49	< 0.005	0.02	_	0.02	0.02	_	0.02	_	72.5	72.5	< 0.005	< 0.005	_	72.8

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmer		0.01	0.10	0.09	< 0.005	< 0.005	_	< 0.005	< 0.005	-	< 0.005	-	12.0	12.0	< 0.005	< 0.005	-	12.1
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_
Worker	0.09	0.08	0.05	0.66	0.00	0.00	0.01	0.01	0.00	0.00	0.00	_	111	111	0.01	< 0.005	0.52	113
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_		_	_	_		_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	1.46	1.46	< 0.005	< 0.005	< 0.005	1.49
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.24	0.24	< 0.005	< 0.005	< 0.005	0.25
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.2. Site Preparation (2023) - Mitigated

		_ ` .	,	, ,														
Location	TOG	ROG	NOx	CO	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e

# Peterbi**Attachment** 9/2022

Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_		-	_	_	_	_	_	_	_		_	_	_	_	_	_	_
Off-Road Equipmen		3.95	39.7	35.5	0.05	1.81	_	1.81	1.66	_	1.66	_	5,295	5,295	0.21	0.04	_	5,314
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_		_	_	_	_	_	-	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.05	0.54	0.49	< 0.005	0.02	_	0.02	0.02	_	0.02	_	72.5	72.5	< 0.005	< 0.005	_	72.8
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.10	0.09	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	12.0	12.0	< 0.005	< 0.005	_	12.1
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.09	0.08	0.05	0.66	0.00	0.00	0.01	0.01	0.00	0.00	0.00	_	111	111	0.01	< 0.005	0.52	113
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_

## Peterbil V2 Detailed Report 9/19/2022

Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	1.46	1.46	< 0.005	< 0.005	< 0.005	1.49
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.24	0.24	< 0.005	< 0.005	< 0.005	0.25
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.3. Grading (2023) - Unmitigated

Location	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T		PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_		_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		2.04	20.0	19.7	0.03	0.94	_	0.94	0.87	_	0.87	_	2,958	2,958	0.12	0.02	_	2,968
Demolitio n	_	_	_	_	_	_	2.02	2.02	_	0.31	0.31	_	_	_	_	_	_	-
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_		_	_	_		_	_	_	_	_	_	_
Average Daily		_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.44	0.43	< 0.005	0.02	_	0.02	0.02	_	0.02	_	64.8	64.8	< 0.005	< 0.005	_	65.1

# Peterbi**Attachmen 1**/19/2022

Demolitio n	_	_	_	_	_	_	0.04	0.04	_	0.01	0.01	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.08	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	10.7	10.7	< 0.005	< 0.005	_	10.8
Demolitio n	_	_	_	_	_	_	0.01	0.01	_	< 0.005	< 0.005	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.07	0.07	0.05	0.56	0.00	0.00	0.01	0.01	0.00	0.00	0.00	_	94.8	94.8	0.01	< 0.005	0.44	96.6
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.21	0.05	4.01	1.30	0.03	0.05	0.17	0.22	0.05	0.06	0.11	_	2,726	2,726	0.14	0.44	5.18	2,865
Daily, Winter (Max)		_	_		_	_	_				_	_	_	_	_	_		_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	2.01	2.01	< 0.005	< 0.005	< 0.005	2.04
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	< 0.005	0.09	0.03	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	59.7	59.7	< 0.005	0.01	0.05	62.7
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.33	0.33	< 0.005	< 0.005	< 0.005	0.34
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	9.89	9.89	< 0.005	< 0.005	0.01	10.4

### 3.4. Grading (2023) - Mitigated

	TOG	ROG	NOx	co	SO2	PM10E	PM10D	PM10T		PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		2.04	20.0	19.7	0.03	0.94	_	0.94	0.87	_	0.87	_	2,958	2,958	0.12	0.02	_	2,968
Demolitio n	_	_	_	_	_	_	2.02	2.02	_	0.31	0.31	_	_	_		_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.44	0.43	< 0.005	0.02	_	0.02	0.02	_	0.02	_	64.8	64.8	< 0.005	< 0.005	_	65.1
Demolitio n	_	-	_	_	_	_	0.04	0.04	_	0.01	0.01	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_	_
Off-Road Equipmen		0.01	0.08	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	10.7	10.7	< 0.005	< 0.005	_	10.8
Demolitio n	_	_	_	_	_	_	0.01	0.01	_	< 0.005	< 0.005	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1_

Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.07	0.07	0.05	0.56	0.00	0.00	0.01	0.01	0.00	0.00	0.00	_	94.8	94.8	0.01	< 0.005	0.44	96.6
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.21	0.05	4.01	1.30	0.03	0.05	0.17	0.22	0.05	0.06	0.11	_	2,726	2,726	0.14	0.44	5.18	2,865
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	2.01	2.01	< 0.005	< 0.005	< 0.005	2.04
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	< 0.005	0.09	0.03	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	59.7	59.7	< 0.005	0.01	0.05	62.7
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.33	0.33	< 0.005	< 0.005	< 0.005	0.34
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	9.89	9.89	< 0.005	< 0.005	0.01	10.4

### 3.5. Building Construction (2023) - Unmitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.26	11.8	13.2	0.02	0.55		0.55	0.51	_	0.51	_	2,397	2,397	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

# Peterbi**Attachment** 9/2022

Daily, Winter (Max)	_	_			_				_		_	_	_	_	_	_	_	_
Off-Road Equipmen		1.26	11.8	13.2	0.02	0.55	_	0.55	0.51	_	0.51	_	2,397	2,397	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.26	2.40	2.68	< 0.005	0.11	_	0.11	0.10	_	0.10	_	488	488	0.02	< 0.005	_	490
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.05	0.44	0.49	< 0.005	0.02	-	0.02	0.02	_	0.02	-	80.8	80.8	< 0.005	< 0.005	-	81.1
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	-		_	_	_	_	_	_	_	-	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.34	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	57.5	57.5	< 0.005	< 0.005	0.27	58.6
Vendor	0.01	< 0.005	0.15	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	95.0	95.0	< 0.005	0.01	0.24	99.4
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.33	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	55.1	55.1	< 0.005	< 0.005	0.01	56.0
Vendor	0.01	< 0.005	0.15	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	95.0	95.0	< 0.005	0.01	0.01	99.2
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	-	_	_	_	-	-	_	_	-	_

Worker	0.01	0.01	0.01	0.07	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	11.3	11.3	< 0.005	< 0.005	0.02	11.5
Vendor	< 0.005	< 0.005	0.03	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	19.3	19.3	< 0.005	< 0.005	0.02	20.2
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	1.87	1.87	< 0.005	< 0.005	< 0.005	1.90
Vendor	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	3.20	3.20	< 0.005	< 0.005	< 0.005	3.35
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.6. Building Construction (2023) - Mitigated

Location	TOG	ROG	NOx	co	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.26	11.8	13.2	0.02	0.55	_	0.55	0.51	_	0.51	_	2,397	2,397	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-
Off-Road Equipmen		1.26	11.8	13.2	0.02	0.55	_	0.55	0.51	_	0.51	_	2,397	2,397	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.26	2.40	2.68	< 0.005	0.11	_	0.11	0.10	_	0.10	_	488	488	0.02	< 0.005	_	490

# Peterbi**Attachmen 1**/19/2022

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmer		0.05	0.44	0.49	< 0.005	0.02	_	0.02	0.02	_	0.02	_	80.8	80.8	< 0.005	< 0.005	_	81.1
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.34	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	57.5	57.5	< 0.005	< 0.005	0.27	58.6
Vendor	0.01	< 0.005	0.15	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	95.0	95.0	< 0.005	0.01	0.24	99.4
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.33	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	55.1	55.1	< 0.005	< 0.005	0.01	56.0
Vendor	0.01	< 0.005	0.15	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	95.0	95.0	< 0.005	0.01	0.01	99.2
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.01	0.01	0.01	0.07	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	11.3	11.3	< 0.005	< 0.005	0.02	11.5
Vendor	< 0.005	< 0.005	0.03	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	19.3	19.3	< 0.005	< 0.005	0.02	20.2
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	1.87	1.87	< 0.005	< 0.005	< 0.005	1.90
Vendor	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	3.20	3.20	< 0.005	< 0.005	< 0.005	3.35
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.7. Building Construction (2024) - Unmitigated

Officeria	· Onorca	1110 (10) 41	ay ioi ac	illy, toll/y	TOT GITTI	adij dila	01100 (	ibrady io	i dany, it	7117 yr 101	ariiraarj							
Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	-	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.52	4.81	5.62	0.01	0.21	_	0.21	0.20	_	0.20	_	1,028	1,028	0.04	0.01	_	1,031
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_
Off-Road Equipmen		0.09	0.88	1.03	< 0.005	0.04	_	0.04	0.04	_	0.04	_	170	170	0.01	< 0.005	_	171
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	<u> </u>	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.32	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	56.5	56.5	< 0.005	< 0.005	0.25	57.6
Vendor	0.01	< 0.005	0.14	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	93.7	93.7	< 0.005	0.01	0.24	98.1
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.31	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	54.2	54.2	< 0.005	< 0.005	0.01	55.0
Vendor	0.01	< 0.005	0.15	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	93.7	93.7	< 0.005	0.01	0.01	97.9
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.02	0.02	0.01	0.13	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	23.4	23.4	< 0.005	< 0.005	0.05	23.8
√endor	< 0.005	< 0.005	0.06	0.02	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	40.2	40.2	< 0.005	0.01	0.04	42.0
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Vorker	< 0.005	< 0.005	< 0.005	0.02	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	3.87	3.87	< 0.005	< 0.005	0.01	3.94
/endor	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	6.65	6.65	< 0.005	< 0.005	0.01	6.95
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00

### 3.8. Building Construction (2024) - Mitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

# Peterbi**Attachment** 9/2022

Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	-	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	-	_	_	_	_	_	_	_	_	-	_	-	_	-	_	_
Off-Road Equipmen		0.52	4.81	5.62	0.01	0.21	_	0.21	0.20	_	0.20	_	1,028	1,028	0.04	0.01	_	1,031
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.09	0.88	1.03	< 0.005	0.04	_	0.04	0.04	_	0.04	_	170	170	0.01	< 0.005	_	171
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.32	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	56.5	56.5	< 0.005	< 0.005	0.25	57.6
Vendor	0.01	< 0.005	0.14	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	93.7	93.7	< 0.005	0.01	0.24	98.1
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.04	0.03	0.31	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	54.2	54.2	< 0.005	< 0.005	0.01	55.0

## Peterbil V2 Detailed Report 9/19/2022

Vendor	0.01	< 0.005	0.15	0.06	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	_	93.7	93.7	< 0.005	0.01	0.01	97.9
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.02	0.02	0.01	0.13	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	23.4	23.4	< 0.005	< 0.005	0.05	23.8
Vendor	< 0.005	< 0.005	0.06	0.02	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	40.2	40.2	< 0.005	0.01	0.04	42.0
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.02	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	3.87	3.87	< 0.005	< 0.005	0.01	3.94
Vendor	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	6.65	6.65	< 0.005	< 0.005	0.01	6.95
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.9. Paving (2024) - Unmitigated

		,	,	J, . J					<b>J</b> ,									
Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.76	6.87	8.89	0.01	0.33	_	0.33	0.30	_	0.30	_	1,351	1,351	0.05	0.01	_	1,355
Paving	_	0.44	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

# Peterbi**Attachmen 1**/19/2022

Off-Road Equipmen		0.04	0.34	0.44	< 0.005	0.02	_	0.02	0.01	_	0.01	_	66.6	66.6	< 0.005	< 0.005	_	66.8
Paving	_	0.02	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_		_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.06	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	11.0	11.0	< 0.005	< 0.005	_	11.1
Paving	_	< 0.005	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	-	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	-
Worker	0.09	0.08	0.06	0.70	0.00	0.00	0.01	0.01	0.00	0.00	0.00	_	124	124	0.01	0.01	0.55	127
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	-
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.03	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	5.91	5.91	< 0.005	< 0.005	0.01	6.01
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.98	0.98	< 0.005	< 0.005	< 0.005	1.00
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

#### 3.10. Paving (2024) - Mitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	всо2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	<u> </u>	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.76	6.87	8.89	0.01	0.33	_	0.33	0.30	_	0.30	_	1,351	1,351	0.05	0.01	_	1,355
Paving	_	0.44	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.34	0.44	< 0.005	0.02	_	0.02	0.01	_	0.01	_	66.6	66.6	< 0.005	< 0.005	_	66.8
Paving	_	0.02	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.06	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	-	11.0	11.0	< 0.005	< 0.005	_	11.1
Paving	_	< 0.005	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_

## Peterbil V2 Detailed Report 1/19/2022

Worker	0.09	0.08	0.06	0.70	0.00	0.00	0.01	0.01	0.00	0.00	0.00	_	124	124	0.01	0.01	0.55	127
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.03	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	5.91	5.91	< 0.005	< 0.005	0.01	6.01
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.98	0.98	< 0.005	< 0.005	< 0.005	1.00
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.11. Architectural Coating (2024) - Unmitigated

		(1.07 0.0.	,	J, J.					j,	. ,	J							
Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.14	0.91	1.15	< 0.005	0.03	_	0.03	0.03	_	0.03	_	134	134	0.01	< 0.005	_	134
Architect ural Coatings	_	40.3	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

# Peterbi**Attachment** 9/2022

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.04	0.06	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	6.58	6.58	< 0.005	< 0.005	_	6.61
Architect ural Coatings	_	1.99	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		< 0.005	0.01	0.01	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	1.09	1.09	< 0.005	< 0.005	_	1.09
Architect ural Coatings	_	0.36	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.01	0.01	0.01	0.06	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	<u> </u>	11.3	11.3	< 0.005	< 0.005	0.05	11.5
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	-	-	_	_	_	_	_	-	_	_	_	_	-	-	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.54	0.54	< 0.005	< 0.005	< 0.005	0.55

Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.09	0.09	< 0.005	< 0.005	< 0.005	0.09
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 3.12. Architectural Coating (2024) - Mitigated

			i e			Jaij aliu	<u> </u>									1		
Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.14	0.91	1.15	< 0.005	0.03	_	0.03	0.03	_	0.03	_	134	134	0.01	< 0.005	_	134
Architect ural Coatings	_	40.3	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.04	0.06	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	6.58	6.58	< 0.005	< 0.005	_	6.61
Architect ural Coatings	_	1.99		_	_		_	_	_	_	_	_	_	_	_	_	_	_

# Peterbi**Attachmen 1**/19/2022

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmer		< 0.005	0.01	0.01	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	1.09	1.09	< 0.005	< 0.005	_	1.09
Architect ural Coatings	_	0.36	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.01	0.01	0.01	0.06	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	11.3	11.3	< 0.005	< 0.005	0.05	11.5
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	-	_	-	_	_	_	-
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	_	0.54	0.54	< 0.005	< 0.005	< 0.005	0.55
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	0.00	0.00	-	0.09	0.09	< 0.005	< 0.005	< 0.005	0.09
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

### 4. Operations Emissions Details

#### 4.1. Mobile Emissions by Land Use

#### 4.1.1. Unmitigated

Mobile source emissions results are presented in Sections 2.6. No further detailed breakdown of emissions is available.

#### 4.1.2. Mitigated

Mobile source emissions results are presented in Sections 2.5. No further detailed breakdown of emissions is available.

#### 4.2. Energy

#### 4.2.1. Electricity Emissions By Land Use - Unmitigated

Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	62.0	62.0	0.01	< 0.005	_	62.6
Automob ile Care Center	_			_	_	_	_	_	_	_	_	_	78.9	78.9	0.01	< 0.005	_	79.7
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	64.0	64.0	0.01	< 0.005	_	64.6
undefine d	_	_	_	_	_	_	_	_	_	_	_	_	216	216	0.03	< 0.005	_	218
Total	_	_	_	_	_	_	_	_	_	_	_	_	421	421	0.07	0.01	_	425
Daily, Winter (Max)	_	_	_	_	_	_	_	_	37 / 91	_	_	_	_	_	_	_	_	_

General	_	_	_	_	_	_	_	_	_	_	_	_	62.0	62.0	0.01	< 0.005	_	62.6
Light Industry																		
Automob ile Care Center		_	_	_	_	_	_	_	_	_	_	_	78.9	78.9	0.01	< 0.005	_	79.7
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	64.0	64.0	0.01	< 0.005	_	64.6
undefine d	_	_	_	_	_	_	_	_	_	_	_	_	216	216	0.03	< 0.005	_	218
Total	_	_	_	_	_	_	_	_	_	_	_	_	421	421	0.07	0.01	_	425
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	10.3	10.3	< 0.005	< 0.005	_	10.4
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	13.1	13.1	< 0.005	< 0.005	_	13.2
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	10.6	10.6	< 0.005	< 0.005	_	10.7
undefine d	_	_	_	_		_				_	_	_	25.5	25.5	< 0.005	< 0.005	_	25.7
Total	_	_	_	_	_	_	_	_	_	_	_	_	59.4	59.4	0.01	< 0.005	_	60.0

#### 4.2.2. Electricity Emissions By Land Use - Mitigated

Officeria		10 (10) 00	,	· j, · o · · · j ·	101 0111110	an, and	000 (.	o, aay ioi	u.u.,	,	armaarj							
Land	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Use																		
Daily,	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Summer																		
(Max)																		

# Peterbi**Attachment** 9/2022

_	_	_	_	_	_	_	_	_	_	_	_	62.0	62.0	0.01	< 0.005	_	62.6
_	_	_	_	_	_	_	_	_	_	_	_	78.9	78.9	0.01	< 0.005	_	79.7
_	_	_	_	_	_	_	_	_	_	_	_	64.0	64.0	0.01	< 0.005	_	64.6
_	_	_	_	_	_	_	_	_	_	_	_	216	216	0.03	< 0.005	_	218
_	_	_	_	_	_	_	_	_	_	_	_	421	421	0.07	0.01	_	425
_	_	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	-	_	_	_	_	_	_	_	_	62.0	62.0	0.01	< 0.005	_	62.6
_	_	_	_	_	_	_	_	_	_	_	_	78.9	78.9	0.01	< 0.005	_	79.7
_	_	_	-	_	_	_	_	_	_	_	_	64.0	64.0	0.01	< 0.005	_	64.6
_	_	_	_	_	_	_	_	_	_	_	_	216	216	0.03	< 0.005	_	218
_	_	_	_	_	_	_	_	_	_	_	_	421	421	0.07	0.01	_	425
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	-	-	_	_	_	_	_	_	_	_	_	10.3	10.3	< 0.005	< 0.005	_	10.4
_	_	_	_	_	_	_	_	_	_	_	_	13.1	13.1	< 0.005	< 0.005	_	13.2
													-       -				

Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	10.6	10.6	< 0.005	< 0.005		10.7
undefine d	_	_	_	_	_	_	_	_	_	_	_	_	25.5	25.5	< 0.005	< 0.005	_	25.7
Total	_	_	_	_	_	_	_	_	_	_	_	_	59.4	59.4	0.01	< 0.005	_	60.0

#### 4.2.3. Natural Gas Emissions By Land Use - Unmitigated

				illy, torry	SO2		•					DOOG-	NDOOG	ОООТ	0114	NOO -		000
Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	0.01	0.01	0.12	0.10	< 0.005	0.01	_	0.01	0.01	_	0.01	_	149	149	0.01	< 0.005	_	149
Automob ile Care Center	0.02	0.01	0.16	0.13	< 0.005	0.01	_	0.01	0.01	_	0.01	_	189	189	0.02	< 0.005	_	190
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	338	338	0.03	< 0.005	_	339
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	0.01	0.01	0.12	0.10	< 0.005	0.01	_	0.01	0.01	_	0.01	_	149	149	0.01	< 0.005	_	149
Automob ile Care Center	0.02	0.01	0.16	0.13	< 0.005	0.01	_	0.01	0.01	_	0.01	_	189	189	0.02	< 0.005	_	190

## Peterbil V2 Detailed Report 1/19/2022

Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	338	338	0.03	< 0.005	_	339
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	24.6	24.6	< 0.005	< 0.005	_	24.7
Automob ile Care Center	< 0.005	< 0.005	0.03	0.02	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	31.3	31.3	< 0.005	< 0.005	_	31.4
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.01	< 0.005	0.05	0.04	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	56.0	56.0	< 0.005	< 0.005	_	56.1

#### 4.2.4. Natural Gas Emissions By Land Use - Mitigated

			,	J, J		,			,									
Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	0.01	0.01	0.12	0.10	< 0.005	0.01	_	0.01	0.01	_	0.01	_	149	149	0.01	< 0.005	_	149
Automob ile Care Center	0.02	0.01	0.16	0.13	< 0.005	0.01	_	0.01	0.01	_	0.01	_	189	189	0.02	< 0.005	_	190
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	338	338	0.03	< 0.005	_	339

## Peterbil V2 Detailed Report 1/19/2022

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_
General Light Industry	0.01	0.01	0.12	0.10	< 0.005	0.01	_	0.01	0.01	_	0.01	_	149	149	0.01	< 0.005	_	149
Automob ile Care Center	0.02	0.01	0.16	0.13	< 0.005	0.01	_	0.01	0.01	_	0.01	_	189	189	0.02	< 0.005	_	190
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.03	0.02	0.28	0.24	< 0.005	0.02	_	0.02	0.02	_	0.02	_	338	338	0.03	< 0.005	_	339
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	24.6	24.6	< 0.005	< 0.005	_	24.7
Automob ile Care Center	< 0.005	< 0.005	0.03	0.02	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	31.3	31.3	< 0.005	< 0.005	_	31.4
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.01	< 0.005	0.05	0.04	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	56.0	56.0	< 0.005	< 0.005	_	56.1

### 4.3. Area Emissions by Source

#### 4.3.2. Unmitigated

			•															
Source	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	всо2	NBCO2	CO2T	СН4	N2O	R	CO2e
Daily,	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Summer																		
(Max)																		

# Peterbia 2 Detailed Report 1/19/2022

Architect Coatings	_	40.5	_	_	_	_	_	_	_		_	_	_	_	_	_	_	_
Consum er Products	_	0.55	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_
Landsca pe Equipme nt	0.19	0.18	0.01	1.09	< 0.005	< 0.005	-	< 0.005	< 0.005	-	< 0.005	_	4.47	4.47	< 0.005	< 0.005	_	4.49
Total	0.19	41.2	0.01	1.09	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.47	4.47	< 0.005	< 0.005	_	4.49
Daily, Winter (Max)	_	_	_	_	_	_	-	_	_	_	_	_	_	_	_	_	_	-
Consum er Products	_	0.55	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.20	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	0.74	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.40	_	_	_	_	_	_	_	_	_	_	_	-	_	_	-	-
Consum er Products	_	0.10	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_
Landsca pe Equipme nt	0.03	0.03	< 0.005	0.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	0.67	0.67	< 0.005	< 0.005	_	0.67
Total	0.03	0.53	< 0.005	0.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	0.67	0.67	< 0.005	< 0.005	_	0.67

#### 4.3.1. Mitigated

Officeria						adi) dila										_		
Source	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	40.5	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Consum er Products	_	0.55	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Landsca pe Equipme nt	0.19	0.18	0.01	1.09	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.47	4.47	< 0.005	< 0.005	_	4.49
Total	0.19	41.2	0.01	1.09	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	4.47	4.47	< 0.005	< 0.005	_	4.49
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Consum er Products	_	0.55	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.20	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	0.74	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.40	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Consum er Products	_	0.10	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Landsca	0.03	0.03	< 0.005	0.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	0.67	0.67	< 0.005	< 0.005	_	0.67
pe Equipme																		
Total	0.03	0.53	< 0.005	0.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	0.67	0.67	< 0.005	< 0.005	_	0.67

#### 4.4. Water Emissions by Land Use

#### 4.4.2. Unmitigated

		, ,	_	<i>J</i> , · <i>J</i>					<b>J</b> ,	.,								
Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	4.87	8.88	13.8	0.50	0.01	_	29.9
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	2.52	3.98	6.51	0.26	0.01	_	14.8
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	< 0.005	< 0.005	< 0.005	< 0.005	_	< 0.005
Total	_	_	_	_	_	_	_	_	_	_	_	7.40	12.9	20.3	0.76	0.02	_	44.7
Daily, Winter (Max)	_	_			_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	4.87	8.88	13.8	0.50	0.01	_	29.9
Automob ile Care Center	_	_				_	_	_	_	_	_	2.52	3.98	6.51	0.26	0.01	_	14.8

Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	< 0.005	< 0.005	< 0.005	< 0.005	_	< 0.005
Total	_	_	_	_	_	_	_	_	_	_	_	7.40	12.9	20.3	0.76	0.02	_	44.7
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	0.81	1.47	2.28	0.08	< 0.005	_	4.95
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	0.42	0.66	1.08	0.04	< 0.005	_	2.46
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	< 0.005	< 0.005	< 0.005	< 0.005	_	< 0.005
Total	_	_	_	_	_	_	_	_	_	_	_	1.22	2.13	3.35	0.13	< 0.005	_	7.40

#### 4.4.1. Mitigated

			,	<i>y</i> ,					<b>J</b> ,									
Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_		_	4.87	8.22	13.1	0.50	0.01	_	29.2
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	2.52	3.98	6.51	0.26	0.01	_	14.8
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	< 0.005	< 0.005	< 0.005	< 0.005	_	< 0.005
Total	_	_	_	_	_	_	_	_	_	_	_	7.40	12.2	19.6	0.76	0.02	_	44.1

# Peterbil V2 Detailed Report 9/19/2022

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	4.87	8.22	13.1	0.50	0.01	_	29.2
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	2.52	3.98	6.51	0.26	0.01	_	14.8
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	< 0.005	< 0.005	< 0.005	< 0.005	_	< 0.005
Total	_	_	_	_	_	_	_	_	_	_	_	7.40	12.2	19.6	0.76	0.02	_	44.1
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	0.81	1.36	2.17	0.08	< 0.005	_	4.84
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	0.42	0.66	1.08	0.04	< 0.005	_	2.46
Parking Lot	_	_	_		_	_	_	_	_	_	_	0.00	< 0.005	< 0.005	< 0.005	< 0.005	_	< 0.005
Total	_	_	_	_	_	_	_	_	_	_	_	1.22	2.02	3.25	0.13	< 0.005	_	7.30

## 4.5. Waste Emissions by Land Use

#### 4.5.2. Unmitigated

				. j, j .														
Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

# Peterbi**Attachmen 1**/19/2022

General Light Industry	_	_	_	_	_	_	_	_	_	_	_	7.35	0.00	7.35	0.73	0.00	_	25.7
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	28.8	0.00	28.8	2.88	0.00	_	101
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	7.35	0.00	7.35	0.73	0.00	_	25.7
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	28.8	0.00	28.8	2.88	0.00	_	101
Parking Lot	_	-	_	_	_	_	_	_	_	-	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	1.22	0.00	1.22	0.12	0.00	_	4.26
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	4.77	0.00	4.77	0.48	0.00	_	16.7
Parking Lot	_	_		_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	5.99	0.00	5.99	0.60	0.00	_	21.0

#### 4.5.1. Mitigated

Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	7.35	0.00	7.35	0.73	0.00	_	25.7
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	28.8	0.00	28.8	2.88	0.00	_	101
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	7.35	0.00	7.35	0.73	0.00	_	25.7
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	28.8	0.00	28.8	2.88	0.00	_	101
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	36.2	0.00	36.2	3.62	0.00	_	127
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	1.22	0.00	1.22	0.12	0.00	_	4.26

Automob Care Center	_	_	_	_	_	_	_	_	_	_	_	4.77	0.00	4.77	0.48	0.00	_	16.7
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	5.99	0.00	5.99	0.60	0.00	_	21.0

## 4.6. Refrigerant Emissions by Land Use

#### 4.6.1. Unmitigated

		(1.07 0.0.						o, alony io.					1		_	1		
Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2.86	2.86
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,902	2,902
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2.86	2.86
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,902	2,902

Total	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	2,905	2,905
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.47	0.47
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	481	481
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	481	481

#### 4.6.2. Mitigated

Land	TOG	ROG	NOx	со	SO2	PM10E			PM2.5E			BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Use																		
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2.86	2.86
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,902	2,902
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Daily, Winter (Max)	_	_			_		_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2.86	2.86

Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,902	2,902
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	2,905	2,905
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
General Light Industry	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.47	0.47
Automob ile Care Center	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	481	481
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	481	481

## 4.7. Offroad Emissions By Equipment Type

#### 4.7.1. Unmitigated

Equipme nt Type	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.7.2. Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Туре																		
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	<u> </u>	_	_	_	_	_	_	_	<u> </u>	<u> </u>	_	<u> </u>	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

## 4.8. Stationary Emissions By Equipment Type

#### 4.8.1. Unmitigated

Equipme nt Type	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

# Peterbi**Attachment** 9 2022

Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.8.2. Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt Type	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.9. User Defined Emissions By Equipment Type

#### 4.9.1. Unmitigated

Equipme nt Type	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

# Peterbi**Attachment** 9 2022

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.9.2. Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt Type	TOG	ROG				PM10E				PM2.5D		BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

## 4.10. Soil Carbon Accumulation By Vegetation Type

#### 4.10.1. Soil Carbon Accumulation By Vegetation Type - Unmitigated

			,	, ,														
Vegetatio	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
n																		

# Peterbi**Attachment** 9 2022

Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.10.2. Above and Belowground Carbon Accumulation by Land Use Type - Unmitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.10.3. Avoided and Sequestered Emissions by Species - Unmitigated

			(	,	J, J-		,	(-		<b>,</b> ,									
9	pecies	TOG	ROG	NOx	lco	ISO2	DM10E	DM10D	PM10T	DM2 5E	I DM2 5D	DM2.5T	IRCO2	NRCO2	LCO2T	CHA	N2O	R	CO2e
		100	11.00		100	1002	II MIIOE		II INI IO I	I IVIZ.UL	I IVIZ.UD	I IVIZ.U I	10002	INDCOZ	10021	OI 1 <del>4</del>	INZU	18	0026

# Peterbi**Attachment** 9/2022

Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_		_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	

# Peterbi**Attachment** 9/2022

Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	-	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_

Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN

## 4.10.4. Soil Carbon Accumulation By Vegetation Type - Mitigated

Vegetatio n	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	<u> </u>	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	<u> </u>
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.10.5. Above and Belowground Carbon Accumulation by Land Use Type - Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.10.6. Avoided and Sequestered Emissions by Species - Mitigated

Species	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_

# Peterbi**Attachment** 9/2022

undefine	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
undefine d	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_

# Peterbi**Attachment** 9/2022

undefine d	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
undefine d	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
undefine d	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_

Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Oak, interior live	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Planetre e, London	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
undefine d	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Pistache, Chinese	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	NaN	NaN	NaN	NaN	NaN	NaN	_	NaN	NaN	_	_	_	NaN

# 5. Activity Data

#### 5.1. Construction Schedule

Phase Name	Phase Type	Start Date	End Date	Days Per Week	Work Days per Phase	Phase Description
Site Preparation	Site Preparation	8/30/2023	9/6/2023	5.00	5.00	_
Grading	Grading	9/7/2023	9/18/2023	5.00	8.00	_
Building Construction	Building Construction	9/19/2023	8/6/2024	5.00	230	_
Paving	Paving	8/7/2024	9/1/2024	5.00	18.0	_

Architectural Coating	Architectural Coating	9/27/2024	5.00	18.0	_
0					

## 5.2. Off-Road Equipment

## 5.2.1. Unmitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Site Preparation	Rubber Tired Dozers	Diesel	Average	3.00	8.00	367	0.40
Site Preparation	Tractors/Loaders/Backh oes	Diesel	Average	4.00	8.00	84.0	0.37
Grading	Excavators	Diesel	Average	1.00	8.00	36.0	0.38
Grading	Graders	Diesel	Average	1.00	8.00	148	0.41
Grading	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Grading	Tractors/Loaders/Backh oes	Diesel	Average	3.00	8.00	84.0	0.37
Building Construction	Cranes	Diesel	Average	1.00	7.00	367	0.29
Building Construction	Forklifts	Diesel	Average	3.00	8.00	82.0	0.20
Building Construction	Generator Sets	Diesel	Average	1.00	8.00	14.0	0.74
Building Construction	Tractors/Loaders/Backh oes	Diesel	Average	3.00	7.00	84.0	0.37
Building Construction	Welders	Diesel	Average	1.00	8.00	46.0	0.45
Paving	Cement and Mortar Mixers	Diesel	Average	2.00	6.00	10.0	0.56
Paving	Pavers	Diesel	Average	1.00	8.00	81.0	0.42
Paving	Paving Equipment	Diesel	Average	2.00	6.00	89.0	0.36
Paving	Rollers	Diesel	Average	2.00	6.00	36.0	0.38
Paving	Tractors/Loaders/Backh oes	Diesel	Average	1.00	8.00	84.0	0.37
Architectural Coating	Air Compressors	Diesel	Average	1.00	6.00	37.0	0.48

#### 5.2.2. Mitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Site Preparation	Rubber Tired Dozers	Diesel	Average	3.00	8.00	367	0.40
Site Preparation	Tractors/Loaders/Backh oes	Diesel	Average	4.00	8.00	84.0	0.37
Grading	Excavators	Diesel	Average	1.00	8.00	36.0	0.38
Grading	Graders	Diesel	Average	1.00	8.00	148	0.41
Grading	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Grading	Tractors/Loaders/Backh oes	Diesel	Average	3.00	8.00	84.0	0.37
Building Construction	Cranes	Diesel	Average	1.00	7.00	367	0.29
Building Construction	Forklifts	Diesel	Average	3.00	8.00	82.0	0.20
Building Construction	Generator Sets	Diesel	Average	1.00	8.00	14.0	0.74
Building Construction	Tractors/Loaders/Backh oes	Diesel	Average	3.00	7.00	84.0	0.37
Building Construction	Welders	Diesel	Average	1.00	8.00	46.0	0.45
Paving	Cement and Mortar Mixers	Diesel	Average	2.00	6.00	10.0	0.56
Paving	Pavers	Diesel	Average	1.00	8.00	81.0	0.42
Paving	Paving Equipment	Diesel	Average	2.00	6.00	89.0	0.36
Paving	Rollers	Diesel	Average	2.00	6.00	36.0	0.38
Paving	Tractors/Loaders/Backh oes	Diesel	Average	1.00	8.00	84.0	0.37
Architectural Coating	Air Compressors	Diesel	Average	1.00	6.00	37.0	0.48

## 5.3. Construction Vehicles

#### 5.3.1. Unmitigated

		a =. =	— .	
Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix

Site Preparation	_	_	<u> </u>	_
Site Preparation	Worker	17.5	8.10	LDA,LDT1,LDT2
Site Preparation	Vendor	_	6.90	HHDT,MHDT
Site Preparation	Hauling	0.00	20.0	HHDT
Site Preparation	Onsite truck	_	_	HHDT
Grading	_	_	_	_
Grading	Worker	15.0	8.10	LDA,LDT1,LDT2
Grading	Vendor	_	6.90	HHDT,MHDT
Grading	Hauling	36.0	20.0	ННОТ
Grading	Onsite truck	_	_	HHDT
Building Construction	_	_	_	_
Building Construction	Worker	9.10	8.10	LDA,LDT1,LDT2
Building Construction	Vendor	4.10	6.90	HHDT,MHDT
Building Construction	Hauling	0.00	20.0	HHDT
Building Construction	Onsite truck	_	_	HHDT
Paving	_	_	_	_
Paving	Worker	20.0	8.10	LDA,LDT1,LDT2
Paving	Vendor	_	6.90	HHDT,MHDT
Paving	Hauling	0.00	20.0	HHDT
Paving	Onsite truck	_	_	HHDT
Architectural Coating	_	_	_	_
Architectural Coating	Worker	1.82	8.10	LDA,LDT1,LDT2
Architectural Coating	Vendor	_	6.90	HHDT,MHDT
Architectural Coating	Hauling	0.00	20.0	HHDT
Architectural Coating	Onsite truck	_	_	ннот

## 5.3.2. Mitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Site Preparation	_	_	_	_
Site Preparation	Worker	17.5	8.10	LDA,LDT1,LDT2
Site Preparation	Vendor	_	6.90	ннот,мнот
Site Preparation	Hauling	0.00	20.0	ннот
Site Preparation	Onsite truck	_	_	HHDT
Grading	_	_	_	_
Grading	Worker	15.0	8.10	LDA,LDT1,LDT2
Grading	Vendor	_	6.90	HHDT,MHDT
Grading	Hauling	36.0	20.0	HHDT
Grading	Onsite truck	_	_	HHDT
Building Construction	_	_	_	_
Building Construction	Worker	9.10	8.10	LDA,LDT1,LDT2
Building Construction	Vendor	4.10	6.90	HHDT,MHDT
Building Construction	Hauling	0.00	20.0	HHDT
Building Construction	Onsite truck	_	_	HHDT
Paving	_	_	_	_
Paving	Worker	20.0	8.10	LDA,LDT1,LDT2
Paving	Vendor	_	6.90	HHDT,MHDT
Paving	Hauling	0.00	20.0	HHDT
Paving	Onsite truck	_	_	HHDT
Architectural Coating	_	_	_	_
Architectural Coating	Worker	1.82	8.10	LDA,LDT1,LDT2
Architectural Coating	Vendor	_	6.90	HHDT,MHDT
Architectural Coating	Hauling	0.00	20.0	HHDT
Architectural Coating	Onsite truck	_	_	HHDT

#### 5.4. Vehicles

#### 5.4.1. Construction Vehicle Control Strategies

Non-applicable. No control strategies activated by user.

#### 5.5. Architectural Coatings

Phase Name	Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
Architectural Coating	0.00	0.00	43,381	14,460	7,841

## 5.6. Dust Mitigation

#### 5.6.1. Construction Earthmoving Activities

Phase Name	Material Imported (cy)	Material Exported (cy)	l de la companya de	Material Demolished (Building Square Footage)	Acres Paved (acres)
Grading	0.00	0.00	0.00	25,000	_
Paving	0.00	0.00	0.00	0.00	3.00

#### 5.6.2. Construction Earthmoving Control Strategies

Control Strategies Applied	Frequency (per day)	PM10 Reduction	PM2.5 Reduction
Water Exposed Area	2	61%	61%
Water Demolished Area	2	36%	36%

#### 5.7. Construction Paving

Land Use	Area Paved (acres)	% Asphalt
General Light Industry	0.00	0%
Automobile Care Center	0.00	0%

Parking Lot	3.00	100%
-------------	------	------

#### 5.8. Construction Electricity Consumption and Emissions Factors

kWh per Year and Emission Factor (lb/MWh)

Year	kWh per Year	CO2	CH4	N2O
2023	0.00	204	0.03	< 0.005
2024	0.00	204	0.03	< 0.005

#### 5.9. Operational Mobile Sources

#### 5.9.1. Unmitigated

Land Use Type	Trips/Weekday	Trips/Saturday	Trips/Sunday	Trips/Year	VMT/Weekday	VMT/Saturday	VMT/Sunday	VMT/Year
Total all Land Uses	178	0.00	0.00	0.00	38.0	0.00	0.00	0.00

#### 5.9.2. Mitigated

Land Use Type	Trips/Weekday	Trips/Saturday	Trips/Sunday	Trips/Year	VMT/Weekday	VMT/Saturday	VMT/Sunday	VMT/Year
Total all Land Uses	178	0.00	0.00	0.00	38.0	0.00	0.00	0.00

#### 5.10. Operational Area Sources

5.10.1. Hearths

5.10.1.1. Unmitigated

5.10.1.2. Mitigated

5.10.2. Architectural Coatings



Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
0	0.00	43,381	14,460	7,841

#### 5.10.3. Landscape Equipment

Season	Unit	Value
Snow Days	day/yr	0.00
Summer Days	day/yr	330

#### 5.10.4. Landscape Equipment - Mitigated

Season	Unit	Value
Snow Days	day/yr	0.00
Summer Days	day/yr	330

## 5.11. Operational Energy Consumption

#### 5.11.1. Unmitigated

Electricity (kWh/yr) and CO2 and CH4 and N2O and Natural Gas (kBTU/yr)

Land Use	Electricity (kWh/yr)	CO2	CH4	N2O	Natural Gas (kBTU/yr)
General Light Industry	110,948	204	0.0330	0.0040	464,137
Automobile Care Center	141,206	204	0.0330	0.0040	590,720
Parking Lot	114,476	204	0.0330	0.0040	0.00

#### 5.11.2. Mitigated

Electricity (kWh/yr) and CO2 and CH4 and N2O and Natural Gas (kBTU/yr)

Land Use	Electricity (kWh/yr)	CO2	CH4	N2O	Natural Gas (kBTU/yr)
General Light Industry	110,948	204	0.0330	0.0040	464,137

Automobile Care Center	141,206	204	0.0330	0.0040	590,720
Parking Lot	114,476	204	0.0330	0.0040	0.00

## 5.12. Operational Water and Wastewater Consumption

#### 5.12.1. Unmitigated

Land Use	Indoor Water (gal/year)	Outdoor Water (gal/year)
General Light Industry	2,543,750	547,924
Automobile Care Center	1,317,136	13.6
Parking Lot	0.00	13.6

#### 5.12.2. Mitigated

Land Use	Indoor Water (gal/year)	Outdoor Water (gal/year)
General Light Industry	2,543,750	246,151
Automobile Care Center	1,317,136	6.09
Parking Lot	0.00	6.09

## 5.13. Operational Waste Generation

#### 5.13.1. Unmitigated

Land Use	Waste (ton/year)	Cogeneration (kWh/year)	
General Light Industry	13.6	0.00	
Automobile Care Center	53.5	0.00	
Parking Lot	0.00	0.00	

#### 5.13.2. Mitigated

Land Use	Waste (ton/year)	Cogeneration (kWh/year)
General Light Industry	13.6	0.00
Automobile Care Center	53.5	0.00
Parking Lot	0.00	0.00

## 5.14. Operational Refrigeration and Air Conditioning Equipment

#### 5.14.1. Unmitigated

Land Use Type	Equipment Type	Refrigerant	GWP	Quantity (kg)	Operations Leak Rate	Service Leak Rate	Times Serviced
General Light Industry	Other commercial A/C and heat pumps	R-410A	2,088	0.30	4.00	4.00	18.0
Automobile Care Center	Other commercial A/C and heat pumps	R-410A	2,088	< 0.005	4.00	4.00	18.0
Automobile Care Center	Supermarket refrigeration and condensing units	R-404A	3,922	26.5	16.5	16.5	18.0

#### 5.14.2. Mitigated

Land Use Type	Equipment Type	Refrigerant	GWP	Quantity (kg)	Operations Leak Rate	Service Leak Rate	Times Serviced
General Light Industry	Other commercial A/C and heat pumps	R-410A	2,088	0.30	4.00	4.00	18.0
Automobile Care Center	Other commercial A/C and heat pumps	R-410A	2,088	< 0.005	4.00	4.00	18.0
Automobile Care Center	Supermarket refrigeration and condensing units	R-404A	3,922	26.5	16.5	16.5	18.0

## 5.15. Operational Off-Road Equipment

#### 5.15.1. Unmitigated

Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Air Compressors	Electric	Average	10.0	8.00	37.0	0.48
_	Diesel	Average	_	8.00	_	_

#### 5.15.2. Mitigated

Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Air Compressors	Electric	Average	10.0	8.00	37.0	0.48
_	Diesel	Average	_	8.00	_	_

## 5.16. Stationary Sources

#### 5.16.1. Emergency Generators and Fire Pumps

Equipment Type	Fuel Type	Number per Day	Hours per Day	Hours per Year	Horsepower	Load Factor

#### 5.16.2. Process Boilers

Equipment Type	Fuel Type	Number	Boiler Rating (MMBtu/hr)	Daily Heat Input (MMBtu/day)	Annual Heat Input (MMBtu/vr)
Equipment Type	1 doi 1ypo	TTUTTE	Donor realing (MMDEA/III)	Bany Hour input (Miniblarday)	/ tillidai i loat ilipat (iviivibta/yi)

#### 5.17. User Defined

Equipment Type	Fuel Type
_	_

## 5.18. Vegetation

5.18.1. Land Use Change

5.18.1.1. Unmitigated

Vegetation Land Use Type   Vegetation Soil Type   Initial Acres   Final Acre	ros
regetation Land Ose Type   Vegetation Soil Type   Initial Acres   Initial Acres   Initial Acres	165

#### 5.18.1.2. Mitigated

Vegetation Land Use Type	Vegetation Soil Type	Initial Acres	Final Acres
vegetation Land OSC Type	regetation con Type	Initial Acies	i ilai Acica

## 5.18.1. Biomass Cover Type

#### 5.18.1.1. Unmitigated

Bi	omass Cover Type	Initial Acres	Final Acres

#### 5.18.1.2. Mitigated

Biomass Cover Type	Initial Acres	Final Acres
--------------------	---------------	-------------

#### 5.18.2. Sequestration

#### 5.18.2.1. Unmitigated

Tree Type	Number	Electricity Saved (kWh/year)	Natural Gas Saved (btu/year)
Pistache, Chinese	35.0	_	_
Oak, interior live	-3.00	_	_
Planetree, London	-3.00	_	_

## 5.18.2.2. Mitigated

Tree Type	Number	Electricity Saved (kWh/year)	Natural Gas Saved (btu/year)
Pistache, Chinese	35.0	_	_
_	_	_	_
Oak, interior live	-3.00	_	_

Planetree, London	-3.00	_	_
_	_	_	_

### 6. Climate Risk Detailed Report

#### 6.1. Climate Risk Summary

Cal-Adapt midcentury 2040–2059 average projections for four hazards are reported below for your project location. These are under Representation Concentration Pathway (RCP) 8.5 which assumes GHG emissions will continue to rise strongly through 2050 and then plateau around 2100.

Climate Hazard	Result for Project Location	Unit
Temperature and Extreme Heat	21.6	annual days of extreme heat
Extreme Precipitation	5.70	annual days with precipitation above 20 mm
Sea Level Rise	0.00	meters of inundation depth
Wildfire	27.4	annual hectares burned

Temperature and Extreme Heat data are for grid cell in which your project are located. The projection is based on the 98th historical percentile of daily maximum/minimum temperatures from observed historical data (32 climate model ensemble from Cal-Adapt, 2040–2059 average under RCP 8.5). Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

Extreme Precipitation data are for the grid cell in which your project are located. The threshold of 20 mm is equivalent to about <sup>3</sup>/<sub>4</sub> an inch of rain, which would be light to moderate rainfall if received over a full day or heavy rain if received over a period of 2 to 4 hours. Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

Sea Level Rise data are for the grid cell in which your project are located. The projections are from Radke et al. (2017), as reported in Cal-Adapt (2040–2059 average under RCP 8.5), and consider different increments of sea level rise coupled with extreme storm events. Users may select from four model simulations to view the range in potential inundation depth for the grid cell. The four simulations make different assumptions about expected rainfall and temperature are: Warmer/drier (HadGEM2-ES), Cooler/wetter (CNRM-CM5), Average conditions (CanESM2), Range of different rainfall and temperature possibilities (MIROC5). Each grid cell is 50 meters (m) by 50 m, or about 164 feet (ft) by 164 ft.

Wildfire data are for the grid cell in which your project are located. The projections are from UC Davis, as reported in Cal-Adapt (2040–2059 average under RCP 8.5), and consider historical data of climate, vegetation, population density, and large (> 400 ha) fire history. Users may select from four model simulations to view the range in potential wildfire probabilities for the grid cell. The four simulations make different assumptions about expected rainfall and temperature are: Warmer/drier (HadGEM2-ES), Cooler/wetter (CNRM-CM5), Average conditions (CanESM2), Range of different rainfall and temperature possibilities (MIROC5). Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

#### 6.2. Initial Climate Risk Scores

Climate Hazard	Exposure Score	Sensitivity Score	Adaptive Capacity Score	Vulnerability Score
Temperature and Extreme Heat	N/A	N/A	N/A	N/A
Extreme Precipitation	N/A	N/A	N/A	N/A
Sea Level Rise	1	0	0	N/A
Wildfire	1	0	0	N/A

# Peterbia v2 Detailed Report 1/19/2022

Flooding	N/A	N/A	N/A	N/A
Drought	0	0	0	N/A
Snowpack	N/A	N/A	N/A	N/A
Air Quality	N/A	N/A	N/A	N/A

The sensitivity score reflects the extent to which a project would be adversely affected by exposure to a climate hazard. Exposure is rated on a scale of 1 to 5, with a score of 5 representing the greatest exposure.

The adaptive capacity of a project refers to its ability to manage and reduce vulnerabilities from projected climate hazards. Adaptive capacity is rated on a scale of 1 to 5, with a score of 5 representing the greatest ability to adapt.

The overall vulnerability scores are calculated based on the potential impacts and adaptive capacity assessments for each hazard. Scores do not include implementation of climate risk reduction measures.

#### 6.3. Adjusted Climate Risk Scores

Climate Hazard	Exposure Score	Sensitivity Score	Adaptive Capacity Score	Vulnerability Score
Temperature and Extreme Heat	N/A	N/A	N/A	N/A
Extreme Precipitation	N/A	N/A	N/A	N/A
Sea Level Rise	1	1	1	2
Wildfire	1	1	1	2
Flooding	N/A	N/A	N/A	N/A
Drought	1	1	1	2
Snowpack	N/A	N/A	N/A	N/A
Air Quality	N/A	N/A	N/A	N/A

The sensitivity score reflects the extent to which a project would be adversely affected by exposure to a climate hazard. Exposure is rated on a scale of 1 to 5, with a score of 5 representing the greatest exposure.

The adaptive capacity of a project refers to its ability to manage and reduce vulnerabilities from projected climate hazards. Adaptive capacity is rated on a scale of 1 to 5, with a score of 5 representing the greatest ability to adapt.

The overall vulnerability scores are calculated based on the potential impacts and adaptive capacity assessments for each hazard. Scores include implementation of climate risk reduction measures.

#### 6.4. Climate Risk Reduction Measures

#### 6.4.1. Wildfire

Oser delected ineasures   Oo-Deficition Achieved   Exposure reduction   Oelistivity freduction   Adaptive dapacity increase		User Selected Measures	Co-Benefits Achieved	Exposure Reduction	Sensitivity Reduction	Adaptive Capacity Increase
---	--	------------------------	----------------------	--------------------	-----------------------	----------------------------

WF-1: Implement Fire-safe	Improved Air Quality, Improved	_	1.00	_
Landscaping	Ecosystem Health, Improved Public			
	Health			

#### 6.4.2. Drought

User Selected Measures	Co-Benefits Achieved	Exposure Reduction	Sensitivity Reduction	Adaptive Capacity Increase
D-3: Install Drought Resistant Landscaping	Water Conservation	_	1.00	1.00

# 7. Health and Equity Details

#### 7.1. CalEnviroScreen 4.0 Scores

The maximum CalEnviroScreen score is 100. A high score (i.e., greater than 50) reflects a higher pollution burden compared to other census tracts in the state.

Indicator	Result for Project Census Tract
Exposure Indicators	_
AQ-Ozone	26.7
AQ-PM	4.19
AQ-DPM	7.27
Drinking Water	64.2
Lead Risk Housing	5.77
Pesticides	58.4
Toxic Releases	15.0
Traffic	35.1
Effect Indicators	_
CleanUp Sites	0.00
Groundwater	0.00
Haz Waste Facilities/Generators	16.6
Impaired Water Bodies	51.2

# Peterbia Pet

Solid Waste	59.2
Sensitive Population	_
Asthma	32.4
Cardio-vascular	24.0
Low Birth Weights	19.0
Socioeconomic Factor Indicators	_
Education	17.2
Housing	22.1
Linguistic	10.4
Poverty	15.8
Unemployment	6.30

## 7.2. Healthy Places Index Scores

The maximum Health Places Index score is 100. A high score (i.e., greater than 50) reflects healthier community conditions compared to other census tracts in the state.

Indicator	Result for Project Census Tract
Economic	_
Above Poverty	78.91697677
Employed	43.98819453
Education	_
Bachelor's or higher	70.67881432
High school enrollment	100
Preschool enrollment	76.63287566
Transportation	_
Auto Access	61.56807391
Active commuting	28.23046324
Social	_
2-parent households	63.80084691

# Peterbi**Attachment** 9/2022

Voting	96.77916079
Neighborhood	_
Alcohol availability	75.47799307
Park access	2.194276915
Retail density	7.391248556
Supermarket access	20.78788656
Tree canopy	89.15693571
Housing	_
Homeownership	88.6179905
Housing habitability	75.08020018
Low-inc homeowner severe housing cost burden	41.46028487
Low-inc renter severe housing cost burden	37.03323495
Uncrowded housing	81.14974978
Health Outcomes	_
Insured adults	70.40934172
Arthritis	0.0
Asthma ER Admissions	59.2
High Blood Pressure	0.0
Cancer (excluding skin)	0.0
Asthma	0.0
Coronary Heart Disease	0.0
Chronic Obstructive Pulmonary Disease	0.0
Diagnosed Diabetes	0.0
Life Expectancy at Birth	62.5
Cognitively Disabled	68.5
Physically Disabled	32.1
Heart Attack ER Admissions	79.3

# Peterbi**Attachment** 9/2022

Mental Health Not Good	0.0
Chronic Kidney Disease	0.0
Obesity	0.0
Pedestrian Injuries	19.6
Physical Health Not Good	0.0
Stroke	0.0
Health Risk Behaviors	
Binge Drinking	0.0
Current Smoker	0.0
No Leisure Time for Physical Activity	0.0
Climate Change Exposures	_
Wildfire Risk	28.0
SLR Inundation Area	0.0
Children	84.0
Elderly	4.7
English Speaking	95.9
Foreign-born	8.4
Outdoor Workers	40.3
Climate Change Adaptive Capacity	_
Impervious Surface Cover	94.8
Traffic Density	19.7
Traffic Access	0.0
Other Indices	_
Hardship	25.9
Other Decision Support	_
2016 Voting	96.3

#### 7.3. Overall Health & Equity Scores

Metric	Result for Project Census Tract
CalEnviroScreen 4.0 Score for Project Location (a)	6.00
Healthy Places Index Score for Project Location (b)	73.0
Project Located in a Designated Disadvantaged Community (Senate Bill 535)	No
Project Located in a Low-Income Community (Assembly Bill 1550)	No
Project Located in a Community Air Protection Program Community (Assembly Bill 617)	No

a: The maximum CalEnviroScreen score is 100. A high score (i.e., greater than 50) reflects a higher pollution burden compared to other census tracts in the state.

#### 7.4. Health & Equity Measures

Measure Title	Co-Benefits Achieved
IE-5: Provide Education on Essential Topics Related to Project	Social Equity
PH-2: Increase Urban Tree Canopy and Green Spaces	Energy and Fuel Savings, Enhanced Energy Security, Improved Air Quality, Improved Ecosystem Health, Improved Public Health, Social Equity

#### 7.5. Evaluation Scorecard

Health and Equity Evaluation Scorecard not completed.


## 8. User Changes to Default Data

Screen	Justification
Construction: Construction Phases	There are no existing structures to demolish
Construction: Demolition	Spreading water is required during grading.
Construction: Dust From Material Movement	Grading is balanced. No import or export trips are anticipated.

b: The maximum Health Places Index score is 100. A high score (i.e., greater than 50) reflects healthier community conditions compared to other census tracts in the state.

# PETERBILT PASO ROBLES

2805 Theatre Drive Paso Robles, CA 93446




Information on required routine maintenance measures, including, but not limited to,

11. A copy of all special inspection verifications required by the enforcing agency or this

caulking, painting, grading around the building....etc.

10. Information about state solar energy and incentive programs available.



OWNER / CLIENT	ARCHITECT	CIVIL ENGINEER
Coast Counties Peterbilt CONTACT: Craig Archer	Studio 2G Architects, LLP Laura Gough, AIA	Tartaglia Engineering Robert Tartaglia
3030 Ramada Drive	811 Palm St.	7360 El Camino Real #
Paso Robles, CA 93446	San Luis Obispo, CA 93401 P: 805.594.0771 EXT.112	Atascadero, CA 93422 P: 805.466.5660
	F: 805.540.5137	1 . 000.400.0000
PLANNER Planning Solutions	MECHANICAL/PLUMBING BMA Mechanical	ELECTRICAL  JMPE Electrical Engine
Pam Jardini	CONTACT: Dustin Lane	CONTACT: John Malon
1360 New Wine Place Templeton, CA 93465	689 Tank Farm Rd, Ste. 240 San Luis Obispo, CA 93401	627 Olive Street Santa Barbara, CA 931
P: 805.801.0453	P: 805.544.4269	P: 805.569.9216
LANDSCAPE ARCHITECT	CONTRACTOR	
Pleine Aire Design Group	Wiemann G Construction	
CONTACT: Kevin Small 3203 Lightning St., Ste.201	Greg Wiemann 3400 Stage Springs Rd.	
Santa Maria, CA 93455	Creston, CA 93432	
P: 805.349.9695	P: 805.674.0125	
PROJECT INFO	)	
	cualtion for semi trucks.	ork and landscaping to sup
Grading and drainage control fo building use. Construction of ar Site lighting and signage as req	r proposal retailer facility with flatw n 25,000+ SF, two story building to	
Grading and drainage control for puilding use. Construction of an Site lighting and signage as requestions.	r proposal retailer facility with flatw n 25,000+ SF, two story building to	accomodate the proposed u
Grading and drainage control for puilding use. Construction of an Site lighting and signage as requestions of the summary of t	r proposal retailer facility with flatw n 25,000+ SF, two story building to uired. 2805 Theatre Dr 009-851-022	accomodate the proposed t
Grading and drainage control for puilding use. Construction of an Site lighting and signage as requestions of the summary of t	r proposal retailer facility with flatw n 25,000+ SF, two story building to uired. 2805 Theatre Dr	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as requestions of the second signage as requestions. SITE SUMMARY ADDRESS: APN#: PARCEL SIZE:	r proposal retailer facility with flatw n 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as requestion of the site lighting signal in the site lighting signal signal in the site lighting signal in the site lighting signal signal in the site lighting signal signal signal signal signal si	r proposal retailer facility with flatw n 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting and signage as required as signage.  SITE SUMMARY ADDRESS:  ADDRESS:  APN#: PARCEL SIZE: FIRE SEVERITY ZONE:  BUILDING SUMMARY USE: OCCUPANCY:	r proposal retailer facility with flatw n 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting and signage as required as signage.  SITE SUMMARY ADDRESS: ADDRESS: APN#: PARCEL SIZE: FIRE SEVERITY ZONE:  BUILDING SUMMARY USE: OCCUPANCY: CONSTRUCTION TYPE:	r proposal retailer facility with flatwn 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting and signage as required as signage as r	r proposal retailer facility with flatw n 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M	accomodate the proposed t
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting site lightin	r proposal retailer facility with flatwn 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting as sit	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting.  BUILDING SUMMARY USE: OCCUPANCY: CONSTRUCTION TYPE: EXISTING STORIES: PROPOSED STORIES: PROPOSED STORIES: BUILDING AREA NEW CONDITIONED GROUND FLOOR RETAIL/SER	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2	accomodate the proposed t
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting as site lighting and signage as required as site lighting a	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2  RVICE 20,735 SF 4,553 SF 25,288 SF	accomodate the proposed u
Grading and drainage control for building use. Construction of an Site lighting and signage as required as site lighting as site lighting and signage as required as site lighting and signage as required as site lighting and signage as required as site lighting as site	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2  EVICE 20,735 SF 4,553 SF	accomodate the proposed u
	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2  RVICE 20,735 SF 4,553 SF 25,288 SF  1,889 SF	accomodate the proposed u
Grading and drainage control for considing use. Construction of an Site lighting and signage as required as site lighting as site lighting and signage as required as site lighting and signage as required as site lighting and signage as required as site lighting as site	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2  RVICE 20,735 SF 4,553 SF 25,288 SF  1,889 SF 3,330 SF	accomodate the proposed u
Grading and drainage control for considing use. Construction of an Site lighting and signage as required as site lighting as site lighting and signage as required as site lighting and signage as required as site lighting and signage as required as site lighting as site	r proposal retailer facility with flatwon 25,000+ SF, two story building to uired.  2805 Theatre Dr 009-851-022 6.6 acres N/A  C2 H-2 / M II-A N/A 2  RVICE 20,735 SF 4,553 SF 25,288 SF  1,889 SF 3,330 SF	accomodate the proposed u

AGENCIES & UTILITIES - CITY OF PASO ROBLES

Paso Robles, CA 93446

Service Center

406 Higuera Street

805.546.5380

SOCALGAS

800.427.2200

2240 Emily Street

800.310.2355 (Residential)

San Luis Obispo, CA 93401

San Luis Óbispo, CA 93401

800.750.2355 (Business)

900 Park Street

FIRE DEPARTMENT

Paso Robles, CA 93446

UTILITIES DEPARTMENT

San Luis Obispo, CA 93401

900 Park Street

805.227.7560

879 Morro Street

805.781.7237

805.237.6464

BUILDING DEPARTMENT POLICE DEPARTMENT

1000 Spring Street

1000 Spring Street

PUBLIC WORKS

821 Pine Street #A

Paso Robles, CA 93446

DEPARTMENT

805.737.3996

Paso Robles, CA 93446

805.237.3850

805.237.3970

Paso Robles, CA 93446

PLANNING DEPARTMENT

0.004	INDEX - COMMERCIAL	
G-001 G-011 G-021 G-022	TITLE SHEETS GENERAL NOTES SOILS REPORT SOILS REPORT	
C-4 C-10 C-11 C-16 C-17	CIVIL SITE PLAN WATER LINE EXTENSION PLAN & DETAILS WATER & SEWER EXTENSION PLAN DEMOLITION PLAN - NORTH PORTION DEMOLITION PLAN - SOUTH PORTION	
L-00 L-01 L-02	CONCEPTUAL LANDSCAPE PLAN RENDER CONCEPTUAL LANDSCAPE PLAN PLANT IMAGERY	
AS101 AS111 AS112 AS201 AS202	OVERALL ARCHITECTURAL SITE PLAN SITE FENCING EXHIBIT SITE DETAILS SITE LIGHTING PLAN SITE LIGHTING PLAN	
A-101 A-102 A-131 A-201	FIRST FLOOR DIMENSIONAL PLAN SECOND FLOOR DIMENSIONAL PLAN ROOF PLAN EXTERIOR ELEVATIONS	
TOTAL SHEETS	21	
SOILS I	REPORT	
The geotechni Peterbilt - Pas	REPORT  cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.	
The geotechni Peterbilt - Pas considered a p	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0	3/08/2022] shall be the soils engineer a
The geotechni Peterbilt - Pas considered a p The Architectu found to be in	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.	3/08/2022] shall be the soils engineer a
The geotechni Peterbilt - Pas considered a p The Architectu found to be in	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.  Iral and Structural plans have been reviewed by conformance with geotechnical report. Refer to	3/08/2022] shall be the soils engineer a
The geotechnic Peterbilt - Passidered a property of the Architectur found to be in	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.  Iral and Structural plans have been reviewed by conformance with geotechnical report. Refer to	3/08/2022] shall be the soils engineer a sheet G-021
The geotechnic Peterbilt - Passiconsidered a property of the Architectur found to be in PERMIT	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.  Iral and Structural plans have been reviewed by conformance with geotechnical report. Refer to TYPE  PERMIT TYPE	3/08/2022] shall be the soils engineer a sheet G-021
The geotechnic Peterbilt - Passionsidered a property of the Architectur found to be in PERMIT  PERMIT  ####  STATEN  This project has adopted code State Accessite	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.  Iral and Structural plans have been reviewed by conformance with geotechnical report. Refer to	3/08/2022] shall be the soils engineer at sheet G-021  DATE 00/00/0  the City of Paso Romited to the Californ
The geotechnic Peterbilt - Passionsidered a property of the Architectur found to be in PERMIT  PERMIT  ####  STATEN  This project has adopted code State Accessite	cal engineering report [H-211472] prepared by [o Robles project at 2805 Theatre Drive dated [0 part of these plans.  I and Structural plans have been reviewed by conformance with geotechnical report. Refer to TYPE  PERMIT TYPE  PERMIT TYPE  as been designed in accordance with and meets and ordinance requirements including, but not libility Standards and I/We will be responsible for	3/08/2022] shall be the soils engineer an sheet G-021  DATE 00/00/0  the City of Paso Ro mited to the Californ all clarifications deer



SED ARCHES

CHINA T. CHILLIAN

TRANSPORT

OF CALIFORNIA

OF CALIFO

Craig Archer 3030 Ramada Drive, Paso Robles CA

030 Ramada Drive, Paso Robles CA

aso Roble eatre Drive

eterbilt F

SUBMITTALS & REVISIONS

DATE

IS

SUBMITTALS & REVISIONS

DATE ISSUE

03 JUN 22 DEVELOPMENT PLAN RESUBMITTAL

JOB NUMBER **2138** 

2138
GENCY APPROVAL

TITLE SHEET

G-001

- After installing wall, ceiling, or floor insulation, the installer shall post in a conspicuous location in the building a certificate signed by the installer stating that the installation conforms with the requirements of Title 24 Energy Conservation Standards. The certificate shall also state the manufacturer's name and material identification and installed R – Value.
- All contractors and sub-contractors must have on file with the building department, a list of all such contractors and sub-contractors with appropriate current business

license numbers.

- All materials and workmanship shall be new and the best of its class and kind.
- I. All piping in public spaces, except for the fire risers, shall be concealed throughout.
- All reasonable effort shall be made by the contractor to minimize noise and other adverse impacts on the operation of adjacent businesses and residences. All construction parking and deliveries shall be confined to the site.
- All sub trades and material suppliers shall have, in place, an approved OSHA safety plan prior to performing work or visiting the building site.
- All subcontractors, related trades and supplies shall cooperate and provide an overal management of time and work progress so as no delays or loss of time will occur. The general contractor is responsible for the overall coordination of the general
- All trade names specified on any drawings, may be changed for another approved equal upon the expressed approval of the architect.
- Annular spaces around pipes, electric cables, conduits or other openings in sole/bottom plates at exterior walls will be rodent-proofed by closing such openings with cement mortar, concrete masonry, or similar method acceptable to the enforcing
- ). Before the building may be occupied, installation certificates for manufactured devices regulated by the appliance standards or certificates for manufactured devices regulated by the appliance standards of 2019 CMC and 2019 CBC, shall be posted adjacent to the building permit(s). Certificates shall: - Identify features required to verify compliance with the appliance standards.
- -Include a statement indicating that the installed devices conform to the appliance standards and the requirements for such devices given on the plans and specification approved by the local enforcement agency. - State the number of building permits under which the construction or installation was performed.
- 1. Contractor is responsible for scheduling inspections by the building department and other agencies as required.
- 2. Contractor shall follow all applicable industrial safety regulations. The local governing agency, owner, architect, and engineer are not responsible for the overall coordination & management of work.
- Contractor shall obtain all necessary building permits from the local building department prior to construction. Contractor shall contact local building department for all required inspections. An approved set of plans shall be kept on the job site at
- 4. Contractor to coordinate with the owner(s) regarding the selection of any items not specified in these plans, including but not limited to: Kitchen appliances, bathroom specialties, cabinetry, interior finishes, floor finishes, hardware and electrical fixtures.
- 15. Contractor to provide manufacturer instructions at job site for inspection.
- 16. Do not scale drawings. Written dimensions shall have precedence over scale of drawings. Dimensions are to face of footing or face of studs, unless noted otherwise.
- 7. Doors and windows between conditioned and unconditioned spaces shall be designed to limit air leakage into & from the building envelope. - Manufactured doors and windows shall have air infiltration rates certified by the manufacturer and not exceeding those shown in the regulations. - Site construction doors and windows, exterior joint and openings in the building envelope shall be caulked, gasketed, weather - stripped or otherwise sealed. Exception Fire rated doors and windows, unframed glass doors, and exterior elevation shaft ventilation dampers are also not required.
- 8. Dust control shall be maintained to the satisfaction of the agency of record at the time of rough installation or during storage on the constuction site and until final startup of the heating and cooling equipment. All duct and other related air distribution component openings shall be covered with tape, plastic, sheetmetal or other methods accepteable to the enforcing agency to reduce the amount of dust or debris which may collect in the system.
- 19. Each contractor shall clean up and remove from the site all waste materials and debris which may be accumulate on the site or in the building. Final clean-up of all surfaces and removal of foreign substances from the job site is the responsibility of the general contractor.
- 0. In the event of found materials suspected to be of an archaeological or paleontological nature, all grading and excavation shall cease in the immediate area and the appropriate authorities to be notified by the contractor. Any finds shall be left untouched until an evaluation by a qualified archaeologist or paleontologist is
- 1. It is the contractor's responsibility to ensure that details required by the various codes, but not specifically in these plans, be completed according to the codes.
- 22. Larger scale drawings shall take precedence over smaller scale drawings. Details shall take precedence over plans and sections.

23. Mechanical equipment shall be screened with paint or building materials and colors

- complimentary to the building.
- 24. No work shall be performed from these construction documents until they are approved by the appropriate regulatory agencies.
- 25. Notes on drawings shall take precedence over separate specifications. 26. Nothing in these drawings shall be construed to permit an installation in violation of
- 7. Storm water drainage and retention during construction: Refer to civil and site plan

in order to comply with applicable requirements, the contractor shall notify the

applicable codes and or restrictions. Should any changes in the drawings be needed

architect at once and cease work on all parts of the construction which are affected.

- for mandatory site development measures. 28. Sub-contractor shall provide Title 24 approvals & guarantees for all assemblies. 29. The bid submittal, by the contractor, represents that he is familiar with the local conditions under which the work is to be performed, and fully understands the
- 30. The contract drawings and specifications represent the finished structure; unless otherwise shown, they do not indicate the method of construction. Each contractor shall supervise and direct his work and be solely responsible for all construction means, methods and procedures in accordance with generally accepted construction

facilities, difficulties and restrictions related to the execution of the work for this

- . The contractor shall follow all applicable industrial safety regulations. The local governing agency, the architect, and the owner shall not be responsible for enforcing
- 2. The issuance or granting of a permit or approval of plans, specifications and computations shall not be construed to be a permit for, or an approval of, any violation of any of the provisions of the codes or of any other ordinance of this jurisdiction. Permits
- presuming to give authority to violate or cancel the provisions of this code or other ordinances of this jurisdiction shall not be valid.

33. This permit shall expire by limitation if work authorized under this permit is not

a period exceeding 180 days after work has commenced. 34. This set of plans shall be on the job site at all times during construction. All work shall be done in accordance with the approved plans. No changes or revisions to the approved plans or specifications shall be permitted unless submitted to and approved by the building official. The issuance of a permit shall not prevent the building official

from requiring the correction of errors or omissions from the approved plans and

commenced within 180 days from the date of issuance or if the work is suspended for

85. Typical details shall apply to all possible conditions unless noted otherwise. Typical details and typical notes are minimum requirements to be used when specific

specifications.

- 36. Verification: The contractor is responsible for verifying all grades, flowlines, points of connections and dimensions prior to start of construction. Architect shall be notified of any discrepancies or changes in plans. Deviations by contractors are done at contractor's own risk. In the event that any further data, information, or clarification of these drawings is required, it is the responsibility of the contractor to contact the Architect & inform her of any ambiguity, inconsistency, discrepancy, or error found within this set of drawings before continuing with construction.
- . Where a manufacturer is indicated for a specific item, install the specified item per manufacturer's recommendations.

## **GENERAL ARCHITECTURAL NOTES**

- A Certificate of Construction: Compliance based on observation of construction shall be submitted to the building department and shall be signed by the contractor at the time of final inspection.
- 2. All concealed plumbing joints shall be non slip connections.
- All exterior and interior doors shall be standard height 6'8" unless noted otherwise. Set all frames true and plumb. Fit all door hardware and remove for painting and staining. Max. floor level change is 1/2" (including threshold) at all exterior doors to landing unless noted otherwise.
- 4. All exterior swinging doors and windows shall be completely weather stripped.
- 5. All hallways to be a minimum of 36" wide finish to finish.
- 6. All hardware including (but not limited to) door latches, hinges, cabinetry hardware, light fixtures (color, type and finish), switch plates, outlets (color and type) shall be chosen by the owner. Owner shall verify all locations and heights of all outlets, lighting fixtures, etc.
- All interior finishes, chosen by the owner, must conform to the requirements of Chapter 8 of the 2019 CBC & CalGreen Codes
- . All kitchen and bathroom fixtures and appliances shall be chosen by the owner.
- 9. All operable portions of window shall have bug screens, including sliding glass doors, unless noted otherwise.
- 10. All plumbing walls shall be 2 x 6 studs, min.
- 11. All stairways shall have a landing measured in the direction of travel equal to or greater than the width of the stairway to 44" max. All stairs shall have min. headroom clearance of 6'-8" above the nosing.
- 12. All tub and shower enclosures shall be tempered or safety glass.
- 13. All water closet compartments shall be min. 15" from its center to a side wall or obstruction or closer than 30" center to center to a similar fixture. The clear space in front of a water closet, lavatory, or bidet shall not be less than 24". No urinal shall be set closer than 12" from its center to a side wall or partition or closer than 24" center to center. [CPC 402.5]
- 14. All windows and sliding and swinging glass doors shall be dual glazed unless noted
- 15. All windows and sliding glass doors shall meet the requirements of CEnC 110.6(a)1and shall be certified and labeled.
- 16. Any floor areas to receive carpet and pad or resilient flooring shall be left clean, dry, and dust free.
- side with (1) one layer 5/8" type 'x' gyp. wallboard w/2 @ 16" o.c. nailers @ edge / field (solid blocked continuous). 18. Erosion and sediment control best management practices must be in place and

17. Enclosed usable space under interior stairway is to be protected on the enclosed

- functional prior to the first inspection. No inspections can be performed if they are not in place or have failed to provide erosion control. 19. Exterior swinging doors shall be equipped with a dead bolt, key operated from
- 20. Fireplaces shall have a minimum of 19'-6" from base of fireplace to top of chimney. Chimneys shall be either 12"x12" clay flue tiles ( maximum 10"x10" I.D.) or round 10" I.D. clay or refractory flue tiles. A 10" round insulated "Class A" metal chimney (UL103HT rated) is also allowed.

outside and manually operated from the inside without the use of a key or any special

- 21. Floor and wall finishes of closets to match that of the adjacent room unless noted
- 22. For vinyl over wood floors, provide 3/8" particle board underlayment. 23. Gas vents and non combustible piping, in walls, passing through three floors or less, shall be effectively draft stopped at each floor or ceiling.
- 24. Toilet, bathing and shower room floor finish materials shall have a smooth, hard, nonabsorbent surface. The intersections of such floors and walls shall have a smooth, hard, non-absorbent vertical base that extends upward onto the walls not less than 4 inches. [CBC 1209.2.1]
- 25. Heating and cooling equipment located in garage which generates a glow, spark or flame capable of igniting flammable vapors shall be installed with pilots and burners or heating elements and switches at least 18" above the floor level.
- 26. Height to combustible materials above kitchen ranges shall be a min. 30" when unprotected, 24" when unprotected.
- 27. Inactive leaf of double doors shall have a hardened deadbolt top and bottom with 1/2' min. embedment.
- 28. Mechanical and plumbing systems are to be designed to meet T-24 Requirements. Contractor shall install equipment that follows duct layout and meets the min rating as indicated in the Certified T-24 Documentation.
- 29. Min. net clear opening height dimension shall be 24", minimum net clear opening width shall be 20 inches. The net clear opening dimensions shall be a result of normal operation of the opening. [2019 CBC 1030.2.1] Maximum sill height for emergency egress windows to be 44" above finished floor. [2019 CBC 1030.3] If room is below grade, provide window well per 2019 CBC 1030.4.
- 30. Minimum headroom clearance for stairway should be no less than 80". This measurement is from a plane tangent to the stairway tread nosing per 2019 CBC 1011.3. The minimum clearance shall be maintained thge full width of the stairway and landing.
- 31. No construction materials containing asbestos may be used on this project. 32. Penetration of fire-resistant walls, floor ceilings and roof ceilings shall be protected as
- 33. Provide attic access for roof attics having over 30 inches clear height. Access opening to be a minimum of 20" x 30". Clear headroom of not less than 30 inches shall be provided in the attic space at or above the access opening. [2019 CBC

required in 2019 CBC 714.

- 34. Provide gypsum board when required (1/2" over framing members with 16" o.c. spacing, 5/8" over framing members with 24" o.c spacing) with texture over assembly. Verify texture with owner.
- 35. Safety glazing requirements per 2019 CBC 2406 in areas subject to human impact.
- 36. Shower & tub shower combinations shall have individual control valves of the pressure balance or thermostatic mixing valve type.
- 37. Skylights shall be flat with clear or bronze glazing. Bubble or dome skylights with frosted or colored glazing are prohibited
- 38. The building described on the following pages may be required to be equipped with a fire sprinkler system. Shop drawings shall be submitted and approved by the county building and fire department prior to installation of the system. System design shall meet all requirements of State Fire Marshall, NFPA and County regulations. Sprinkler shop drawings shall be submitted and approved prior to rough framing inspection.
- 39. The California Energy Conservation: Standards for residential buildings have been reviewed and the building described on these pages is in substantial conformance. The Energy Pro by EnergySoft computer program has been used to perform calculations. This program is authorized by the CA Energy Commission for use with the second generation non residential building energy efficiency standards. Second generation residential occupancies, complying with this program conform to the results produced by the public domain point system.
- 40. The owner is to secure the proper occupancy permits prior to occupying the building.
- 41. Wall and ceiling materials shall not exceed the flame spread classification in the 2019 CBC Table 803.13. See 2019 CBC 803.1.2 for classification. 42. Water pressure in buildings shall be limited to 80 psi or less.

# CITY OF PASO ROBLES GENERAL NOTES

1. 01. Contact the Public Works Inspection hotline within a 48 hour notice for any required encroachment permit inspections or final inspection. 02. Within city easements for connections to public utilities, water sewer, and fire service laterals, curb, gutter, and sidewalk, driveway approaches, sidewalk underdrains, storm drain improvements, street tree planting or pruning, curb ramps, street paving, and pedestrain protection or construction staging in the right-of-way. 03. All work located within the public right-of-way or within jurisdiction of the city utilities and public works departments shall comply with the most current edition of the Engineering Standards and Specifications. 04. Any sections of damaged or displaced curb, gutter and sidewalk or driveway

approach shall be repaired or replaced to the satisfaction of the public works director.

# FIREBLOCKING GENERAL NOTES

fire-resistance rating

- 714.1.1 DUCTS AND AIR TRANSFER OPENINGS Penetrations of fire-resistance-rated walls by ducts that are not protected with to be protected with fire dampers by other sections of this code, shall comply with Sections 714.5 through 714.6.2. Ducts and air transfer openings that are protected with dampers shall comply with Section 717.
- 2. 714.4.1 THROUGH PENETRATIONS Through penetrations of fire-resistance-rated walls shall comply with Section 714.4.1.1 or 714.4.1.2.
- annular space between the penetrating item and the fire-resistance-rated wall is permitted to be protected by either of the following measures: 144 square inches (0.0929 m2), concrete, grout or mortar is permitted where it is installed the full thickness of the wall or the thickness required to maintain the
- hot gases sufficient to ignite cotton waste when subjected to ASTM E119 or UL 263 time-temperature fire conditions under a minimum positive pressure differential of 0.01 inch (2.49 Pa) of water at the location of the penetration for the time period equivalent to the fire-resistance rating of the construction penetrated.
- . 714.4.1.1 FIRE RESISTANCE-RATED ASSEMBLIES Through penetrations shall be protected using systems installed as tested in the
- 714.4.1.2 THROUGH PENETRATION FIRESTOP SYSTEM installed as tested in accordance with ASTM E814 or UL 1479, with a minimum positive pressure differential of 0.01 inch (2.49 Pa) of water and shall have an F
- . 714.4.2 MEMBRANE PENETRATIONS
- EXCEPTION: 1. Membrane penetrations of maximum 2-hour fire-resistance-rated walls and
- Such boxes on opposite sides of the wall or partition shall be separated by one of the 1.1 By a horizontal distance of not less than 24 inches (610 mm) where the wall or partition is constructed with individual noncommunicating stud cavities.
- wall cavity is filled with cellulose loose-fill, rockwool or slag mineral wool insulation. 1.3 By solid fireblocking in accordance with Section 718.2.1 1.4 By protecting both outlet boxes with listed putty pads. 1.5 By other listed materials and methods.
- boxes have been tested for use in fire-resistance-rated assemblies and are installed in accordance with the instructions included in the listing. The annular space between the wall membrane and the box shall not exceed 1/8 inch (3.1 mm) unless listed otherwise. Such boxes on opposite sides of the wall or partition shall be separated by one of the following: 2.1 By the horizontal distance specified in the listing of the electrical boxes.
- 2.2 By solid fireblocking in accordance with Section 718.2.1. 2.3 By protecting both boxes with listed putty pads 2.4 By other listed materials and methods.
- fire-resistance-rated assemblies and are installed in accordance with the instructions included in the listing. 4. Membrane penetrations by boxes other than electrical boxes, provided that such penetrating items and the annular space between the wall membrane and the box, are protected by an approved membrane penetration firestop system installed as tested in accordance with ASTM E814 or UL 1479, with a minimum positive pressure
- 5. The annular space created by the penetration of an automatic sprinkler, provided it is covered by a metal escutcheon plate. 6. Membrane penetrations of maximum 2-hour fire-resistance-rated walls and partitions by steel electrical boxes that exceed 16 square inches in area, or steel electrical boxes of any size having an aggregate area through the membrane exceeding 100 square inches in any 100 square feet of wall area, provided that such penetrating items are protected by listed putty pads or other listed materials and
- . 714.4.3 DISSIMILAR MATERIALS
- the wall is maintained.

accordance with their listing.

- 1. Two-inch nominal lumber. 2. Two thicknesses of 1-inch nominal lumber with broken lap joints.
- 0.719-inch wood structural panels. 4. One thickness of 0.75-inch particleboard with joints backed by 0.75-inch particle-board.
- 6. One-fourth-inch cement-based millboard. 7. Batts or blankets of mineral wool, mineral fiber or other approved materials installed in such a manner as to be securely retained in place.
- 718.2.1.1 BATTS OR BLACKETS OF MINERAL WOOL OR MINERAL FIBER shall be permitted for compliance with the 10-foot (3048 mm) horizontal fireblocking in walls constructed using parallel rows of studs or staggered studs.
- 718.2.1.2 UNFACED FIBERGLASS insulation shall be packed tightly around the obstruction.
- hot gases. 11. 718.2.2 - CONCEALED WALL SPACES Fireblocking shall be provided in concealed spaces of stud walls and partitions,
- Fireblocking shall be provided at interconnections between concealed vertical stud wall or partition spaces and concealed horizontal spaces created by an assembly of floor joists or trusses, and between concealed vertical and horizontal spaces such as occur at soffits, drop ceilings, cove ceilings and similar locations.

# **SUB-CONTRACTOR REPRESENTATION**

- be taken as prima facie evidence of compliance with this condition.
- Each sub-contractor shall thoroughly examine and be familiar with the drawings and
- The bid submittal, by the sub-contractor, represents that he is familiar with the local conditions under which the work is to be performed, and fully understands the facilities, difficulties and restrictions related to the execution of the work for this
- or the contract. No additional charges will be allowed because of lack of such knowledge. The submission of the sub-contractor's bid shall be taken as prima facie evidence of compliance with this condition.
- The sub-contractor shall field certify all elevations, flow lines and points of connections before beginning work and shall notify the architect of any
- The sub-contractor shall visit the site before submitting his bids and verify all existing

. The sub-contractor shall verify all dimensions before beginning any work and shall

- dampers shall comply with Sections 714.3 through 714.4.3. Penetrations of horizontal assemblies not protected with a shaft as permitted by Section 717.6, and not required
- EXCEPTION: Where the penetrating items are steel, ferrous or copper pipes, tubes or conduits, the 1. In concrete or masonry walls where the penetrating item is a maximum 6-inch (152 mm) nominal diameter and the area of the opening through the wall does not exceed
- 2. The material used to fill the annular space shall prevent the passage of flame and
- approved fire-resistance-rated assembly.
- Through penetrations shall be protected by an approved penetration firestop system rating of not less than the required fire-resistance rating of the wall penetrated.
- Membrane penetrations shall comply with Section 714.4.1. Where walls or partitions are required to have a fire-resistance rating, recessed fixtures shall be installed such that the required fire-resistance will not be reduced.
- partitions by steel electrical boxes that do not exceed 16 square inches (0.0 103 m2) in area, provided the aggregate area of the openings through the membrane does not exceed 100 square inches (0.0645 m2) in any 100 square feet (9.29 m2) of wall area. The annular space between the wall membrane and the box shall not exceed 1/8 inch (3.1 mm).
- 1.2 By a horizontal distance of not less than the depth of the wall cavity where the
- 2. Membrane penetrations by listed electrical boxes of any material, provided such
- 3. Membrane penetrations by electrical boxes of any size or type, that have been listed as part of a wall opening protective material system for use in
- differential of 0.01 inch (2.49 Pa) of water, and shall have an F and T rating of not less than the required fire-resistance rating of the wall penetrated and be installed in
- methods, and installed in accordance with the listing.
- Noncombustible penetrating items shall not connect to combustible items beyond the point of firestopping unless it can be demonstrated that the fire-resistance integrity of
- 718.2.1 FIREBLOCKING MATERIALS Fireblocking shall consist of the following materials:
- 3. One thickness of 0.719-inch wood structural panels with joints backed by
- 5. One-half-inch gypsum board.
- 8. Cellulose insulation installed as tested for the specific application. Batts or blankets of mineral wool or mineral fiber or other approved nonrigid materials
- Unfaced fiberglass batt insulation used as fireblocking shall fill the entire cross section of the wall cavity to a minimum height of 16 inches (406 mm) measured vertically. Where piping, conduit or similar obstructions are encountered, the
- 10. 718.2.1.3 LOOSE-FILL INSULATION MATERIAL Loose-fill insulation material, insulating foam sealants and caulk materials shall not be used as a fireblock unless specifically tested in the form and manner intended for use to demonstrate its ability to remain in place and to retard the spread of fire and
- including furred spaces, and parallel rows of studs or staggered studs, as follows: Vertically at the ceiling and floor levels. - Horizontally at intervals not exceeding 10 feet (3048 mm). 12. 718.2.3 - CONNECTIONS BETWEEN HORIZONTAL AND VERTICAL SPACES

- Each sub-contractor shall be totally familiar with pertinent rules and regulations of government bodies having jurisdiction, state of labor, materials markets, and shall make due allowance for all contingencies. No additional charges will be allowed because of lack of such knowledge. The submission of the sub-contractor's bid shall
- related specifications.
- The failure of any sub-contractor to receive or examine any form, instrument, or other document, or to visit the site as necessary, and become acquainted with the existing conditions, shall in no way relieve them from their obligations with respect to their bid
- notify the architect of any discrepancies.

- PLUMBING NOTES
- All pipe systems must be supported according to guidelines for seismic restraint of
- mechanical systems and plumbing piping systems, most currently adopted edition, published by SMACNA and PPIC.
- All plumbing fixtures and fittings shall be installed in accordance with the 2019 CBC
- and the 2019 CPC. At penetrations through fire rated membranes not larger than a nominal four inch pipe
- size or sixteen square inches in overall cross sectional area containing noncombustibles, fill the void with an approved material to prevent the passage of flames and hot gasses, fire and smoke resistance of the filler material must be equal to or greater than the fire or smoke resistance of the surrounding membrane. The material must be a tested assembly approved by the fire marshal and it must provide the necessary 'T' or 'F' rating appropriate for the installation.
- Gas piping materials shall be per 2019 CPC 1208.6. Water piping shall be per 2019
- Gas vents and non-combustible piping in walls, passing through three floors or less shall be effectively draft stopped at each floor or ceiling.
- Hose bibbs and lawn sprinkler systems shall have approved backflow prevention devices per 2019 CPC 603. Hot water lines shall be insulated.
- . If a sprinkler system is proposed, the contractor shall submit plans and calculations for fire sprinkler system per NFPA 13-D Standards and Specifications, to the fire department for review and approval prior to installation. Plumbing contractor to verify the local water main flow rate and static and residual pressure prior to the design. The water service line from the street to the water meter must be sized to provide adequate flow and pressure to support the 13-D system. The system shall also meet all requirements set forth by 2019 CFC 903.3.5.
- . If water pressure exceeds 80 psi, a pressure regulator is required per 2019 CPC
- 10. In showers and shower-tub combinations, control valves must be pressure balanced or thermostatic mixing valves per 2019 CPC 417.0.
- . Indoor water use shall be demonstrated by the prescribed method: A calculation demonstrating a 20% reduction in building "water use" baseline as established in 4.303 per 2019 CalGreen Code shall be provided. The calculation shall be limited to water closets, urinals, lavatory faucets and showerheads.
- Install plumbing fixtures at mounting heights and with anchorages recommended by 13. Install pressure relief valves with drain to outside at water heaters. 2019 CPC 608.
- 4. Insulation applied to piping in attic or wall cavities must be 1-1/2" thick with vapor barrier. Insulation must be one pound per cubic floor density and shall not exceed a flame spread of 25 & smoke developed rating of 50 when tested as a composite system including insulation, facing materials, tapes & adhesives as normally applied.
- 5. Minimum size for service risers for structures shall be 1" diameter. Materials shall be schedule 40 pvc or type "I" copper pipe, min.
- 16. Minimum slope of sanitary lines to be 1/4" per foot per 2019 CPC 708. 7. Plumbing contractor shall coordinate all piping and equipment installation with other trades and structural components prior to installation. Conflicts must be resolved prior to installation. Where conflicts exist, contractor is required to develop shop drawings
- to assist the architect with conflict resolution. 8. Plumbing loops shall be provided for water softeners, which may be exchange type
- 19. Pressure test all water lines and gas lines prior to covering or closing in construction.

only; irrigation and hose bibs are not to be served by water softeners.

20. Refer to 'C-sheets' for connection to public utilities, if applicable. 21. Roof/deck drain and overflow piping within the building shall utilize approved

drainage fittings. Roof/deck drains and overflows (fixtures) shall be IAPMO listed.

- 22. The contractor is required to seal all penetrations through fire walls, smoke walls, fire/smoke walls or ceiling assemblies with approved flame and smoke resistant sealant. Materials used for sealing must be approved by the California State Fire Marshal and installation must be according to the manufacturer's approved details.
- 23. The contractor must determine in advance of commencing work that existing water flows, pressures and invert elevations are sufficient to meet requirements of the
- 24. Trap primers shall be installed at all lavatories. 25. Water heater shall be strapped within 1/3 of the top and bottom of the heater and the

straps shall be a minimum of 4" away from the water heater controls.

MAXIMUM FIXTURE FLOW RATE AT ≥ 20% REDUCTION							
SHOWERHEADS	1.8 gpm @ 80 psi						
MULTIPLE SHOWER HEADS	Single valve not to exceed 1.8 gpm @ 80 psi						
LAVATORY FAUCETS, RESIDENTIAL	1.2 gpm @ 60 psi (1)						
KITCHEN FAUCETS*	1.8 gpm @ 60 psi (3)						
GRAVITY TANK-TYPE WATER CLOSETS	1.28 gallons/flush (4)						
FLUSHOMETER TANK WATER CLOSETS	1.28 gallons/flush (4)						
FLUSHOMETER VALVE WATER CLOSETS	1.28 gallons/flush (4)						
ELECTROMECHANICAL HYDRAULIC WATER CLOSETS	1.28 gallons/flush (4)						

- **MECHANICAL NOTES** Adjust equipment, ducts, necks, grilles and registers for proper volume and distribution of air: Air velocity passing through necks shall not exceed 800 fpm on low
- All 90° turns in flex duct shall have sheet metal elbows. 3. All duct work to be ridged sheet metal and flex type in sizes to provide a complete, quiet air flow system with insulation R-value based on Table E 503.7.2 per 2019
- All flex duct shall be Class 1. Flex duct to be used at connection to grills only. Set
- back thermostats shall be 'honeywell' #T8082A or approved equal. All mechanical work shall conform with the 2019 CMC based on 2018 UMC.
- 6. All penetrations through roof shall be guaranteed to be weatherproof. . All plenums exposed to outside shall be lined with 1" glass fiber.

10. Clearances for furnace and water heater shall be per 2019 CMC 906.7.

- 8. All sheet metal to attic shall be wrapped with 1-1/2" fiberglass blanket. 9. All substitutions to be approved by owner and Architect.
- 11. Clothes dryer shall be vented directly to the outside and shall be equipped with a backdraft damper. (2019 CMC-504.4)
- 13. Duct tape, meeting the requirements of UL181, 181A or 181B, shall be used or additional duct attachment devices will be required for installing mechanical ducting.

12. Duct layout shall be submitted to the Architect in the form of shop drawing for

- 14. Gas vents and non-combustible piping in walls passing through three floors or less shall be effectively draft stopped at each floor or ceiling per 2019 CBC. 15. Mechanical contractor shall be responsible for complete system installation per all 6. Mechanical contractor shall carefully coordinate mechanical installations with the
- clearances for all installations within wall and floor framing space. Any conflicts or discrepancies shall be brought to the immediate attention of the architect for resolution prior to proceeding with work. 7. Plumbing contractor shall size gas line to FAU units per 2019 CPC within 36" of

general contractor, electrical contractor and plumbing contractor to assure adequate

- 8. Pressure absorbing devices or approved mechanical devices are required on water lines, located as close as possible to quick acting valves, that will absorb high pressures resulting from quick closing of quick-acting valves.
- 9. Sheet metal ducts shall be fabricated in accordance with CMC and SMACNA 20. Sheet metal ducts shall be fabricated in accordance with CMC and SMACNA

21. Subcontractor shall provide duct and register layout for Architect approval.

22. The point of discharge of mechanical venting systems shall be at least 10 feet from any opening which allows air entry into occupied portions of the building (2019 CMC 407.2.2). Discharge shall be located at least 25 feet from exhaust outlets (2019 CMC

23. The return air plenum serving the mechanical equipment must be fully ducted from

24. Water heater or furnace exhaust flues running up walls shall be type B, double wall

metal vents, UL listed, installed with full clearance from combustible materials as

the equipment to the conditioned space. Drop ceilings, wall cavities, & equipment

recommended by vent manufacturer. 25. Where possible, combine vent runs to limit penetrations through roof.

platforms may not be used as plenums.

# **INDOOR AIR QUALITY**

- 01. Whole House Exhaust Fans - All dwelling units shall meet the requirements of ANSI/ASHRAE standard 62.2 ventilation and acceptable indoor air quality in low-rise residential buildings. - The whole house shall have an exhaust fan ducted to the outside with a minimum ventilation rate calculated according to ASHRAE standard 62.2 equation 4.1(a): REFER TO FORMULA ON SHEET E1.0 - Ducting shall be sized according C. to ASHRAE standard 62.2 table 7.1. - One of the local exhaust fans in a bathroom or kitchen may be used, provided the
- exhaust fan meets the minimum ventilation rates for both the local and whole house ventilation requirements - All continuously operating fans shall be rated at a maximum of 1.0 sone. Intermittently operated whole-building ventilation fans shall be rated at a maximum of - The exhaust fan control(s) used for whole-building continuous operation is labeled to communicate the required continuous building ventilation function and importance with a statement to make clear how the control (e.g., on/off switch) is to be operated.
- At a minimum, the label should communicate: "to maintain minimum levels of outside air ventilation required for good health, the fan control should be on at all times when the building is occupied, unless there is severe outdoor air contamination." It is recommended that the label text should be in bold type, placed on a white background, and no smaller than the equivalent of Arial 12 point type.
- 02. Bathroom Exhaust Fan For the purposes of this section, a bathroom is a room which contains a bathtub,
- shower, or tub/shower combination. - Exhaust fans that are ENERGY STAR-compliant , ducted and that terminate outside the building will be provided in every bathroom. (2019 CGC) - Specify CFM of the bathroom fan and it will be used for required whole house ventilation. Each bathroom shall be mechanically ventilated for purposes of humidity. The minimum local exhaust rates hall be 50 cfm for intermittent ventilation or 20 cfm for continuous ventilation. (2019 CMC Table 403.7) (2019 CGC 5.506) - Buildings shall meet or exceed the provisions of California Building Code, CCR,
- 3. 03. Kitchen Exhaust Fans Each kitchen shall have an exhaust fan ducted to the outside with a minimum

Title 24, Part 2, Sections 1202 (Ventilations) and Chapter 14 (Exterior Walls).

62.2 table 7.1 4. 04. Local Exhaust Fan All ceiling mounted intermittent local ventilation fans have a sound rating of three sones or less at the required airflow rate. All intermittent local ventilation exhaust fans have been designed to be operated as needed by the occupant. At a minimum, a wall

ventilation rate of 100 cfm. The ducting shall be sized according to ASHRAE standard

humidity sensors, or occupancy sensors may be used. 5. Air inlets (not exhaust) shall be located away from known contaminants. Air inlets (not

switch may be used. Alternatively, some other type of control such as shut off timers,

- exhaust) shall be located away from known contaminants. 6. Air moving equipment used to meet either the whole-building ventilation requirement or the local ventilation exhaust requirement shall be rated in terms of airflow and
- Combustion appliances shall be properly vented and air systems shall be designed to prevent back drafting. Mechanical systems supplying air to occupiable space through ductwork shall be provided with a filter having a minimum efficiency of MERV 6 or better.

9. The wall and openings between occupiable spaces and the garage shall be sealed.

HVAC systems that include air handlers or return ducts located in garages shall have

total air leakage of no more than 6% of total fan flow when measured at 0.1 in. w.c. using California Title 24 or equivalents. 10. Ventilation air shall be provided directly from the outdoors and not as transfer air from adjacent dwelling units or other spaces, such as garages, unconditioned

# ENVIRONMENTAL QUALITY

crawlspaces, or unconditioned attics.

- 5.504.3 COVERING OF DUCT OPENINGS AND PROTECTION OF MECHANICAL **EQUIPMENT DURING CONSTRUCTION.** At the time of rough installation and during storage on the construction site until final startup of the heating, cooling and ventilating equipment, all duct and other related air distribution component openings shall be covered with tape, plastic, sheet metal or other methods acceptable to the enforcing agency to reduce the amount of dust, water and debris which may enter the system.
- . 5.504.4.4 CARPET SYSTEMS: All carpet installed in the building interior shall meet at least one of the following testing and product requirements: 1. Carpet and Rug Institute's Green Label Plus Program; 2. Compliant with the VOC-emission limits and testing requirements specified in the California Department of Public Health Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using
- Standard Method V1.1 or Specification 01350); 3. NSF/ANSI 140 at the Gold level or higher; 4. Scientific Certifications Systems Sustainable Choice; or 5. Compliant with the Collaborative for High Performance Schools California (2014 CA-CHPS) Criteria and listed in the CHPS High Performance Product Database. 5.504.4.4.1 All carpet cushion installed in the building interior shall meet the requirements of the Carpet and Rug Institute's Green Label program.

Environmental Chambers, Version 1.1, February 2010 (also known as CDPH

5.504.4.4.2 All carpet adhesive shall meet the requirements of Table 5.504.4.1.

5.504.4.6 RESILIENT FLOORING SYSTEMS, TIER 1: For 80 percent of floor area receiving resilient flooring, installed resilient flooring shall meet at least one of the following: 1. Certified under the Resilient Floor Covering Institute (RFCI) FloorScore program; 2. Compliant with the VOC-emission limits and testing requirements specified in the California Department of Public Health's 2010 Standard Method for the Testing and Evaluation Chambers, Version 1.1, February 2010; 3. Compliant with the Collaborative for High Performance Schools California (2014

CA-CHPS) Criteria and listed in the CHPS High Performance Product Database; or

Children's & Schools Program). 4. 5.504.4.6.1 VERIFICATION OF COMPLIANCE.

4. Products certified under UL GREENGUARD Gold (formerly the Greenguard

Documentation shall be provided verifying that resilient flooring materials meet the pollutant emission limits. 5.504.4 FINISH MATERIAL POLLUTANT CONTROL Adhesives, sealants and caulks used on the project shall meet the requirements of the following standards: 1. Adhesives, adhesive bonding primers, adhesive primers, sealants, sealant primers and caulks shall comply with local or regional air pollution control or air quality management district rules where applicable, or SCAQMD Rule 1168 VOC limits, as

shown in Tables 5.504.4.1 and 5.504.4.2. Such products shall also comply with the

Rule 1168 prohibitiobn in the use of certain toxic compounds (chloroform, ethylene dichloride, methylene chloride, perchloroethylene and trichloroethylene), except for aerosol products as specified in subsection 2, below. 2. Aerosol adhesives, and smaller unit sizes of adhesives, and sealant or caulking compounds (in units of product, less packaging, which do not weigh more than one pound and do not consist of more than 16 fluid ounces) shall comply with statewide VOC standards and other requirements, including prohibition on use of certain toxic compounds, of California Code of Regulations, Title 17, commencing with Section

#### **TABLE 4.504.1** Adhesive Voc Limit - Less Water Less Exempt Compounds (In Grams Per Liter) ARCHITECTUAL APPLICATIONS VOC LIMIT (g/L less water) Indoor Carpet Adhesives

Carpet Pad Adhesives

Outdoor Carpet Adhesives

Porous Material (except Wood)

Wood Flooring Adhesives

Rubber Floor Adhesives	60
Subfloor Adhesives	50
Ceramic Tile Adhesives	65
Vct And Ashpalt Tile Adhesives	50
Drywall & Panel Adhesives	50
Cove Base Adhesives	50
Multipurpose Construction Adhesives	70
Structural Glazing Adhesives	100
Single-ply Roof Membrane	250
Other Adhesives Not Specifically Listed	50
SPECIALTY APPLICATIONS	
Pvc Welding	510
Cpvc Welding	490
Abs Welding	325
Plastic Cement Welding	250
Adhesive Primer For Plastic	550
Contact Adhesive	80
Special Purpose Contact Adhesive	250
Structural Wood Member Adhesive	140
Top And Trim Adhesive	250
SUBSTRATE SPECIFIC APPLICATIONS	
80	30
Plastic Foams	50

#### **TABLE 5.504.4.1** Adhesive Voc Limit - Less Water Less Exempt Compounds (In Grams Per Liter) ARCHITECTUAL APPLICATIONS VOC LIMIT (g/L less water) door Carpet Adhesives Carpet Pad Adhesives Outdoor Carpet Adhesives Nood Flooring Adhesives Rubber Floor Adhesives Subfloor Adhesives Ceramic Tile Adhesives /ct And Ashpalt Tile Adhesives Drywall & Panel Adhesives ove Base Adhesives Iltipurpose Construction Adhesives ructural Glazing Adhesives Single-ply Roof Membrane Other Adhesives Not Specifically Listed SPECIALTY APPLICATIONS Pvc Welding Cpvc Welding Abs Welding Plastic Cement Welding Adhesive Primer For Plastic Contact Adhesive Special Purpose Contact Adhesive tructural Wood Member Adhesive op And Trim Adhesive SUBSTRATE SPECIFIC APPLICATIONS prous Material (except Wood)

# TABLE 5.504.4.2

ADLL J.JUT.T.Z					
Sealant Voc Limit - Less Water Less Exempt Compounds ( In Grams Per Liter )					
Sealants	Current VOC Limit				
Architectural	250				
Marine Deck	760				
Nonmembrane Roof	300				
Roadway	250				
Signle-ply Roof Membrane	450				
Other	420				
Sealant Primer					
Architectural					
Non Porous	250				
Porous	775				
Modified Bituminous	500				

Architectural Coatings Voc Limit - Less Wate	r Less Exempt Compounds (in Grams Per Liter)
Coating Category	VOC Limit
Flat Coatings	50
Nonflat Coatings	100
Nonflat High Gloss Coatings	150
Specialty Coatings	
Aluminum Roof Coatings	400
Basement Specialty Coatings	400
Bituminous Roof Coatings	50
Bituminous Roof Primers	
	350
Bond Breakers	350
Concrete Curing Compounds	350
Concrete/Masonry Sealers	100
Driveway Sealers	50
Dry Fog Coatings	150
Faux Finish Coatings	350
Fire Resistive Coatings	350
Floor Coatings	100
Form-Release Compounds	250
Graphic Arts Coatings (Sign Paints)	500
High Temperature Coatings	420
Industrial Maintenance Coatings	250
Low Solids Coatings	120
Magnesite Cement Coatings	450
Mastic Texture Coatings	100
Metallic Pigmented Coatings	500
Multicolor Coatings	250
Pre-treatment Wash Primers	420
Primers, Sealers, And Undercoaters	100
Reactive Penetrating Sealers	350
Recycled Coatings	250
Roof Coatings	50
Rust Preventative Coatings	250
Shellacs	
Clear	730

#### Swimming Pool Coatings Traffic Marking Coatings Tub & Tile Refinish Coatings Vaterproofing Membranes Vood Coatings Wood Preservatives **TABLE 5.504.4.5**

Product

Specialty Primers, Sealers, And Undercoaters

#### MAXIMUM FIXTURE FLOW RATE AT ≥ 20% REDUCTION LAVATORY FAUCETS CHEN FAUCETS' RAVITY TANK-TYPE WATER CLOSETS

5.303.3.2 - URINALS

be in operation at a time.

LUSHOMETER TANK WATER CLOSETS

LUSHOMETER VALVE WATER CLOSETS

Hardwood Plywood Veneer Core

Medium Density Fiber Board

ardwood Plywood Composite Core

Opaque

Particle Board

Stone Consolidants

LECTROMECHANICAL HYDRAULIC WATER CLOSETS 1.28 gallons/flush (4) **INDOOR WATER USE** 

Formaldehyde Limits - Maximum Formaldehyde Emissions In Parts Per Million

0.5 gpm @ 60 psi (1)

0.5 gpm @ 60 psi (3)

1.28 gallons/flush (4)

1.28 gallons/flush (4)

1.28 gallons/flush (4)

5.303.3 - Plumbing fixtures (water closets and urinals) and fittings (faucets and showerheads) shall comply with the following: 5.303.3.1 - WATER CLOSETS The effective flush volume of all water closets shall not exceed 1.28 gallons per flush. Tank-type water closets shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Tank-Type Toilets.

Note: The effective flush volume of dual flush toilets is defined as the composite,

average flush volume of two reduced flushes and one full flush.

WALL-MOUNTED URINALS: The effective flush volume of wall-mounted urinals shall not exceed 0.125 gallons per flush. FLOOR-MOUNTED URINALS: The effective flush volume of floor-mounted or other urinals shall not exceed 0.5 gallons per flush. 5.303.3.3 - SHOWERHEADS SINGLE SHOWERHEADS: Showerheads shall have a maximum flow rate of not more than 1.8 gallons per minute at 80 psi. Showerheads shall be certified to the

performance criteria of the U.S. EPA WaterSense Specification for Showerheads.

by more than one showerhead, the combined flow rate of all showerheads and/or

other shower outlets controlled by a single valve shall not exceed 1.8 gallons per

MULTIPLE SHOWERHEADS SERVING ONE SHOWER: When a shower is served

minute at 80 psi, or the shower shall be designed to allow only one shower outlet to

than 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the

WASH FOUNTAINS: Wash fountains shall have a maximum flow rate of not more

flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and

Note: A hand-held shower shall be considered a showerhead. 5.303.3.4 - FAUCETS AND FOUNTAINS NONRESIDENTIAL LAVATORY FAUCETS: Lavatory faucets shall have a maximum flow rate of not more than 0.5 gallons per minute at 60 psi. KITCHEN FAUCETS: Kitchen faucets shall have a maximum flow rate of not more

must default to a maximum flow rate of 1.8 gallons per minute at 60 psi.

than 1.8 gallons per minute/20 [rim space (inches) at 60 psi].



ARCHITECT STAMP CONSULTANT S

Craig Archer 3030 Ramada Drive, Paso Robles CA

oble 0

93

03 JUN 22 DEVELOPMENT PLAN RESUBMITTAL

AGENCY APPROVAL

JOB NUMBER

2138

**GENERAL** 

# **Geotechnical Engineering and Percolation Report**

# **Proposed Commercial Building and Associated**

## Improvements Theatre Drive - APN: 009-851-022

Paso Robles, California

March 8, 2022 H-211472

Prepared For: Craig Archer

Hallin Geotechnical, Inc. Atascadero, California

March 8, 2022

H-211472

H-211472

Project Manager INTRODUCTION

# A. Project Description

This report presents results of a Geotechnical Engineering and Percolation Study performed for the proposed tilt-up concrete commercial building to be located at the southwest corner of Theater Drive and Nutwood Circle in the City of Paso Robles, California.

1. We anticipate that the site will be developed by grading minor cuts and fills to construct a relatively level building pad. 2. The proposed commercial building will be a concrete tilt-up

structure with an approximate 4,700 sq. ft. footprint. The structure is to be of reinforced concrete construction supported by a conventional perimeter footing/slab-on-grade foundation system. Related improvements will include a new parking lot and driveway, on-site infiltrator drainage system and connection to utilities present at or near the property.

3. Structural considerations for maximum wall loads of 3.0 kips per lineal foot and point loads of 30 kips were used as a basis for the recommendations of this report. If actual loads vary significantly from these assumed loads, this firm should be notified as reevaluation of the recommendations contained herein may be

## B. <u>Purpose and Scope of Work</u>

The purpose of the geotechnical investigation that led to this report was to evaluate the soil conditions of the site with respect to the proposed commercial building. These conditions include surface and subsurface soil types, expansion potential, and settlement potential, bearing capacity and the presence or absence of subsurface water. The scope of our work included:

- Reconnaissance of the site. 2. Drilling, sampling and logging from 8 borings to investigate soils and groundwater conditions.
- 3. Laboratory testing of soil samples obtained from subsurface exploration to determine their physical and engineering
- 4. Geotechnical analysis of the data obtained. 5. Consultation with owner representatives and design professionals.
- 6. Preparation of this report.

March 8, 2022

Contained in the report are:

Discussions on local soil and groundwater conditions.

2. Results of laboratory and field tests. 3. Conclusions and recommendations pertaining to site grading and structural design. 4. The stabilized percolation rates.

C. Site Setting 1. The site of the proposed development is located at the southwest corner of Theater Drive and Nutwood Circle in the City of Paso Robles, California. The geographical coordinates of the project site are 35°34'41.21"N and 120°41'52.30"W at an elevation of 791 feet above mean sea level, (MSL). A Vicinity Map is provided in Appendix A.

2. The site is currently vacant and relatively level with several stockpiles of fill which the source(s) are unknown. Weeds to 12 inches in height are present at the site. The area of the property at the corner of Theater Drive and Nutwood Circle was previously used as a manufactured home sales facility and is currently vacant.

SOIL CONDITIONS A. Evaluation of the subsurface indicates that soils are generally soft and moist slightly silty sands underlain by soft and moist slightly silty sandy clays transitioning to firm silty sands and gravels

underlain by moist very silty clayey sands with minor gravels. B. Soils encountered at approximate bearing depths are characterized as loose and inadequate for bearing and should be designed as Site Classification D in accordance with the local building code.

C. Expansion determination indicates that the bearing soils, after importing non-expansive soils, will result in the "Very Low" expansion potential range. D. Groundwater was not encountered to a maximum depth of 20 feet

# below existing grade.

LIQUEFACTION A. Earthquake-induced vibrations can be the cause of several significant phenomena, including liquefaction in fine sands and silty sands. Liquefaction results in a complete loss of strength and can cause structures to settle or even overturn if it occurs in the bearing zone. If liquefaction occurs beneath sloping ground, a phenomenon known as lateral spreading can occur.

March 8, 2022 H-211472

Liquefaction is typically limited to the upper 50 feet of the subsurface soils and to soils that have a relative density of less than B. Based on the site characteristics and the soils encountered at the site, it is our opinion that the potential for liquefaction is low at this

PERCOLATION TESTING

Percolation testing was performed at the site in accordance with the Standards set forth by the City of Paso Robles, California. Four (4) borings were drilled in the proposed area of the infiltrator system with their approximate locations shown on the Site Map in Appendix A. The borings were pre-saturated and subsequently tested. The resulting stabilized percolation rates are as follows:

RATE (MIN./INCH)

Based on the resulting percolation rates at the represented depths, we recommend that the infiltrator drainage system be designed using a stabilized rate of 30 minutes per inch.

A representative sample was obtained from the area of the proposed leach field. A sieve analysis resulted in greater than 10 percent passing the No. 200 screen.

# CONCLUSIONS AND RECOMMENDATIONS

The site is suitable for the proposed development from a geotechnical engineering standpoint provided the recommendations contained herein are properly implemented into the project.

# General Grading

a. Grading, at a minimum, should conform to Chapter 18 and Appendix J of the 2019 California Building Code

b. The existing ground surface should be initially prepared for grading by removing all vegetation, trees, large roots, debris, non-complying fill and all other organic material. Voids created by removal of such material should not be backfilled unless the underlying soils have been observed by a representative of this firm.

March 8, 2022

H-211472

c. The bottom of all excavations should be observed by a representative of this firm prior to processing or placing fill. d. Fill and backfill placed at near optimum moisture in layers with loose thickness not greater than 8 inches should be compacted to a minimum of 90% of maximum dry density obtainable by the ASTM D 1557 Test Method.

e. Import soils used to raise site grade should be equal to or better than on-site soils in strength, expansion and compressibility characteristics. Import soils can be evaluated, but will not be pre-qualified by the geotechnical engineering firm. Final comments on the characteristics of the import soils will be offered after the material is at the

Roof draining systems should be designed so that water is not discharged onto bearing soils or near structures.

g. Final site grade should be such that all water is diverted away from the structure and is not allowed to pond. The ground immediately adjacent to the building shall be sloped 5% for a minimum distance of 10 feet measured perpendicular to the face of the wall. All diverted water is to be directed to an approved drainage facility. Alternative

grading methods can be found in C.B.C. Section 1803.3. h. We recommend that this firm be retained to provide intermittent geotechnical engineering services during site development, grading and foundation construction phases of the work to observe compliance with the design concepts, specifications and recommendations, and to allow design changes in the event that subsurface conditions differ from

those anticipated prior to the start of construction. Plans and specifications should be provided to this firm prior to grading. Plans should include the grading plans, and foundation details. Structural loads should be shown on the foundation plans.

Should soils become unstable during grading due to excessive subsurface moisture, alternatives to correct instability may include aeration or the use of gravels and/or geotextiles as stabilizing measures. Recommendations for stabilization should be provided by this firm as needed during construction.

H-211472

March 8, 2022

Site Grading/Development Grading - Building Pad a. The primary concerns from a geotechnical engineering standpoint are the soft near surface moderate to highly expansive clays. To provide more uniform bearing conditions, to prevent excessive and/or differential settlement and to provide a non-expansive building pad over-excavation and re-compaction will be necessary. To mitigate the potential of the effects of the expansive clays and to construct a non-expansive pad, we recommend that the building area, extending to a distance of 5 feet beyond the building perimeter be excavated to a depth of 4 feet below finish pad grade or existing grade, whichever is greater. The non-expansive soil should also include the proposed loading dock of the structure. The soil should be replaced with a non-expansive (E.I.<10) soil. The exposed surface of the excavation should be scarified to a depth of 1 foot, moisture conditioned to 2% to 3% above optimum moisture content and re-compacted. The non-expansive soil should then be placed in thin lifts, moisture conditioned and compacted to a minimum of 90% of maximum dry density to finish subgrade elevation. The intention of these recommendations is to provide a minimum of 4 feet of non-

expansive soil under the structure. A representative of this firm should be notified to provide testing and observation services during construction in order to verify the intent of these recommendations. b. Areas outside of the building envelope to receive fill, exterior slabs-on-grade, sidewalks and areas to be paved should be over-excavated to a depth of 1 foot. The exposed surface of the excavation should be scarified, moisture conditioned and re-compacted to a minimum of 90% of maximum dry density. The previously removed material should then be

to a minimum of 90% of maximum dry density or 95% of the top 12 inches for areas to be paved. c. Although not encountered in our borings, should any trash, debris or subsurface structures be encountered during grading, removals will be necessary to adequate depths and horizontal limits as recommended by this firm at the time of

grading.

replaced in thin lifts, moisture conditioned and re-compacted

March 8, 2022

Slope Construction a. Although not anticipated for this project, any hillside grading and construction of any fill slopes should conform to the minimum standards in Chapter 18 of the California Building Code. It is recommended that a representative of this firm review the grading plans prior to grading and site

development. b. Fill slopes should be keyed and benched into firm natural ground when the existing slope to receive fill is 10:1.

H-211472

H-211472

horizontal to vertical, or steeper. The keys should be sloped into the heel of the keyway at a minimum gradient of 2%, should be a minimum of one equipment width (min. 10 feet wide), and should extend a minimum of 3 feet deep at the outside edge.

c. Fill slopes should be overfilled, compacted and cut back to planned configurations. This will yield better compaction on the slope faces than other methods.

d. Lined drainage swales and down drains should be provided at the tops of all cut and fill slopes to divert drainage away

e. Cut and fill slopes should not be constructed steeper than 2:1 (horizontal to vertical). Setbacks of structures from slopes should be maintained in accordance with the C.B.C.

Utility Trenches Utility trench backfill should be governed by the provisions of this report relating to minimum compaction standards. In general, service lines inside of the property lines may be packfilled with non-expansive soils and compacted to a minimum of 90% of maximum dry density.

Backfill of offsite service lines will be subject to the specifications of the jurisdictional agency or this report, whichever is more stringent. c. A representative of this firm is to monitor compliance with

#### B. <u>Structural Design</u> Seismic Design Conditions

these recommendations.

The following estimated ground motion parameters have been established using the methods outlined in the 2019 California Building Code with reference to the acceleration contour maps provided by the U.S. Geological Survey (USGS) and the National Seismic Hazard Mapping Project (NSHMP).

March 8, 2022

These ground motion parameters represent the Maximum Considered Earthquake (MCE) spectral response of seismic events experiencing 5 percent damped acceleration and having a 2 percent probability of exceedance within a 50 year period.

#### TABLE B1.a 2019 CALIFORNIA BUILDING CODE SEISMIC PARAMETERS

PARAMETER	VALUE
Site Class	D
Short Period Spectral Acceleration, Ss	1.111
1-Second Period Spectral Acceleration, S1	0.408
Short Period Site Coefficient, Fa	1.2
1-Second Period Site Coefficient, Fv	N/A
Adjusted Short Period Spectral Acceleration, Sms	1.333
Adjusted 1-Second Period Spectral Acceleration, Sm1	N/A
Short Period Design Spectral Acceleration, Sps	0.889
1-Second Period Design Spectral Acceleration, Sp1	N/A

a. Conventional continuous footings may be used for support of the structure. Footings should bear entirely into firm recompacted non-expansive soils to be tested and approved

by this firm. b. Conventional continuous footings may be designed based on an allowable bearing value of 2000 psf. Allowable bearing values are net (weight of footing and soils

surcharge may be neglected) and are applicable for dead plus reasonable live loads. Bearing values may be increased by one-third when transient loads such as wind and/or seismicity are incorporated into designs using the alternate load combinations in 2019 CBC Section 1605.3.2. d. Lateral loads may be resisted by soil friction on floor slabs and foundations and by passive resistance of the soils acting

on foundation stem walls. Lateral capacity is based on the assumption that any required backfill adjacent to foundations and grade beams is properly compacted. e. For structures to be constructed above slopes, the outside

faces at the bottom of footings should provide a minimum horizontal distance of 5 feet from the slope face. f. Conventional continuous footings for buildings where the

ground surface slopes at 10:1, horizontal to vertical, or

steeper should be stepped so that both top and bottom are

March 8, 2022 March 8, 2022 H-211472 g. Reinforcement of footings bottomed in soils in the "Very the recommendations of this report. Low" expansion range should be designed by the Project

immediately prior to placement of concrete. h. Foundation excavations should be observed by a representative of Hallin Geotechnical, Inc. after excavation but prior to placing reinforcing steel or

3. Slab-On-Grade

a. Concrete slabs should be supported by compacted structural fill as recommended earlier in this report. b. We recommended that perimeter slabs (walks, patios, etc.) be designed relatively independent of footing stems (i.e.

Structural Engineer or Architect. Soils should be moistened

free floating) so foundation adjustment will be less likely to cause cracks. c. Slabs should be underlain with a minimum of 2 inches of clean and free draining sand over 4 inches of 34 inch crushed gravel. Areas where floor wetness would be undesirable should be underlain with a moisture barrier (min. 10 mil. visqueen) to reduce moisture transmission from the subgrade soils to the slab. The barrier should be placed between the sand and gravel or as recommended by the Project Engineer or Architect.

Reinforcement and slab thickness should be determined by the Project Structural Engineer or Architect. e. Soils underlying slabs in the "Very Low" expansion range should be moistened prior to placement of concrete.

Frictional and Lateral Coefficients

a. Resistance to lateral loading may be provided by friction acting on the base of foundations. A coefficient of friction of 0.35 may be applied to dead load forces. This value does not include a factor of safety.

b. Passive resistance acting on the sides of foundation stems equal to 250 pcf of equivalent fluid weight may be included for resistance to lateral load. This value does not include a factor of safety. However, when passive resistance is used in conjunction with friction. the coefficient of friction should be reduced by one-third in determining the total lateral resistance.

. A one-third increase in the quoted passive value may be used when considering transient loads such as wind and seismicity.

March 8, 2022

Settlement Considerations

a. Maximum expected settlements of less than ½ inch can be anticipated for foundations and floor slabs designed as recommended.

b. Differential settlement between adjacent load bearing members should be less than one-half the total settlement. c. The majority of settlement should occur during construction. Post construction settlement should be minimal.

Retaining Walls

a. Conventional cantilever retaining walls bearing in soils prepared in accordance with Section A-2 of this report and backfilled with compacted on-site soils may be designed for the lateral pressures listed below:

H-211472

H-211472

H-211472

**ACTIVE CASE** AT REST CASE PASSSIVE CASE 50 PCF MAXIMIM TOE PRESSURE 2000 PSF COEF. OF SLIDING FRICTION

b. In addition to the static soil pressures described above, it is

important to note that the active pressure condition will only

fully develop if the retaining wall structure is allowed to

move a sufficient distance. The necessary lateral

movements required to establish the active pressure condition are shown as follows:

Non-Expansive Granular Soil 0.001H - 0.004H

Expansive Cohesive Soil 0.01H - 0.04H

"H" represents the height of the wall. At-rest pressures should be used for design purposes where retaining wall systems connected or adjacent to building structures would be adversely affected by the above referenced lateral displacements

Retaining wall conditions requiring additional seismic design load values should be reviewed by this firm prior to establishing the appropriate seismic design parameters. The pressures listed above were based on the assumption that backfilled soils will be compacted to 90% of maximum

dry density as determined by ASTM D 1557 Test Method.

March 8, 2022

e. The lateral earth pressure to be resisted by the retaining walls or similar structures should include the loads from any structures or temporary loads that influence the wall design. f. A back drain or an equivalent system of backfill drainage should be incorporated into the retaining wall design. Should an active sump drainage system be required, the project Civil Engineer should be consulted for further design considerations. Backfill immediately behind the retaining structure should be a free-draining granular material. Alternatively, the back of the wall could be lined with a

geodrain system. g. Compaction on the uphill side of the wall within a horizontal distance equal to one wall height should be performed by hand-operated or other lightweight compaction equipment. This is intended to reduce potential "locked-in" lateral pressures caused by compaction with heavy grading equipment.

h. Water should not be allowed to pond near the top of the wall. To accomplish this, the final backfill site grade should be such that all water is diverted away from the retaining

#### ADDITIONAL SERVICES

This report is based on the assumption that an adequate program of monitoring and testing will be performed by Hallin Geotechnical, Inc. during construction to verify compliance with the recommendations offered in this report. The recommended tests and observations include, but are not necessarily limited to the following:

1. Review of the building and grading plans during the design phase of the project. 2. Observation and testing during site preparation, grading, placing of engineered fill, and foundation construction. 3. Consultation as required during construction.

# LIMITATIONS AND UNIFORMITY OF CONDITIONS

The analysis and recommendations submitted in this report are based in part upon the data obtained from the borings drilled on site. The nature and extent of variations between and beyond the borings

12

may not become evident until construction.

If variations then appear evident, it may be necessary to re-evaluate

The scope of our services did not include environmental assessment or geological study. The scope of services did not include investigation for the presence or absence of wetlands, hazardous or toxic materials in the soil, surface water, groundwater or air.

Any statements in this report or on the soil boring logs regarding odors, unusual or suspicious items or conditions observed are strictly for the information of the client.

Findings of this report are valid as of this date, however, changes in a condition of a property can occur with passage of time whether they be due to natural processes or works of man on this or adjacent properties. In addition, changes in applicable or appropriate standard may occur whether they result from legislation or broadening knowledge. Accordingly, findings of this report may be invalidated wholly or partially by changes outside our control. Therefore, this report is subject to review and should not be relied upon after a period of two (2) years.

In the event that any changes in the nature, design, or location of the structure and other improvements are planned, the conclusions and recommendations contained in this report shall not be considered valid unless such changes are reviewed and the conclusions and recommendations within this report are verified or modified in writing.

of the owner or his representatives to ensure that the information and recommendations offered herein are incorporated into all project specifications and plans and are brought to the attention of the Project Engineers and/or Architects. It is also the responsibility of the owner or his representatives to

ensure the information and recommendations offered herein are

Incorporated into the project plans and specifications and the

necessary steps are taken to see that the contractor and


This report is issued with the understanding that it is the responsibility

subcontractors carry out such recommendations in the field. This firm has prepared this report for the exclusive use of the client and authorized agents. This report has been prepared in accordance


with generally accepted geotechnical engineering practices.

APPENDIX A

Vicinity Map Site Plan Field Investigation Boring Logs Unified Soil Classification



PROPOSED COMMERCIAL BUILDING & RELATED IMPROVEMENTS THEATRE DRIVE; APN: 009-851-022 PASO ROBLES, CALIFORNIA PROJECT NO. H-211472



811 Palm Street P 805.594.0771 F 805.594.5137 ARCHITECT STAMP CONSULTANT S

Craig Archer 3030 Ramada Drive, Paso Robles CA

> 0 0

. ග 0 0 S <

0

DATE

03 JUN 22 DEVELOPMENT PLAN RESUBMITTAI

JOB NUMBER 2138

AGENCY APPROVAL

**SOILS REPORT** 

G-021

#### A-1 FIELD INVESTIGATION

- A. The borings were drilled to a maximum depth of 20 feet below the existing ground surface to observe the soil profile and to obtain samples for laboratory analysis. The borings were drilled on January 26, 2022 using a Giddings model XHDGSRPS truck mounted drill rig. The approximate locations of the borings were determined in the field by pacing and sighting, and are shown on the Site Plan in this Appendix.
- B. Bulk samples of the soils encountered were gathered from the auger cuttings. C. The final logs of borings represent our interpretation of the contents of the field logs and the results of laboratory testing performed on the samples obtained during the subsurface investigation. The final logs are included in this Appendix.

lig Ty luger	/Helper /pe: Gid Diamet Januar	dings ter: 6"			В	DRING	NO. 3		
Depth ft.)		Blows	Drilling comments	Voids	Moisture	Descrip	otion	USCS	Soil ID
0			Soft		Moist	Orange	brown slightly silty medium to coarse sands	SM	A1
			JUIL			Dark br	own silty sandy clay	CL	C1
5			Stiff						
Ť			OLII				,		
			Firm			Brown	very silty clayey sand w/ minor gravel	SM/SC	A3
10									
						Total D	Depth = 12'0"		
15						Groun	dwater Not Encountered		
20									
20									
25									
								hill a	
30									
									10/5
35									
						1			
40									

T=Shelby tube

HALLIN GEOTECHNICAL, Inc.

LOG OF BORING

[] 3" [] Other:

Project No. H-211472

HALLIN GEOTECHNICAL, Inc.

HALLIN GEOTECHNICAL, Inc. LOG OF BORING Site Location: Paso Robles, CA Theatre Drive; APN: 009-851-022 Site Location: Paso Robles, CA Theatre Drive; APN: 009-851-022 Project No. H-211472 Driller/Helper: DH/MW Driller/Helper: DH/MW Rig Type: Giddings Auger Diameter: 6" Date: January 26, 2022 Depth Bag Blows Drilling (ft.) Sample per ft. comments Voids Moisture Description 0 \* Moist Orange brown slightly silty medium to coarse sands SM A1


\* Soft Dark brown silty sandy clay CL C1 Firm Dry Light brown silty fine to coarse sand w/ gravel Moist

Brown very silty clayey sand w/ minor gravel SM/SC A3 15 20

Total Depth = 20'0"

Groundwater Not Encountered 25 +--30 \_ \_\_\_ 35 \_\_\_\_ 40 GROUNDWATER SAMPLE TYPE U=Undisturbed ring sample S=Standard penetration tube T=Shelby tube Time Depth N.E.

[] 3" [] Other:



#### HALLIN GEOTECHNICAL, Inc. LOG OF BORING Site Location: Paso Robles, CA Theatre Drive; APN: 009-851-022 Project No. H-211472 Driller/Helper: DH/MW Rig Type: Giddings **BORING NO. 2** Auger Diameter: 6" Date: January 26, 2022 Depth Bag Blows Drilling (ft.) Sample per ft. comments Voids Moisture Description 0 Moist Orange brown slightly silty medium to coarse sands SM A1 Soft Dark brown silty sandy clay CL C1 5 Stiff Firm Light brown silty fine to coarse sand w/ gravel SM A2 Brown very silty clayey sand w/ minor gravel SM/SC A3 Total Depth = 12'0" Groundwater Not Encountered 25 30 35 SAMPLE TYPE U=Undisturbed ring sample S=Standard penetration tube T=Shelby tube [] 3" [] Other:

MAJO	R DIVISIONS		GRAPH SYMBOL	SYMBOL	TYPICAL DESCRIPTIONS
	GRAVEL AND	CLEAN GRAVELS		ew '	WELL-GRADED GRAVES, GRAVES SAHD MIXTURES, LITTLE OR NO FINES
COARSE GRAINED	GRAVELLY SOILS	(LITTLE OR NO FINES)		6	POORLY-GRADED GRAVES, CRAVE- SAND MEXTURES, LITTLE OR NO FINES
SOILS	MORE THAN 50% OF COARSE	GRAVELS WITH FIXES		en en	SELTY GRAVES, GRAVELSAND- SELT MIXTURES
	FRACTION RETIANED ON NO. 4 SIEVE	MODILOLDES		ec	CLAYEY GRAVES, GRAVE-SAND- CLAY MIXTURES
	SAND AND	CLEAN		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
MORE THAN 50% OF MATERIAL IS	SANDY SOILS	(LITTLE OR NO PINES)		57	POORLY-GRADED SANDS, GRAVELY SANDS, LITTLE OR NO FINES
LARGER THAN NO. 200 SIEVE SIZE	MORE THAN 50% OF COARSE	SAND WITH FINES		SM	SILLY SANDS, SAND-SILT KEXTURES
	FRACTION PASSING ON NO. 4 SIEVE	prescuent respect of female		sc	CLAYEY SANDS, SAND-CLAY MIXTURES
FINE	SILTS	LIQUED		ML	INGREANIC SILTS AND VERT FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
GRAINED SOILS	AND	LESS THAN		а	Morganic clays of low to medium plasticity, gravelly clays, sandy clays, silt clays, lean clays
	CLAYS	50		OL.	ORGANIC SILTS AND ORGANIC SILTY  CLAYS OF LOW PLASTICITY
MORE THAN 50% OF MATERIAL IS	SILTS	LIQUID		Heri	INDRIGANIC SILTS, MECACHOLIS OR DEATOMACHOUS FINE SAND OR SILTY SOILS
SMALLER THAN NO. 200 SIEVE SIZE	AND	GREATER		ан	INORGANIC CLAYS OF HIGH PLASTRITY, FAT CLAYS
	CLAYS	THAN 50		OH	CREAMIC CLAYS OF MEDIUM TO HIGH PLASTICTLY, CREAMIC STITS
	Y ORGANIC SOILS			PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

Laboratory Testing Bench & Keyway Detail Transition Lot Detail

LABORATORY TESTING

APPENDIX B

Test Results

Samples were reviewed along with field logs to determine which would be analyzed further. Those chosen for laboratory analysis were considered representative of soils that would be exposed and/or used during grading, and those deemed to be within the influence of the proposed structure. Test results are presented in this Appendix.

In-situ Moisture Content and Unit Dry Weight for the ring samples were determined in general accordance with ASTM D 2947.

Expansion index test were performed on bulk soil samples in accordance with the ASTM Test Method. The samples were surcharged under 144 pounds per square foot at moisture content of near 50% saturation. Samples were then submerged in water for 24 hours and the amount of expansion was recorded with a dial indicator.

Maximum density was performed to estimate the moisture-density relationship of typical soil materials. The tests were performed in accordance with ASTM designation D 1557-88.

**TEST RESULTS** 

Boring Depth 1@0'-1' 1@1'-6' 1@6'-12' 1@12'-20' Soil Type A1 C1 A2 A3 USCS SM SM/CL SM SM/SC Maximum Density (pcf) 128.4 116.0 121.7 119.6 Optimum Moisture (%) 10.6 14.2 11.0 12.1 Expansion Index 0 73 0 52

811 Palm Street San Luis Obispo, CA 93401 P 805.594.0771 F 805.594.5137

ARCHITECT STAMP | CONSULTANT ST

Craig Archer 3030 Ramada Drive, Paso Robles CA

> oble Drive A 934 1-022 2805 Theatre I Paso Robles, CA APN: 009-851 2


ete

DATE 03 JUN 22 DEVELOPMENT PLAN RESUBMITTAL


JOB NUMBER 2138


AGENCY APPROVAL


**SOILS REPORT** 





BEFORE YOU DIG


















NOTE:
TELEPHONE LINES, GAS MAIN AND SERVICES, ELECTRICAL LINES, A.T.&T. LINES AND PRIVATE WATER LINES EXIST IN THE AREA OF WORK. THE CONTRACTOR SHALL CALL USA TO FIELD LOCATE ALL FACILITIES AND HE SHALL THEN POTHOLE EACH UTILITY TO VERIFY DEPTH AND LOCATION PRIOR TO THE START OF CONSTRUCTION.


SEE PLAN SHT. C-4 FOR CONSTRUCTION NOTE LEGEND


UNDERGROUND SERVICE ALERT

DIAL 811

TWO WORKING DAYS BEFORE YOU DIG W.H.M.W.CO. WATER LINE EXTENSION STA. 11+00 TO 13+50









TWO WORKING DAYS


BEFORE YOU DIG

STA. 13+50 TO 20+23





BEFORE YOU DIG





DIAL 811 TWO WORKING DAYS BEFORE YOU DIG


DEMOLITION PLAN SOUTH PORTION

T TARTAGL	APP.	DATE	DESCRIPTION	REV.
CIVI 7360 El Camino Ro	_	_	_	
805-466-3				
C A				
C. AI				

*RCHER* 







# **GENERAL NOTES**


- 1. MINIMUM PLANT SIZES:
  - STREET TREES (24"BOX), SITE TREES (15 GAL.), SHRUBS (1 GAL.), GROUNDCOVER (FLATS)
- IRRIGATION SYSTEM TO BE INSTALLED AS A PART OF SITE CONSTRUCTION. SYSTEM SHALL BE UNDERGROUND, AUTOMATIC WITH POP-UP SPRAY HEADS, "SMART" CONTROLLER AND AUTOMATIC RAIN SHUTOFF. LOW PRECIPITATION RATE HEADS TO BE USED TO MINIMIZE RUNOFF.
- 3. POINT OF CONNECTION FOR WATER SUPPLY, SHALL BE BY A NEW LANDSCAPE SUB METER.
- 4. ALL PLANTING AREAS SHALL RECEIVE A 3" LAYER OF MEDIUM BARK MULCH AFTER INSTALLATION.
- 5. ALL PLANT MATERIAL SHALL CONFORM TO THE CITY OF PASO ROBLES OR STATE OF CALIFORNIA MODEL WATER CONSERVATION ORDINANCE.
- 6. ALL PLANTING AND IRRIGATION SHALL BE INSTALLED PER THE CITY OF PASO ROBLES STANDARDS AND CODES.
- 7. FOR SITE WORK, ARCHITECTURAL, AND GRADING/DRAINAGE INFORMATION SEE PLANS BY OTHERS.
- 8. ALL AREAS BEYOND THE AREA OF WORK THAT ARE DISTURBED BY CONSTRUCTION SHALL BE RETURNED TO ORIGINAL CONDITION.
- DRAWINGS ARE FOR DESIGN AND REVIEW PURPOSES ONLY AND SHALL NOT BE USED AS CONSTRUCTION DOCUMENTS. 10. TREES PLANTED IN AN AREA LESS THAN 8' WIDE SHALL BE INSTALLED
- DAMAGE. 11. STREET TREES ARE TO BE SELECTED FROM THE CITY OF PASO ROBLES APPROVED TREE LIST.


WITH A LINEAR ROOT BARRIER TO PROTECT AGAINST HARDSCAPE



Non-irrigated

SCALE: 1" = 40'-0" NORTH





\* - Preferred Plants

DESIGN GROUP 3203 Lightning St., Ste. 201 // Santa Maria, CA 93455 805.349.9695 // www.pleinairedg.com EXCLUSIVE PROPERTY OF KEVIN J. SMALL LANDSCAPE ARCHITECT. THEY ARE NOT TO BE REUSED, REPRODUCED, COPIED, SOLD, OR USED FOR ANY OTHER PURPOSE WITHOUT THE EXPRESSED WRITTEN CONSENT OF KEVIN J. SMALL; RLA 2929. © 2022 KEVIN J. SMALL


SHEET TITLE CONCEPTUAL

LANDSCAPE **PLAN OWNER** Craig Archer 3030 Ramada Drive

SHEET NO.

Paso Robles, California 93446 2022.12.15 22219

L-01



HYDROSEED MIX - SEED

S&S Seeds - Basic Native Mix

Non-irrigated

SMALL ORNAMENTAL GRASSES - 1 GAL.

Blue Oát Grass - Helictotrichon sempervirens \*

Siskiyou Blue Fescue - Fetuca 'Siskiyou Blue'

Berkeley Sedge - Carex divulsa \*

Italian Buckthorn - Rhamnus alaternus \*

OAK TREE SPECIES (MITIGATION) - 15 GAL.

Clara Indian Hawthorn - Rhaphiolepis i. 'Clara' \*

Little John Bottlebrush - Callistemon 'Little John'

Concha ceanothus - Ceanothus 'Concha'

FLOWERING GROUNDCOVERS - FLATS

Creeping Myoporum - Myoporum p. 'Putah Creek' \*

Bearberry Cotoneaster - Cotoneaster d. 'Low Fast' \*
Trailing Rosemary - Rosmarinus officinalis 'Prostratus' \*

\* - Preferred Plants

SITE -

DESIGN GROUP 3203 Lightning St., Ste. 201 // Santa Maria, CA 93455 805.349.9695 // www.pleinairedg.com ARCHITECT. THEY ARE NOT TO BE REUSED, REPRODUCED, COPIED, SOLD, OR USED FOR ANY OTHER PURPOSE WITHOUT THE EXPRESSED WRITTEN CONSENT OF KEVIN J. SMALL; RLA 2929. © 2022 KEVIN J. SMALL

SHEET TITLE CONCEPTUAL LANDSCAPE

**ENLARGEMENT - A** 

Craig Archer **OWNER** 3030 Ramada Drive Paso Robles, California 93446

2022.12.15 22219 SHEET NO.

L-02

Marquita Ave.

NORTH N.T.S.

DESIGN GROUP

3203 Lightning St., Ste. 201 // Santa Maria, CA 93455 805.349.9695 // www.pleinairedg.com

EXCLUSIVE PROPERTY OF KEVIN J. SMALL LANDSCAPE ARCHITECT. THEY ARE NOT TO BE REUSED, REPRODUCED, COPIED, SOLD, OR USED FOR ANY OTHER PURPOSE WITHOUT THE EXPRESSED WRITTEN CONSENT OF KEVIN J. SMALL; RLA 2929. @ 2022 KEVIN J. SMALL

CONCEPTUAL PLANTING LEGEND

STREET TREES - 24" BOX

Chinese Pistache - Pistacia chinensis \* London Plan Tree - Platanus acerifolia \* PERIMETER SCREENING TREES - 15 GAL

Japanese Zelkova - Zelkova serrata \* Golden Locust - Robinia p. 'Frisia' \* Chinese Elm - Ulmus Parvifolia\* OAK TREE SPECIES (MITIGATION) - 15 GAL. • ) EXISTING TREES TO REMAIN

EXISTING TREES TO BE REMOVED

MEDIUM FLOWERING SHRUBS - 1 GAL. Italian Buckthorn - Rhamnus alaternus \* Clara Indian Hawthorn - Rhaphiolepis i. 'Clara' \* Little John Bottlebrush - Callistemon 'Little John' Concha ceanothus - Ceanothus 'Concha'

SMALL FLOWERING SHRUBS - 1 GAL.

Red Hot Poker - Kniphofia uvaria \* Hidcote Lavender - Lavandula a. 'Hidcote' \* Hardy Yellow Ice Plant - Delosperma nubigens Blue Chalksticks - Senecio serpens

SMALL ORNAMENTAL GRASSES - 1 GAL.

Berkeley Sedge - Carex divulsa \* Blue Oát Grass - Helictotrichon sempervirens \* Siskiyou Blue Fescue - Fetuca 'Siskiyou Blue'

HYDROSEED MIX - SEED

S&S Seeds - Basic Native Erosion Control Mix

Non-irrigated

S&S Seeds - Basic Native Mix

HYDROSEED MIX - SEED



L.I.D. PLANTING - FLATS

Yarrow - Achillea millefolium \* Small Cape Rush - Chondropetalus tectorum \* Elk Blue CA Gray Rush - Juncus patens 'Blue Elk' \* Pine Muhly - Muhlenbergia dubia



FLOWERING GROUNDCOVERS - FLATS

Creeping Myoporum - Myoporum p. 'Putah Creek' \* Bearberry Cotoneaster - Cotoneaster d. 'Low Fast' \*
Trailing Rosemary - Rosmarinus officinalis 'Prostratus' \* \* - Preferred Plants

**VICINITY MAP** Volpi Ysabel Rd. SITE-Marquita Ave. NORTH N.T.S.


SHEET TITLE CONCEPTUAL LANDSCAPE **ENLARGEMENT - B** 

**OWNER** Craig Archer 3030 Ramada Drive Paso Robles, California 93446 DATE 2022.12.15 22219

SHEET NO. L-03



Italian Buckthorn




Yarrow



London Plane Tree



Clara Indian Hawthorn



Small Cape Rush



Japanese Zelkova



Hidcote Lavender



Elk Blue California Gray Rush




Golden Locust



Red Hot Poker




Myoporum



Chinese Elm



Berkeley Sedge



Lowfast Cotoneaster



Oak



Blue Oat Grass



Trailing Rosemary

# NOTE:

PLANT IMAGERY SHOWN IS REPRESENTATIVE ONLY. FINAL SELECTIONS MAY VARY. SEE CONCEPTUAL PLANTING LEGEND FOR MORE INFORMATION.

ERBILT PASO ROBLES

DESIGN GROUP

3203 Lightning St., Ste. 201 // Santa Maria, CA 93455 805.349.9695 // www.pleinairedg.com

EXCLUSIVE PROPERTY OF KEVIN J. SMALL LANDSCAPE ARCHITECT. THEY ARE NOT TO BE REUSED, REPRODUCED, COPIED, SOLD, OR USED FOR ANY OTHER PURPOSE WITHOUT THE EXPRESSED WRITTEN CONSENT OF KEVIN J. SMALL; RLA 2929. © 2022 KEVIN J. SMALL


SHEET TITLE
PLANT IMAGERY

OWNER Craig Archer
3030 Ramada Drive
Paso Robles, California 93446

SHEET NO

\_-04

2022.12.15



Attachment 9

studio

Architects, LLP

811 Palm Street
San Luis Obispo, CA 93401

www.studio-2G.com

P 805.594.0771
F 805.594.5137

These drawings are instruments of service and are the property of studio/2G Architects, LLP. All designs, deriglis, and other information on these drawings are for use on the specified project and shall not be used otherwise without the expressed and written permission of studio/2G Architects, LLP.

ARCHITECT STAMP CONSULTANT STAMP

OWNER INFO

Craig Archer 3030 Ramada Drive, Paso Robles CA

Peterbilt Paso Robles
2805 Theatre Drive

SUBMITTALS & REVISIONS

TE ISSUE

IG22 DEVELOPMENT PLAN REVIEW

CT22 PLANNING COMMISSION SUBMITTAL


JOB NUMBER **2138** 


AGENCY APPROVAL

OVERALL ARCHITECTURAL SITE PLAN

AS101

© 2020 studio2G Architects, LLP





# PROPOSED FENCE AT THEATRE DRIVE ENTRY

# 6' +/- 1" - 4" TYP. PICKETS -NOTE:-THIS RAIL ADDED FOR 7' THRU 10' | HEIGHTS ONLY V CONCRETE FOOTING (PER LOCAL CODE) GREATFENCE.COM F

# INDUSTRIAL STYLE 9 SPECIFICATIONS

Horizontal Rails: 1 5/8" X 1 5/8"

Side Walls: .100" Top Walls: .070"


Internal: 8 Metal Support Ribs ADDING RINGS TO YOUR FENCE PANEL DECREASES "A"

Pickets: 1" x 1" x .062" Picket Spacing: 4" Powder Coat: 2604-5 AAMA

Lifetime Warranty: No Rusting

DIMENSIONS									
A	В	E	F						
7 5/8"	40 3/8"	PER LOC	AL CODE						
7 5/8"	52 3/8"	PER LOC	AL CODE						
7 5/8"	64 3/8"	PER LOC	AL CODE						
10 5/8"	73 3/8"	PER LOC	CAL CODE						
10 5/8"	85 3/8"	PER LOC	CAL CODE						
13 5/8"	94 3/8"	PER LOC	CAL CODE						
13 5/8"	106 3/8"	PER LOC	AL CODE						
	A 7 5/8* 7 5/8* 7 5/8* 10 5/8* 10 5/8* 13 5/8*	A B 7 5/8" 40 3/8" 7 5/8" 52 3/8" 7 5/8" 64 3/8" 10 5/8" 73 3/8" 10 5/8" 85 3/8" 13 5/8" 94 3/8"	A B E  7 5/8" 40 3/8" PER LOC  7 5/8" 52 3/8" PER LOC  7 5/8" 64 3/8" PER LOC  10 5/8" 73 3/8" PER LOC  10 5/8" 85 3/8" PER LOC  13 5/8" 94 3/8" PER LOC						

# PROPOSED FENCE AT NUTWOOD CIRCLE ENTRY



PROPOSED SITE FENCING SCALE: 3/4" = 1'-0"

Craig Archer

3030 Ramada Drive, Paso Robles CA

Robles Peterbilt


03 JUN 22 DEVELOPMENT PLAN RESUBMITTA

2138 AGENCY APPROVAL


SITE FENCING


**EXHIBIT** 

**AS111** 




TRASH ENCLOSURE GATE DETAIL





TRASH ENCLOSURE PLAN



San Luis Obispo, CA 93401 P 805.594.0771 F 805.594.5137 ARCHITECT STAMP | CONSULTANT STAM

3030 Ramada Drive, Paso Robles CA

Craig Archer

Robles 

DATE

03 JUN 22 DEVELOPMENT PLAN RESUBMITTAL

JOB NUMBER

AGENCY APPROVAL

SITE DETAILS

**AS112** 

© 2020 studio 2G Architects, LLP





VIEW FROM NORTHWEST CORNER OF SITE

VIEW FROM SOUTHWEST CORNER OF SITE





VIEW FROM THEATRE DRIVE ENTRY AT NIGHT


3030 Ramada Drive, Paso Robles CA

SITE **RENDERINGS** 

**AS113** 

	INAIRE :								
bol	Label	Quantity Manufacturer	Catalog Number	Description	Lamp	Lumens Per Lamp	Light Loss Factor	Wattage	Notes
]	S	1 LITHONIA	RSX2 LED P3 40K R4 MVOLT SPA NLTAIR2 PIRHN [FINISH]///SSS 21.5FT [THICKNESS] DM28AS [FINISH]	LED POLE MOUNTED AREA LUMIAIRE ON SQUARE STRAIGHT STEEL POLE	4000K LED	22020	0.92	299.96	ASSUMED 2.5FT CONCRETE BASE - PLEASE CONFIRM
	SL	5 LITHONIA	RSX2 LED P3 40K R4 MVOLT AASP HS NLTAIR2 PIRHN [FINISH]///SSS 21.5FT [THICKNESS] DM19AS [FINISH]	LED POLE MOUNTED AREA LUMIAIRE WITH TILTABLE ARM ON SQUARE STRAIGHT STEEL POLE	4000K LED	14473	0.92	149.98	ASSUMED 2.5FT CONCRETE BASE - PLEASE CONFIRM
]	SL1	14 LITHONIA	RSX2 LED P3 40K AFR MVOLT SPA HS NLTAIR2 PIRHN [FINISH]///SSS 21.5FT [THICKNESS] DM19AS [FINISH]	LED POLE MOUNTED AREA LUMIAIRE ON SQUARE STRAIGHT STEEL POLE	4000K LED	16493	0.92	149.98	ASSUMED 2.5FT CONCRETE BASE - PLEASE CONFIRM
	SL2	30 LITHONIA	CNY LED P2 40K MVOLT	LED SURFACE MOUNTED CANOPY DOWNLIGHT	4000K LED	6601	0.92	51.86	
	SL3	2 LITHONIA	WDGE2 LED P2 40K 80CRI T3M MVOLT SRM [FINISH]	LED SURFACE MOUNTED WALL SCONCE	4000K LED	2062	0.92	18.9815	
$\supset$	SL4	12 TARGETTI	KPL 41 WW L2 40 [TRIM RING] [INSTALLATION SLEEVE]	LED RECESSED INGRADE WALLWASHER	4000K LED	4665	0.92	35.7	

STATISTICS											
Description	Symbol	Avg	Max	Min	Max/Min	Avg/M					
CORNER DISPLAY AREA	+	12.1 fc	18.8 fc	2.1 fc	9.0:1	5.8:1					
PAD AROUND BUILDING	+	3.0 fc	12.3 fc	0.3 fc	41.0:1	10.0:1					
PARKING+DRIVE	+	2.5 fc	22.9 fc	0.0 fc	N/A	N/A					
SERVICE CANOPY	+	14.0 fc	18.4 fc	6.4 fc	2.9:1	2.2:1					



Plan View
Scale - 1" = 30ft

DISCLAIMER
The photometric calculation is provided as service for evaluating lighting levels and the results are based upon the data entered by the designer and the criteria provided by the customer. Responsibility of approval is by others. All of the data and fixture selections shall be reviewed and accepted by the approving authority. Fixture nomenclature shall be approved through submittal process prior to product being ordered.



ARCHITECT STAMP CONSULTA

Craig Archer 3030 Ramada Drive, Paso Robles CA

3030 Kamada Diive, Faso Robies

ilt Paso Roble 2805 Theatre Drive

SUBMITTALS & REVISIONS

DATE ISSUE


D3 JUN 22 DEVELOPMENT PLAN RESUBMITTAL

JOB NUMBER **2138** 

2138
AGENCY APPROVAL


SITE LIGHTING PLAN

**AS201** 



CNY LED PO/P1/P2

6.5lbs



for Eat 90", 2 at 180", 3 at 120")

DNAXD Natural Ahmunum

DBLBXD Textured Stack

DWHGXD | fixtured White

and budget friendly, perfect for replacing up to 250W metal halide luminaires while saving up to 80% energy

costs. Quick mount mechanism significantly reduces

the installation time. An LED array and translucent

illumination, CNY LED luminaires are DLC Premium

lens create uniform and visually comfortable

listed and deliver quick payback!

DDBTXD (extured Dark florox

DNATXD Textined Natural Aluminum

DWHXD White

WY LED					
Series	Performance Package	Color Temperature!	Volt	age	Fransh
CNY LED	P0 3,500 lamens P1 4,500 lamens P2 6,600 lamens	40K 4000K 5000K	MV	OLT 1201-277V	DDB Dark bron. = WH White
				NOTES:	
Jurninaires. The CNY LED; parking areas, covered we CONSTRUCTION Cast-aluminim, comosion- Castings are sealed with a	CATIONS  Let deligy-efficient replacements for up to 25 storoides years of maintenance-free illuminance	n live schools, male, afficient	LISTINGS UIL Listed to U.S. and Tested in accordance Designilights Contai Vesions of the prod Qualified Products	temperature only  Correlated color temperature  MVOLT driver operates on  Consider safety standard  e with IESNA LM-79 and Lifthing (DLC) Premium qua- uct may be DLC Freenland	

LITHONIA LIGHTING	Catalog Auniber
	11.40
EATURES & SPECIFICATIONS	Modes
TENDED USE — These specifications are for USA standards only. Square Straight Steel is a general purpose int pole for up to 39-foot mounting heights. This pole provides a robust yet cost effective option for mounting a lights and floodlights.	Type
NSTRUCTION —	Anchor Base Poles
le Shaft: The pole shaft is of uniform dimension and wall thickness and is made of a weldable-grade, hot-rolled, nmercial-quality steel tubing with a minimum yield of 55 KSI (11-gauge, 0.120°), ∞ 50 KSI (7-gauge, 0.179°). alt is one-piece with a full-length longitudinal high-frequency electric resistance weld. Uniformly square incross-	
tion with flat sides, small corner radii and excellent torsional qualities. Available shaft widths are 41,51 and 61.	SSS
le Top: Options include tenon top, drilled for side mount fixture, Lenon with drilling (includes extra handlinle) d open top. Side drilled and open top poles include a removable top cap.	333
indhole: A reinforced handhole with grounding provision is provided at 18" from the base on side Positioning the handhole lower may not be possible and requires engineering review; consult Tech prort-Outdoor for further information. Every handhole includes a cover and cover attachment handware handhole has a nominal dimension of 2.5" x 5".	SQUARE STRAIGHT STEEL
se Cover: A durable ABS plastic two-piece full base cover, finished to match the pole, is provided with each pole embly, Additional base cover options are available upon request.	
cher Base/Bolts: Anchor base is fabricated from steel that meets ASTM A36 standards and can be ered to match existing foundations; consult factory for modifications. Anchor bolts are manufactured ASTM F1SS4 Standards grade 55, (55 KSI minimum yield strength and tensile strength of 75-95 KSI), otheraided portion (norminal 12") is hot-dipped galvanized per ASTM A-153.	
ROWARE — All structural fasteners are high-strength galvanized carbon steet. All non-structural fasteners are ivanized or zinc-plated carbon steet or stainless steet.	
NISH — Extra durable painted finish is coated with TGIC (Trighycidy) (socyanurate) Polyester powder that meets and 5B classifications of ASTM 03359. Powder-coat Finishes include Dark Bronze, White, Black, and Natural Irrihum colors, Architectural Colors and Special Finishes are available by quote and include, but are not limited Paint over Hot-dipped Galvanized, RAL Colors, Custom Colors and Extended Warranty Finishes.	
IY AMERICAN — Product with the BAA option is assembled in the USA and meets the Buy America(n)	
The second secon	

government procurement requirements under FAR, DFARS and DOT, Please refer to www.accitybrancs.com/

INSTALLATION — Do not crect poles without having factures installed. Factory-supplied templates must be

to failure to use Lithonia Lighting factory templates. If poles are stored outside, all protective wrapping must

be removed immediately upon delivery to prevent finish damage. Lithonia Lighting is not responsible for the

WARRANTY - 1-year limited warranty. This is the only warranty provided and no other statements in this

specification sheet create any warranty of any kind. All other express and implied warranties are disclaimed.

Complete warranty terms located at: www.acutybrands.com/support/warranty/rems.and.conditions

NOTE. Actual performance may differ us a result of end-user environment and application.

used when setting anchor bolts. Lithonia Lighting will not accept claim for incorrect anchorage placement due

buy emerican for additional information.

Specifications subject to change without notice.

SSS Square Straight Steel Poles

GUTDOOR POLE-SSS

555								
Series	Nominal fixture mounting height	Nominal shaft base size/wall thickness?	Mounting <sup>3</sup>		Options		Finish <sup>11</sup>	
255"	101-39 (for 1/2 ft Increments, add -6 to the pole height. Ex: 20-6 equals 20ts sig.)  See technical information table for complete ordering information.)	4C 4" 11g (0.120") 4G 4" 7g (0.179") 5C 5" 11g (0.120") 5G 5" 7g (0.179") 6G 6" 7g (0.179") See technical information table for complete ordering information.)	Tenun mounting   PT	AERIS'' Suspend drill mounting**  DM19AST 1 at 90'  DM29AST 2 at 90'  DM39AST 3 at 90'  DM49AST 4 at 90'  OMERO'' Suspend drill mounting**  DM19MRT 1 at 90'  DM29MRT 2 at 180'  DM29MRT 2 at 180'  DM29MRT 2 at 90'	The state of the s	om bracket (1 fixture)**  g' g' g' ed nipple* nipple*	Superdur DDBXD DBLXD DNAXD DWHXD DDBTXD DBLBXD DNAFXD DWHGXD DWHGXD	regional special services

222								
Series	Nominal fixture mounting height	Nominal shaft base size/wall thickness!	Mounting <sup>3</sup>		Options		Finish <sup>u</sup>	
252	10'-39' (fur 1/2 ft increments, add-6 to the pole height. Ex: 20-5 equals 20'tt sin.)  See technical information table for complete ordering information.)	4C 4" 11g (0.120") 4G 4" 7g (0.179") 5C 5" 7g (0.179") 6G 6" 7g (0.179") See technical information table for complete ordering information.)		AERIS** Suspend drill mounting**  DM19AST_ 1 at 90°  DM29AS1_ 2 at 180°  DM39AST_ 3 at 90°  DM49AST_ 4 at 90°  OMERO** Suspend drill mounting**  DM19MRT_ 1 at 90°  DM29MRT_ 2 at 180°  DM39MRT_ 2 at 180°  DM39MRT_ 3 at 90°  DM49MRT_ 4 at 90°	CPL12/xy CPL34/xy CPL1/xy NPL12/xy NPL34/xy NPL1/xy EHHxy NEC KC L/AB TP UL	talled Vibration damper' Horizontal arm bracket (1 fixture)** Festoon outlet less electrical*** 1/2' coupling* 3/4" coupling* 1" coupling* 1/2! threaded nipple* 3/4" threaded nipple* Extra handhole* Extra handhole* Extra handhole* Extra handhole (Not UL Labeled) Interior coating*!  Less anchor bolts (Include when anchor bolts are not needed) Tamper resistant handhole cover fasteners. UL listed with label (Includes NEC compliant cover) Buy Americaln) Act Compliant**	DOBAD DBLXD DNAXD DWHXD DDBTXD DBLBXD DNATXD DWHGXD Other finit GALY Architects Initialist Paint over	Dark bronze Black Natural aluminum White Textured dark bron Textured plack Lextured natural aluminum Textured white shes Galvanized finish ural colors and special r Galvanized, BAL Colors and Extended Finishes available

1. Handfole covers (HHC), full base covers (FBC) and top caps (TC shipped separately. No need to call out in nomendature. 8. Specify location and erientation when ordering option: For additional parts please order as replacements. 2. Wall thickness will be signified with a "C"(1) Gauge) or a "G" (7-Gauge) in nomenclature. "C" - 0.120" | "G" - 0.179". 3. PT open top poles include top cap. When ordering tenon mounting and drill mounting for the same pole, follow this example: DM28/T20. The combination includes a required extra handhole.

4. Refer to the fixture spec sheet for the correct dailing tempiate pattern and orientation compatibility.

PLD78 Plugs for DMxxAS drillings

5. All IAD drilling's require a minimum top D.D. of 4". 6. Insert "1" or "2" to designate future size: e.g. DM19AST2. 7. On 4" and 5" poles, VD cannot be installed if provisions (EHH, FDL, NPL, CPL) are located higher than 2/3 of the pole's Example: Pole height is 25lt, A provision cannot be placed above 76lt.

10. FOL does not come with GFCI outlet or handhole cover. These must be supplied by contractor or electrician. 11. Combination of tenon-top and drill mount includes extra handhole. J HH includes cover-17. Provides enhanced compsion resistance. T.i. Use when mill certifications are required. 14. Finish must be specified. Admitional colors available: see Architectural Culors brochure linked long (Form No. 794.3) Accessories: Order as separate catalog number, PL DT20 Plugs for ESX drillings

MA LITHONIA LIGHTING OUTDOOR: One Lithonia Way Convers, GA 30012 Phone: 800-705-SERV (7378) www.lithonia.com 1994-2022 Acuity Brands Lighting. Inc. All rights reserved. Rev. 04/04/22

For 'x': Specify the height above the base of pole in feet or feet and inches; separate feet and inches with a "-".

For "y": Specify orientation from handhole (A.B.(.D) Refer to the Handhole Grientation diagram below.

9. Horizontal arm is 18" x 2-3/8" O.D. tenon standard, with radius curve providing 12" rise and 2-3/8" O.D. If ordering

Example: 5h = 5 and 20h 3h = 20-3

Example: 1/2' coupling at 5' 8 ", orientation C = CPL 12/5-8C

two horizontal arm at the same height, specify with HAxyy. Example: HAZOBO.

# TARGETTI

## KEPLERO WALL WASHER Professional Inground LED Fixture




Lingett USA A largetti Ginua Company 750 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Proces (7M) 50/1991 Emil. Impetitionarities positionarities impetitionarities impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Proces (7M) 50/1991 Emil. Impetitionarities impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities in medianic company 250 A.W.1.<sup>(6)</sup> St. Costa Mesa, CA 97627 Process (7M) 50/1991 Emil. Impetitionarities (7M) 50/1991 Em



TARGETTI

KEPLERO WALL WASHER



Lingett USA A largetti Graup Company 750 A.W. 2 Pt St. Cesta Mesa, CA 92627 Phone (7M) 5/0/1991 Email: tergettilisensite participant angeltimocom 4/24/21 Page 2 or 6



Specifications

Depth (D1):

Depth (D2):

Weight: (without options)

WDGE LED Family Overview

Height:

WDGE2 LED Architectural Wall Sconce

Precision Refractive Optic OLG OLG Buy American

The WDGE LED family is designed to meet specifier's every wall-mounted lighting need in a widely accepted shape that blends with any architecture. The clean rectilinear design comes in four sizes with lumen packages ranging from 1,200 to 25,000 lumens, providing a true site-wide solution. Embedded with nLight® AIR wireless controls, the WDGE family provides additional energy savings and code compliance.

WDGE2 with industry leading precision refractive optics provides great uniform distribution and optical control. When combined with multiple integrated emergency battery backup options, including an 18W cold temperature option, the WDGE2 becomes the ideal wall-mounted lighting solution for pedestrian scale

# applications in any environment. Lominaire Opins -Standard EM. V.1. Enle EM SUT Sensor on in 10 M M 750 1,200 2,000 - - -1,200 2,000 3,000 4,500 6,000 Standalone / nLight Standalone / nLight 700 1,200 2,000 3,200 4,200

#### WDGE1 LED Visual Comfort 4W WDGE2 LED Visual Comfort WDGEZ LED Precision Refractive 18W WDGE3 LED Precision Refractive Standalone / nLight 7,500 8,500 10,000 12,000 WDGE4 LED Precision Refractive 12,000 16,000 18,000 20,000 22,000 25,000 Ordering Information EXAMPLE: WDGE2 LED P3 40K 80CRI VF MVOLT SRM DDBXD

Summer	Facility	Solor Temperature	H	Пертиничн	Yottage .	Monipling	
WDGE2 LED	P0 P1 P2 P3 P4 P4 P4	27K 2200K 30K 3000W 40K 4000K 50K 5000K AMB <sup>3</sup> Amber	70CRI <sup>4</sup> 80CRI LW <sup>3</sup> Limited Wavelength	T1S Type I Short T2M Type I Medium T3M Type II Medium T4M Type IV Medium TFTM Forward Throw Medium	MVOLT 347 <sup>5</sup> 480 <sup>5</sup>	SRM furtire mounting bracket ICW Indirect Canopy/Celking Yeather bracket (dry/ damp locations only/	Shipped separately  AWS 5/Sinch Architectural wall spacer  PBBW Surface-mounted back box (rop, left, right conduit entry), Use when there is no junction box available.

HWO	Emergency battery backup, Centried in LA Title 20 MAEDIS	Standalone Sensors/Controls						
owc	(10/M, 5°C min) Emergency bittlery backup, Centred in CA Title 20 MAED85	PIR	Bi-level (100/35%) motion sensor for 8-15' mounting heights. Intended for use on switched circuits with external dusk to dawn switching					
	(18W, -20°C min)	PIRH	Bi-level (100/35%) matting sensor for 15-30' mounting heights. Intended for use on					
E7	Photocell, Button Type		switched circuits with external dusk to dawn switching					
MG1	(I-II)/ dimming wires pulled outside fixture (for use with an external control), ordered separately).	PIRTEGY	Bi-level (100/35%) motion sensor for 8-15 mounting heights with photocell pre- programmed for disk to dawn operation.					
Œ	Bottom conduit entry for back box (PBBW). Total of 4 entry profits.	PIRHIFGV	Bi ifere! (100/35%) motion sensor for 15-30 mounting treights with photocell pre- programmed for clock to dawn operation.					
AA.	Buy Amonics(in) Act Compliant	Networked Se	ensors/Controls					
		NUTAIR2 PIR	nughtNRWheless enabled to level motion/ambient sensor for II-19' mounting heights.					
		NLTAIR2 PIRH	nLightA/R Wireless enabled bi-level motion/ambient sensor for 15-30 mounting heights					

see page 4 for our of two functionality

DNATXD Textured natural aluminum DWHGXD Testured white-DSSTXD lextured sandstone mounting heights (Concunting heights WINGEZ LED Rev. 03/01/22

DOBXD Dark brunge

DWHXD White

DSSXD Sandstone

DNAXD Natural alienimum

DDBTXD Textored dark bronze

DBLBXD leximed black

811 Palm Street San Luis Obispo, CA 93401 P 805.594.0771 F 805.594.5137

ARCHITECT STAMP | CONSULTANT ST

Craig Archer 3030 Ramada Drive, Paso Robles CA


0 0 0


DATE 3 JUN 22 DEVELOPMENT PLAN RESUBMITTAI

> JOB NUMBER 2138

AGENCY APPROVAL

SITE LIGHTING **PLAN** 







ARCHITECT STAMP | CONSULTANT 3030 Ramada Dr, Paso Robles, CA


03 JUN 22 DEVELOPMENT PLAN RESUBMITTAI

JOB NUMBER 2138

**FIRST FLOOR DIMENSIONAL PLAN** 








# Peterbilt Paso Robles

PRC	
	SUBMITTALS & REVISIONS
DATE	ISSUE
03 JUN 22	DEVELOPMENT PLAN RESUBMITTAL
	JOB NUMBER
	2138
	2130
AGENCY APPRO	OVAL

SECOND FLOOR DIMENSIONAL PLAN


A-102





**ROOF PLAN** 

A-131



# PASO ROBLES SIGN - 10' x 30' 2805 THEATER DRIVE PASO ROBLES, CA., 93446

## DRAWING ORGANIZATION

THE ORGANIZATION OF THESE DRAWINGS IS NOT INTENDED TO CONTROL THE DIVISION OF WORK AMONG SUBCONTRACTORS. IT SHALL BE THE GENERAL CONTRACTORS RESPONSIBILITY TO DIVIDE THE WORK.

COPIES OF THESE DRAWINGS ARE SUPPLIED TO THE OWNER, THE CONTRACTOR AND OTHERS FOR USE ON THIS PARTICULAR PROJECT. ALL DRAWINGS, SPECIFICATIONS, AND COPIES OF SUCH PREPARED BY ASSOCIATED DESIGN AND ENGINEERING, INC. ARE THE PROPERTY OF ASSOCIATED DESIGN AND ENGINEERING, INC. THE DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED, OR COPIED IN ANY WAY, NOR ARE THEY TO BE ASSIGNED TO A THIRD PARTY WITHOUT FIRST OBTAINING THE WRITTEN PERMISSION OF ASSOCIATED DESIGN AND ENGINEERING, INC.

IT IS THE INTENT OF THE PLANS AND SPECIFICATIONS TO COVER ALL THINGS REQUIRED TO MAKE COMPLETE AND OPERATIVE SYSTEMS. CONTRACTOR IS TO FURNISH ALL LABOR, MATERIALS, TRANSPORTATION, EQUIPMENT, AND ANY OTHER MISCELLANEOUS SERVICES REQUIRED TO COMPLETE THE PROJECT. ANYTHING WHICH MAY BE REASONABLY CONSTRUCED AS A NECESSARY PART OF THE PROJECT IS TO BE INCLUDED WHETHER SPECIFICALLY SHOWN, MENTIONED OR NOT. THE ARCHITECT WILL GIVE ANY INTERPRETATIONS NECESSARY FOR THE CONTRACTOR TO PROPERLY ESTIMATE THE PROJECT.

## CONTRACTOR'S STATEMENT OF RESPONSIBILITY

THE DESIGN/BUILD CONTRACTORS SHALL BE FULLY AND SOLELY RESPONSIBLE AND LIABLE FOR ALL DESIGN, ENGINEERING AND CONSTRUCTION FOR HIS/HER PHASE OF THE WORK AS INDICATED ON THESE DOCUMENTS. BY THE ACT OF COMMENCING WORK ON THIS PROJECT, OR BY THEIR SIGNATURES ON DRAWINGS INCLUDED HEREIN OR TO BE SUBMITTED SEPARATELY FOR THIS PROJECT. EACH CONTRACTOR HAS DIRECTLY AND INDIRECTLY ASSUMED FULL RESPONSIBILITY FOR THE DESIGN, ENGINEERING AND CONSTRUCTION OF HIS WORK INCLUDING, BUT NOT LIMITED TO, ACCURACY, COMPLETENESS AND COMPLIANCE WITH ALL APPLICABLE CODES AND ORDINANCES AND THE REQUIREMENTS OF THE OWNER AND/OR TENANT.

COST OF ALL INSPECTIONS AND TESTS INDICATED ON THE PLANS AND SPECIFICATIONS, RECOMMENDED BY THE SOILS REPORT AND/OR REQUIRED BY ANY GOVERNMENT AGENCY. CONTRACTOR SHALL PROVIDE PROTECTION AS NECESSARY PER CITY AND LOCAL CODE REQUIREMENTS. CONTRACTOR SHAPROVIDE FIRE EXTINGUISHER'S AND ANY REQUIRED SIGNAGE AS DIRECTED BY THE LOCAL FIRE DEPARTMENT.

IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL FIELD MEASUREMENTS AND CONDITIONS FOR CONFORMANCE WITH THE PLANS SHOULD THE CONTRACTOR FIND ANY ERRORS, OMISSIONS OR DISCREPANCIES IN THE PLANS WITH RESPECT TO THE FIELD OBSERVATIONS OR OTHER PARTS OF THE PLANS THE ERRORS, OMISSIONS OR DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE PROJECT ARCHITECT, THE CONTRACTOR AND ARCHITECT SHALL RESOLVE ALL ERRORS, OMISSIONS AND DISCREPANCIES BEFORE COMMENCING THAT PORTION OF THE WORK. DIMENSIONS GOVERN ANY DISCREPANCES, ALL CHANGES TO THE PLANS SHALL REQUIRE THE APPROVAL OF THE OWNER AND PROJECT ARCHITECT.

# CODES, RULES, AND REGULATION

WITH THE FOLLOWING CODES AS ADOPTED AND AMENDED BY THE LOCAL GOVERNING AGENCY. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

2022 CALIFORNIA ADMINISTRATIVE CODE (CAC)
2022 CALIFORNIA BUILDING CODE (CBC)
2022 CALIFORNIA ELECTRIC CODE (CEC)
2022 CALIFORNIA ENERGY CODE (CENC)
2022 CALIFORNIA FIRE CODE (CFC)
SAFETY, ORDERS, STATE DIVISION OF INDUSTRIAL SAFETY TITLE 24 AND 25 CALIFORNIA
CITY ORDINANCES AND REGULATIONS
APPLICABLE SECTIONS OF THE CALIFORNIA ENERGY STANDARDS SERVING UTILITY COMPANIES

NOTE: WHERE WORK OF A HIGHER DEGREE IS INDICATED ON THE PLANS OR IN THE SPECIFICATIONS, THIS REQUIREMENT SHALL GOVERN.

# **GENERAL NOTES:**

EACH SUBCONTRACTOR SHALL VISIT THE SITE AND INSPECT THE PREMISES TO BE IMPROVED AND SHALL VERIFY THE WORK TO BE DONE, THE EXISTING CONDITIONS, AND SHALL NOTIFY THE GENERAL CONTRACTOR OF ANY AND ALL DISCREPANCIES PRIOR TO SUBMITTING BID AND STARTING OF ANY WORK. GENERAL CONTRACTOR SHALL NOTIFY THE OWNER OF ANY AND ALL DISCREPANCIES PRIOR TO SUBMITTING BID AND STARTING OF ANY WORK.

2. ALL WORK SHALL BE DONE IN THE BEST WORKMANLIKE MANNER AND MUST BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF ALL LOCAL GOVERNING AGENCIES. FURTHERMORE, ALL WORK SHALL MEET WITH THE APPROVAL OF THE OWNER.

B. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB, AND ASSOCIATED DESIGN & ENGINEERING, INC. OR THEIR AGENTS SHALL BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS SHALL BE REVIEWED BY ASSOCIATED DESIGN & ENGINEERING, INC. BEFORE PROCEEDING WITH FABRICATION.

4. THIS SET OF DRAWINGS, DESIGN AND/OR SPECIFICATION ARE THE EXCLUSIVE PROPERTY OF ASSOCIATED DESIGN & ENGINEERING, INC. ITS ACCEPTANCE CONSTITUTES AN AGREEMENT THAT IT SHOULD BE TREATED AS A STRICTLY CONFIDENTIAL DOCUMENT TO BE USED FOR NOT PURPOSE OTHER THAN TO AID IN THE ASSEMBLY, CONSTRUCTION OR OPERATION OF THE UNITS OR SYSTEMS SHOWN FOR THIS SPECIFIC PROJECT ONLY, OR AS OTHERWISE EXPRESSLY AUTHORIZED IN WRITING BY ASSOCIATED DESIGN & ENGINEERING, INC.: THAT IT IS TO BE RETURNED UPON REQUEST; AND IS NOT TO BE COMMUNICATED, DISCLOSED, OR COPIED, EXCEPT AS EXPRESSLY AUTHORIZED IN WRITING BY ASSOCIATED DESIGN & ENGINEERING, INC. EXPRESSLY RESERVES ITS COMMONLAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED, OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO A THIRD PARTY WITHOUT FIRST OBTAINING THE WRITTEN PERMISSION AND CONSENT OF ASSOCIATED DESIGN & ENGINEERING, INC. IN THE EVENT OF UNAUTHORIZED REUSE OF THESE PLANS BY A THIRD PARTY, THE THIRD PARTY SHALL HOLD ASSOCIATED DESIGN & ENGINEERING, INC. HARMLESS AND SHALL BEAR THE FINANCIAL RESPONSIBILITY OF ASSOCIATED DESIGN'S LEGAL COSTS.

5. A JOB CARD IS REQUIRED TO BE VISIBLE FROM THE STREET, IT IS UNDERSTOOD THAT IF NO JOB CARD IS OBSERVED NO INSPECTION WILL TAKE PLACE.
6. THIS PERMIT DOES NOT INCLUDE ANY HIGH PILE STORAGE OR RACK STORAGE OVER 6 FEET HIGH. ANY SUCH PROPOSED STORAGE WILL REQUIRE PLANS SUBMITTED FOR REVIEW AND APPROVAL AND ISSUANCE OF PERMITS. (2022 CFC)

1. ALL MATERIALS, EQUIPMENT AND SYSTEMS CALLED FOR ON PLANS AND IN THESE SPECIFICATIONS SHALL BE INSTALLED IN STRICT COMPLIANCE WITH THE MANUFACTURER'S LATEST SPECIFICATIONS.

B. CONTRACTORS SHALL MAINTAIN THE PREMISES IN A CLEAN AND ORDERLY CONDITION AT ALL TIMES AND SHALL REMOVE ALL UNUSED MATERIALS AND DEBRIS, AND LEAVE PREMISES IN A CLEAN CONDITION.

9. ANY SUBSTITUTIONS TO THE MATERIALS AND/OR EQUIPMENT SPECIFIED MUST B

9. ANY SUBSTITUTIONS TO THE MATERIALS AND/OR EQUIPMENT SPECIFIED MUST BE APPROVED BY THE OWNER. CONTRACTOR SHALL SUBMIT REQUEST FOR SUBSTITUTIONS AT THE TIME OF BID SUBMISSION. PRIOR TO START OF CONSTRUCTION, THE GENERAL CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE PLANS AND SPECIFICATIONS.

10. ANY DISCREPANCIES OR ERRORS SHALL BE CALLED TO THE ATTENTION OF THE ARCHITECT FOR CORRECTIONS BEFORE THE WORK EFFECTED THEREBY IS BIDDED OR EXECUTED. THE WORK SHALL COMPLY IN EVERY RESPECT WITH CURRENT GOVERNING LAWS, UNIFORM BUILDING CODE AND ORDINANCES. ALL AGENCIES AND UTILITY COMPANYS SHALL BE GIVEN NECESSARY NOTICES RELATING TO THE WORK. CONTRACTOR SHALL OBTAIN AND PAY FOR ANY PERMITS OR NOTICES. ALL TESTING AND INSPECTION SERVICES SHALL BE PAID DIRECTLY BY THE OWNER.

II. SANITARY TOILET IS REQUIRED ON-SITE DURING CONSTRUCTION. (2022 CBC

12. PORTABLE FIRE EXTINGUISHERS SHALL COMPLY WITH (2022 CBC 906 AND THE 2022 CFC 906).

13. REPAIR ALL DAMAGED AND/OR OFF-GRADE CONCRETE STREET IMPROVEMENTS AS DETERMINED BY THE CONSTRUCTION MANAGED ENGINEER PRIOR TO OCCUPANCY

14. ANY SURVEY MONUMENTS WITHIN THE AREA OF CONSTRUCTION SHALL BE PRESERVED OR RESET BY A PERSON LICENSED TO PRACTICE LAND SURVEYING IN THE STATE OF CALIFORNIA

WORKING DAYS BEFORE COMMENCING EXCAVATION OPERATIONS WITHIN THE STREET RIGHT-OF-WAY AND/OR UTILITY EASEMENTS. ALL EXISTING UNDERGROUND FACILITIES SHALL HAVE BEEN LOCATED BY UNDERGROUND SERVICES ALERT (USA), CALL 1-800-642-2444

5. HIGH STRENGTH BOLTING, EPOXY ANCHORS BOLTS, SHOP AND FIELD WELDING MUST BE INSPECTED BY APPROVED INDEPENDENT INSPECTORS WHO SHALL BE RETAINED BY THE OWNER, INSPECTORS SHALL SUBMIT THEIR REPORTS DIRECTLY TO FRESNO COUNTY DEVELOPMENT SERVICES DIVISION, INSPECTIONS FOR THIS PROJECT WILL BE PROVIDED BY:

Company Address
City, State, Zip



# AERIAL VIEW

# **CODE ANALYSIS**

: 2N CONSTRUCTION TYPE OCCUPANCY CLASSIFICATION OCCUPANCY LOAD FACTOR : N/A OCCUPANT LOAD IS OVER OCCUPANT LOAD : N/A EXIT WIDTH REQUIRED .3"xOCCUPANT LOAD AT STAIRS) (.2"xOCCUPANT LOAD TYP. EGRESS) : N/A OCCUPANCY SEPARATION : N/A FIRE RATING OF BUILDING ELEMENTS DRAFT STOPS : N/A

LOCATION ON PROPERTY (PROTECTED OPENINGS)

ALLOWABLE AREA

ALLOWABLE HEIGHT

FLAME SPREAD CLASSIFICATION
MAXIMUM FLAME SPREAD CLASS
MAXIMUM TRAVEL DISTANCE

: NOT REQUIRED : 612 SQ, FT.

: 60 FEET FROM FINISH GRADE : CLASS 2 : 26-75

MAXIMUM TRAVEL DISTANCE : N
FOR TYPICAL OCCUPANCY 200'
IF FIRE SPRINKLERS 250'

# PROJECT TEAM

OWNER

OUTFRONT MEDIA INCORPORATED
5618 E. SHIELDS AVE.
FRESNO, CA 93121
PHONE: (559) 292-8300
CONTACT: ARYNN RAMAGE

ARCHITECT

ASSOCIATED DESIGN AND ENGINEERING, INC.
351 W. CROMWELL #108
FRESNO, CA 931II
PHONE: (559) 431-2389
FAX: (559) 431-2014
CONTACT: ARMEN DEVEJIAN

CIVIL ENGINEER

KRAZAN‡ASSOC., INC.
GEOTECHNICAL
ENGINEERING DIV.
215 W. DAKOTA AVE.
CLOVIS, CA., 93612
PHONE: (559) 348-2200
CONTACT: DAVID JOROSZ/
STEVE NELSON
PROJ#012-21285
DATE 1-1-2022

CIVIL ENGINEER

STRUCTURAL ENGINEER

LORE ENGINEERING INC.


620 DEWITT AVE. #101 CLOVIS, CA., 93612 PHONE: (559) 297-5200

ASSOCIATED DESIGN AND ENGINEERING, INC. 351 W. CROMWELL #108 FRESNO, CA 93711 PHONE: (559) 431-2389 FAX: (559) 431-2074 CONTACT: MICHAEL JUNDT, SE

GENERAL CONTRACTOR - (TO BE DETERMINED)

ADDRESS CITY, STATE, ZIP: PHONE: FAX: CONTACT:

# VICINITY MAP



# SCOPE OF WORK

INSTALLATION OF NEW 10' X 30' DIGITAL BILLBOARD

# SHEET INDEX

CI-I COVER SHEET

CI-2 SITE PLAN

SI-I SIGN DRAWINGS

SD-I STRUCTURAL DETAILS

SD-2 STRUCTURAL DETAILS

E-I ELECTRICAL SINGLE LINE DIAGRAM

E-2 ELECTRICAL SITE PLAN

E-3 ENERGY FORMS

E-4 ENERGY FORMS

NO. S3396
EXP. 9-30-23

\*
OF CALIFORN

REVISIONS


Attachment 9

REVISIONS


A
A
A
A
A

JOB NO. E23002 DATE 3/27/2023

SOUTH/NORTH ELEVATION (FULL SIGN)



# PLAN VIEW



# **SECTION A-A**

SEE DETAIL 01 SHEET SD-1

# DEFERRED SUBMITTALS

- DEFERRED SUBMITTALS ARE THOSE PORTIONS OF THE DESIGN WHICH ARE NOT SUBMITTED AT THE TIME OF PERMIT APPLICATION AND WHICH ARE TO BE SUBMITTED TO THE PERMITTING AGENCY FOR ACCEPTANCE PRIOR TO INSTALLATION OF THAT PORTION OF THE WORK OR ARE REQUIRED TO BE SUBMITTED FOR REVIEW ONLY BY THE ENGINEER.
- WHERE DEFERRED SUBMITTALS INCLUDE ADDITIONAL MATERIALS, INSTALLATION, ANCHORAGE, OR CERTIFICATION OF COMPONENTS THAT REQUIRE SPECIAL INSPECTION AND/OR STRUCTURAL OBSERVATION TO MEET CODE REQUIREMENTS, THE DEFERRED SUBMITTAL SHALL INCLUDE SPECIFIC LINE ITEMS TO BE ADDED TO THE APPROPRIATE TABLES IN THE PROJECT'S STATEMENT OF SPECIAL INSPECTIONS PLAN IF THEY ARE NOT ALREADY IDENTIFIED.
- THE FOLLOWING IS A LIST OF DEFERRED SUBMITTALS THAT ARE EXPECTED TO CONTAIN STRUCTURAL CALCULATIONS OR SAFETY RELATED SYSTEM INFORMATION FOR REVIEW TO MEET BUILDING PERMITTING REQUIREMENTS FOR DESIGNED SYSTEMS. PRIOR TO INSTALLATION OF THE INDICATED STRUCTURAL ELEMENT, EQUIPMENT, DISTRIBUTION SYSTEM, OR COMPONENT OR ITS ANCHORAGE, THE CONTRACTOR SHALL SUBMIT THE REQUIRED CALCULATIONS AND SUPPORTING DATA AND DRAWINGS FOR REVIEW AND ACCEPTANCE BY THE ENGINEER.

  DIGITAL PANEL ATTACHMENT METHOD

  DIGITAL PANEL FRAMING

NOTE: ALL WELDING SHALL BE PERFORMED BY AN AWS CERTIFIED WELDER. SUBMIT CERTIFICATE TO THE BUILDING INSPECTOR.



11. Engineering \2023\E23002 Outfront Paso Robles Peterbilt Site\E23002.aec 3/21/2023 II:46 AM BY CARLOSF


Attachment 9


30


REVISIONS I.R. REVISION 08/30/22


DATE

3/27/2023











WI2XI6 UPRIGHT

- W6X9 LEDGER





VARIES

TYPICAL SECTION

- WIZNIG UPRIGHT

1/4" /

**UPRIGHT & SPREADER - CONN** 

CATWALK

-24"\$ x .375"-50 ksi TORSION PIPE

- WI2X26 SPREADER

W12×26


- 24"Φ × .375"-50 kai TORSION PIPE

LOWER CATWALK


-(N) L3×3×1/4 HANGRAIL


-L3x3xI/4 STRINGERS (4 REQ'D/FACE)












COLUMN SPLICE DETAIL



0

Attachment 9

E23002 JOB NO. 3/27/2023 DATE

# BIOLOGICAL RESOURCES ASSESSMENT REPORT

# PASO ROBLES PETERBILT PROJECT 2805 THEATRE DRIVE PASO ROBLES, CALIFORNIA

**Project No. 2202-1101** 

#### Prepared for:

Craig Archer
Coast Counties Peterbilt
1740 4<sup>th</sup> Street
San Jose, California 95112

#### Prepared by:

Padre Associates, Inc. 369 Pacific Street San Luis Obispo, California 93401

**APRIL 2022** 





#### **Authenticity and Signature Page**



Padre Associates, Inc. 369 Pacific Street San Luis Obispo, California 93401

Padre Associates, Inc. hereby certifies that all statements furnished in the following Biological Resources Assessment Report and all supporting information acquired for this biological assessment are true and correct to the best of our knowledge and belief. Further, we certify that the field survey associated with this report was performed by Padre and that the report accurately represents all information retained from the field visit.

Christina Santala

**Project Biologist** 

**Alyssa Berry** Senior Biologist Shannon Gonzalez
Project Biologist

Thermon Goryalay


#### **TABLE OF CONTENTS**

1.0 INTROD	DUCTION	1-1
2.0 REGULA	ATORY FRAMEWORK	2-1
2.1 FEDE	RAL REGULATIONS	2-1
2.1.1 E	Endangered Species Act of 1972	2-1
	Aigratory Bird Treaty Act	
	E REGULATIONS	
	California Fish and Game Code.	
	AL REGULATIONS	
3.0 METHO	DS	3-1
3.1 DESK	(TOP REVIEW	3-1
3.2 FIELD	O SURVEYS	3-1
4.0 FINDING	GS	4-1
41 FNVII	RONMENTAL SETTING	4-1
	OGICAL RESOURCES	
	Botanical	
4.2.2 V	Vildlife	4-2
	Aquatic Resources	
	CIAL-STATUS BIOLOGICAL RESOURCES	
	Special-Status Habitats	
	Special-Status Botanical	
	FIAL IMPACTS	
	MENDED MITIGATION MEASURES	
	ENCES	
1.0 KEFEKE		<i>1</i> - 1
	LIST OF FIGURES	
Figure 1-1. P	roject Location	1-2
Figure 4-1. B	iological Assessment Survey Results	4-4
Figure 4-2. R	legional Special-Status Biological Resources	4-5
	APPENDICES	
Appendix A	Site Photographs	
Appendix B	Vascular Plant List	
Appendix C	Wildlife List	
Appendix D	CNDDB Results	
1 1 - 1 - 1 - 1 - 1 - 1		



#### 1.0 INTRODUCTION

Padre Associates, Inc. (Padre) has prepared this Biological Resources Assessment Report (Report) on behalf of Craig Archer of Coast Counties Peterbilt (Client) to document the results of a biological resources assessment completed in support of the environmental review process for the proposed Paso Robles Peterbilt Dealership Development Project (Project) at 2805 Theatre Drive, Paso Robles, San Luis Obispo County, California (Project Site) (Figure 1-1 – Project Location); Assessor's Parcel Number (APN) 009-851-022. This Report documents the results of a desktop review and field survey, and includes a discussion of existing biological resources, special-status biological resources that have the potential to occur within the proposed Project Site, potential Project impacts to these resources, and recommendations for impact avoidance and minimization measures.





#### 2.0 REGULATORY FRAMEWORK

The regulatory framework identifies policies and plans administered by resource agencies pertaining to biological resources that are known to exist and/or have the potential to occur within the Project region.

#### 2.1 FEDERAL REGULATIONS

#### 2.1.1 Endangered Species Act of 1972.

The Federal Endangered Species Act (FESA), administered by the U.S. Fish and Wildlife Service (USFWS), the National Oceanic and Atmospheric Administration, and the National Marine Fisheries Service (NMFS), provides protection to species listed as Threatened or Endangered, and critical habitat designated for the protection of such species. The FESA prohibits "take" of Threatened and Endangered species (including plants) except under certain circumstances and only with authorization from the USFWS through a permit under sections 4(d), 7, or 10(a) of the FESA. Under the FESA, take is defined as to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct.

Critical Habitat is defined in Section 3(5)(A) of the FESA as: (1) specific areas within the geographical area occupied by the species at the time of listing, on which are found those physical or biological features that are essential to the conservation of the listed species and that may require special management considerations or protection; and (2) specific areas outside the geographical area occupied by the species at the time of listing that are essential for the conservation of a listed species.

The FESA also provides protection to those species proposed to be listed under FESA or critical habitats proposed to be designated for such species. In addition to the listed species, the federal government also maintains lists of species that are neither formally listed nor proposed but could potentially be listed in the future. These federal candidate species include taxa for which substantial information on biological vulnerability and potential threats exist and are maintained to support the appropriateness of proposing to list the taxa as an Endangered or Threatened species.

#### 2.1.2 Migratory Bird Treaty Act

The USFWS also administers the Federal Migratory Bird Treaty Act (MBTA) of 1918 (16 USC 703-711). Under the MBTA, it is unlawful to take, possess, buy, sell, purchase, or barter any migratory bird listed in 50 CFR 10, including feathers or other parts of birds, nests, eggs or products, except as allowed by implementing regulations (50 CFR 21). In 2017, Solicitor of the Department of the Interior issued a legal opinion (M-37050 or M-Opinion) stating that "The Migratory Bird Treaty Act Does Not Prohibit Incidental Take" which in effect revoked take protections under the MBTA. On January 5, 2021, the USFWS published a final rule that defined the scope of the MBTA stating that incidental take of birds resulting from an activity is not prohibited when the underlying purpose of that activity is not to take birds. On May 6, 2021, the USFWS announced a proposed rule to revoke the January 7 final regulation that limited the scope of the MBTA, in an effort to reinstate federal MBTA protections. The proposed rule is pending as of June 2021.



In the interim, migratory birds are protected (for take) through AB 454 California Migratory Bird Protection Act (California Fish and Game Code 3513).

#### 2.2 STATE REGULATIONS

#### 2.2.1 California Fish and Game Code.

The California Department of Fish and Wildlife (CDFW) administers a number of laws and programs designed to protect plants, fish, and wildlife resources. Principal of these is the California Endangered Species Act of 1984 (CESA - Fish and Game Code Section 2050) that regulates the listing and take of State Endangered and Threatened species. CDFW also maintains lists of Candidate-Endangered species and Candidate-Threatened species. California candidate species are afforded the same level of protection as listed species. CDFW manages the California Native Plant Protection Act of 1977 (Fish and Game Code Section 1900, et seq.), which was enacted to identify, designate, and protect rare plants. The California Native Plant Society (CNPS) operates under a Memorandum of Understanding (MOU) with the CDFW which outlines broad cooperation in rare plant assessment and protection and formalizes cooperative ventures such as data sharing and production of complementary information sources for rare plants.

#### 2.3 LOCAL REGULATIONS

San Luis Obispo County (County) incorporates all USFWS, CDFW, Regional Water Quality Control Board (RWQCB), and U.S. Army Corps of Engineers (ACOE) standards when assessing project impacts to vegetation, wildlife, and wetland habitats, as well as the California Environmental Quality Act (CEQA) evaluation process, when applicable. The County has developed a framework of land use policies and recommendations intended to reduce impacts to sensitive biological resources.

Oak trees are protected under San Luis Obispo County Land Use Ordinance, Title 22; Chapters 22.56 (Tree Preservation) and 22.58 (Oak Woodland Ordinance) (San Luis Obispo County 2021).



#### 3.0 METHODS

Methods to collect biological resources information included a desktop review and field survey of the Biological Study Area (BSA), which encompassed the entire Project Site.

#### 3.1 DESKTOP REVIEW

Prior to conducting the field survey, a query of the CDFW California Natural Diversity Data Base (CNDDB) was conducted to identify documented occurrences of special-status plant and wildlife species, and sensitive habitats within the vicinity of the BSA. The CNDDB is a continually refined and updated computerized inventory of rare animals, plants, and natural community location information in California, including species that are listed as federally and/or State endangered/threatened. All wildlife taxa listed with the CNDDB are considered "special animals" in which the CDFW is interested in tracking, regardless of their legal protection status.

The Project Site is located within the Templeton 7.5-minute United States Geological Survey (USGS) quadrangle, and the CNDDB search was focused on this and eight adjacent quadrangles within approximately ten miles of the BSA, including Paso Robles, Estrella, Creston, Santa Margarita, Atascadero, Morro Bay North, York Mountain, and Adelaida. The USFWS Critical Habitat database was also investigated to identify critical habitat for federally listed species within the BSA or surrounding region. In addition, the USFWS National Wetlands Inventory (NWI) was accessed to identify previously documented wetlands within the BSA or surrounding area.

#### 3.2 FIELD SURVEYS

On March 31, 2022, Padre Biologists, Christina Santala and Shannon Gonzalez completed a field survey within the BSA focused on the existing biological resources, presence/absence of special-status plant and wildlife species and habitats, as well as the suitability of habitat to support these species within the BSA.

Field survey methods consisted of walking paths of opportunity throughout the BSA and recording wildlife species observed by visual observation using binoculars, indirect signs (e.g., tracks, scat, skeletal remains, and burrows), and/or auditory cues (i.e., calls and songs). Field notes on botanical resources and vegetation communities/habitats were also recorded. Field surveys were conducted in March, within the typical blooming period for most special-status plant species know to occur in the proposed Project region.

Vegetation within the BSA was divided and classified into vegetation types based on *A Manual of California Vegetation*, *Second Edition* (MCV2) (Sawyer, et. al., 2009), or described as site-specific vegetation and/or land use cover types not treated in the MCV2 (i.e., ruderal). All identifiable plant species observed within the BSA were documented. Plant specimens that were not positively identified in the field were further examined using appropriate botanical keys, including *The Jepson Manual Vascular Plants of California* (Baldwin et. al., 2012).



#### 4.0 FINDINGS

The following discussion of biological resources includes those that were observed within the BSA, those identified in the desktop review, and resources that have the potential to occur based on the presence of suitable habitat. Supporting documentation includes Figure 4-1 – Biological Resources Assessment Results, Figure 4-2 – Regional Special-Status Biological Resources, Appendix A – Site Photographs, Appendix B – Plant List, Appendix C – Wildlife List, and Appendix D – CNDDB Results.

#### 4.1 ENVIRONMENTAL SETTING

The Project Site is located on the corner of Nutwood Circle and Theatre Drive, just west of Highway 101 in the City of Paso Robles, San Luis Obispo County, California. The Project Site is a vacant lot surrounded by residential and commercial development, with areas of previous disturbance (e.g., tilling, stockpiling, grading, etc.) and old infrastructure throughout the property. The topography of the area is level to moderately sloping and is situated on the eastern edge of the Santa Lucia Range.

#### 4.2 BIOLOGICAL RESOURCES

#### 4.2.1 Botanical

A list of plant species identified in the BSA during the March 2022 field survey is provided in Appendix B – Plant List. Vegetation communities documented to occur within the Project Site are described in the following paragraphs.

Wild oats and annual brome grassland (Avena spp. – Bromus spp. Herbaceous Semi-Natural Alliance). The Wild oats and annual brome grassland alliance occurs in all topographic settings in foothills, waste places, rangelands, and openings in woodlands. This alliance is characterized by presence of slender wild oats (Avena barbata), wild oats (Avena fatua), false brome (Brachypodium distachyon), rattlesnake grass (Briza maxima), ripgut brome (Bromus diandrus), soft chess (Bromus hordeaceus) and/or foxtail barley (Hordeum murinum) as dominant or co-dominant with other non-natives in the herbaceous layer; cover is open to continuous (Sawyer et. al., 2009). As observed during the field survey, this alliance occurred throughout the BSA. Dominant to co-dominant species included ripgut brome, wild oats, Mediterranean vetch (Vicia benghalensis), tocalote (Centaurea melitensis), red brome (Bromus madritensis ssp. rubens), redstem filaree (Erodium cicutarium), with sparse to moderate occurrences of common fiddleneck (Amsinckia intermedia), telegraph weed (Heterotheca grandiflora) and wild radish (Raphanus sativus). There were several sapling and mature valley oak (Quercus lobata) trees scattered throughout this vegetation alliance within the BSA. This alliance is not considered sensitive by the CDFW and is not protected under CEQA.

**Ornamental.** Within this Report, Ornamental is a site-specific vegetation classification that describes the planted landscape trees and shrubs within the BSA. As observed during the field survey, tree species included blue gum (*Eucalyptus globulus*), pine (*Pinus* sp.) and Coast live oak (*Quercus agrifolia*). Ornamental trees may provide suitable foraging and nesting habitat for fauna. This vegetation community is not considered sensitive by the CDFW and is not protected under CEQA.

**Ruderal.** Within this Report, Ruderal is a term used to describe the unpaved parking area within the BSA. This disturbed area can support vegetative cover consisting primarily of disturbance adapted plant species (ruderal species). As observed during the field survey, the Ruderal area consisted of bare ground with patches of non-native species including cheeseweed (*Malva parviflora*), redstem filaree, and barley. This vegetation community is not considered sensitive by the CDFW and is not protected under CEQA.

#### 4.2.2 Wildlife

Wildlife was identified during the survey through indirect sign and direct observations of individuals. Species observed and detected included western fence lizard (*Sceloporus occidentalis*), California scrub jay (*Aphelocoma californica*), acorn woodpecker (*Melanerpes formicivorus*), house finch (*Haemorhous mexicanus*), and Botta's pocket gopher (*Thomomys bottae*). A complete list of observed wildlife species can be found in Appendix C – Wildlife Species Observed within the BSA.

#### 4.2.3 Aquatic Resources

Based on the results of the desktop review and field observations, no aquatic resources were identified within the Project Site; however, several aquatic features were identified within one mile of the BSA. The NWI recorded features include a Riverine unnamed drainage approximately 0.07 miles south, the Salinas River approximately 0.8 miles east, a Freshwater Emergent Wetland approximately 0.3 miles northwest, and two Freshwater Ponds approximately 0.4 miles west of the BSA (USFWS, 2022b). In addition, an unrecorded drainage basin approximately 0.01 miles west of the Project Site was observed within the BSA during the March 2022 survey. This man-made basin appeared to collect water run-off from the street drain off Nutwood Circle and was vegetated with plant species similar to the surrounding grassland including tocalote, redstem filaree, and annual grasses. A fenced drainage basin was also present within the Project Site and supported vegetation similar to the surrounding grassland. No water was present in these aquatic features.

#### 4.2.4 Oak Trees

Six valley oak trees of varying diameter at breast height (DBH) were observed throughout the Project Site (Figure 4-1). DBH for the six oak trees were as follows: 54 inches, 48 inches, 8 inches, 4 inches, and 4 inches.


#### 4.3 SPECIAL-STATUS BIOLOGICAL RESOURCES


Results of the nine-quadrangle (approximately ten miles surrounding the Project Site) CNDDB query for regional occurrences of special-status plant and wildlife species, and sensitive vegetation communities can be found in Appendix D (CDFW, 2022a). This Report focuses on the special-status plants and wildlife biological resources within five miles of the BSA (Project region)

Paso Robles Peterbilt Project Biological Resources Assessment Report April 2022 (2202-1101)



that have a greater potential to occur within the Project Site based on proximity of documented occurrences. Figure 4-2 depicts CNDDB occurrences and USFWS Critical Habitat within five miles of the Project Site.







#### 4.3.1 Special-Status Habitats

No USFWS-Designated Critical Habitat overlaps the BSA. The nearest occurrence is vernal pool fairy shrimp (*Branchinecta lynchi*) USFWS-Designated Critical Habitat approximately 5.4 miles northeast of the BSA (USFWS, 2022a).

Valley Oak Woodland, a sensitive natural community defined by CDFW, is documented within five miles of the BSA; however, this natural community is not present within the Project Site (CDFW, 2022a).

#### 4.3.2 Special-Status Botanical

Special-status plants are either listed as Endangered or Threatened under FESA or CESA, considered Rare under the California Native Plant Protection Act, or considered rare (but not legally listed) by resources agencies, professional organizations, and the scientific community under the following categories:

- 1. Plants listed or proposed for listing as Threatened or Endangered under the Federal Endangered Species Act (50 CFR 17.12 for listed plants and various notices in the Federal Register for proposed species,).
- 2. Plants that are candidates for possible future listing as Threatened or Endangered under the Federal Endangered Species Act (Federal Register October 10, 2019).
- 3. Plants that meet the definitions of rare or endangered species under the CEQA (State CEQA Guidelines, Section 15380).
- 4. Plants considered by the CNPS to be "Rare, Threatened, or Endangered" in California (Ranks 1B and 2 in CNPS, 2020).
- 5. Plants listed by CNPS as plants about which we need more information and plants of limited distribution (Ranks 3 and 4 in CNPS, 2020).
- 6. Plants listed or proposed for listing by the State of California as Threatened or Endangered under the California Endangered Species Act (14 CCR 670.5).
- 7. Plants listed under the California Native Plant Protection Act (California Fish and Game Code 1900 et seq.).
- 8. Plants considered sensitive by other Federal agencies (i.e., U.S. Forest Service, Bureau of Land Management), state and local agencies or jurisdictions.
- 9. Plants considered sensitive or unique by the scientific community or occurring at the limits of their natural range (State CEQA Guidelines).

Based on the CNDDB query completed as part of the desktop review, there were 43 special-status plant species documented within approximately ten miles of the BSA (Appendix D). Of these species, one species, Lemmon's jewelflower (*Caulanthus lemmonii*), had a greater potential to occur within the Project Site based on proximity of documented occurrences (less than five miles) and presence of generally suitable habitat (grassland) within the BSA.

No special-status plant species were observed during the March 2022 field survey. The survey was conducted within the typical blooming period for potentially occurring special-status plant species of the region and would be identifiable in March. Based on the field survey observations and habitat conditions (dominance of disturbance-adapted plant species) no special-status plant species are likely to occur within the Project Site.

#### 4.3.3 Special-Status Wildlife

Special-status wildlife species are either listed as Endangered or Threatened under FESA or CESA, or considered rare (but not formally listed) by resources agencies, professional organizations, and the scientific community under the following categories:

- Animals listed or proposed for listing as Threatened or Endangered under the Federal Endangered Species Act (50 CFR 17.11 for listed animals and various notices in the Federal Register for proposed species).
- Animals that are candidates for possible future listing as Threatened or Endangered under the Federal Endangered Species Act (Federal Register October 10, 2019).
- Animals that meet the definitions of rare or endangered species under the CEQA (State CEQA Guidelines, Section 15380)
- Animal considered Species of Special Concern (SSC) by CDFW (Shuford and Gardali, 2008 for birds; Williams, 1986 for mammals; Moyle et al., 2015 for fish; and Thomson et al., 2016 for amphibians and reptiles).
- Animals listed or proposed for listing by the State of California as Threatened and Endangered under the California Endangered Species Act (14 CCR 670.5).
- Animal species that are fully protected in California (California Fish and Game Code, Section 3511 [birds], 4700 [mammals], and 5050 [reptiles and amphibians]).
- Animal species protected under the Marine Mammal Protection Act (as amended in 1994).
- Birds of Conservation Concern. Migratory and nonmigratory bird species (beyond those already designated as federally Threatened or Endangered) that represent the USFWS highest conservation priorities in effort to draw attention to species in need of conservation action (Shuford and Gardali, 2008).
- Birds on the CDFW Watch List include "Taxa to Watch" (Shuford and Gardali, 2008)
   1) not on the current Special Concern list but were on previous lists and they have not been state listed under CESA; 2) were previously state or federally listed and now are on neither list; or 3) are on the list of "Fully Protected" species.

Based on the CNDDB query completed as part of the desktop review, there were 38 special-status wildlife species documented within approximately ten miles of the BSA. Of those 38, there are three special-status wildlife species with the potential to occur within the Project Site based on suitable habitat and regional (less than five miles) documented occurrences. These species include Northern California legless lizard (*Anniella pulchra*), American badger (*Taxidea taxus*), and San Joaquin kit fox (*Vulpes macrotis mutica*).



No special-status wildlife species were observed during the March 2022 field survey. However, the Project Site may provide suitable habitat to support the special-status wildlife species listed above. The following sections provide an overview of the general habitat requirements for these species and further detail on the potential for each of these species to occur in the Project Site.

#### 4.3.3.1 Reptiles

Northern legless lizard is a predominantly subterranean lizard that occupies moist, warm, and loose soils with vegetative cover (Stebbins, 2003). It has the potential to utilize areas of the Project Site that have dense leaf litter. Refer to Section 6.0 for recommended mitigation measures for protection of Northern legless lizard during Project activities.

#### 4.3.3.2 Mammals

American badger is a CDFW Species of Special Concern and San Joaquin kit fox is listed as Federally Endangered and State Threatened. The annual grassland habitat, and presence of small mammal (ground squirrel) burrows indicate that general conditions within the Project Site are suitable for both species. No large burrows or sign (i.e., scat, tracks, prey remains, etc.) were identified during the March 2022 survey. Further, the Project Site is situated adjacent to Highway 101 and is surrounded by residential and commercial development that creates significant dispersal barriers for these species. However, because there are documented occurrences within five miles, and generally suitable grassland habitat is, there is a low potential for American badger and San Joaquin kit fox to occur within the Project Site. Refer to Section 6.0 for recommended mitigation measures for protection of these species during Project activities.

#### 4.3.3.3 Nesting Birds

No nesting bird activity was observed within the BSA during the March 2022 field survey; however, trees and vegetation present within or adjacent to the Project Site provide suitable nesting habitat for a variety of bird species. Nesting birds and their nests/eggs are protected under the federal Migratory Bird Treaty Act of 1918 and California Fish and Game Code. Nesting bird season generally occurs between February 1 and August 31. Refer to Section 6.0 for recommended mitigation measures for protection of potentially nesting birds during Project activities.



#### 5.0 POTENTIAL IMPACTS

The proposed Project would include development of most of the Project Site. Grading and construction activities have the potential to impact special-status biological resources that have the potential to occur within the Project Site.

Potential impacts to special-status biological resources are construction-related, including mortality or injury from equipment operations, vehicle traffic, and loss of habitat. Project-related noise also has the potential to negatively affect nesting bird activity within or adjacent to the Project Site. Refer to Section 6.0 for recommended mitigation measures to avoid and/or minimize impacts to special-status biological resources.



#### 6.0 RECOMMENDED MITIGATION MEASURES

Implementation of the following avoidance and minimization measures are recommended to protect sensitive biological resources to the greatest extent feasible during proposed Project activities:

- 1. <u>Work Timing.</u> All work activities shall be completed during daylight hours (between sunrise and sunset) and outside of rain events;
- Work Limits. The Project impact area shall be clearly marked or delineated with stakes, flagging, tape, or signage prior to work. Areas outside of work limits shall be considered environmentally sensitive and shall not be disturbed;
- 3. Vehicles and Equipment. All equipment and vehicles shall be checked and maintained daily to prevent spills of fuel, oil, and other hazardous materials. A designated staging area shall be established for vehicle/equipment parking and storage of fuel, lubricants, and solvents. All fueling and maintenance activities shall take place in the staging area;
- 4. Pre-Activity Nesting Bird Survey. If vegetation removal (i.e., tree trimming/removal activities) is scheduled between February 1 and August 31 (general nesting bird season), nesting bird surveys shall be completed by a qualified biologist within 48 hours prior to start of work. If any active nests are discovered within or adjacent to work limits, an appropriate buffer (i.e., 500 feet for raptors and 250 feet for other birds, or at the discretion of a qualified biologist based on biological or ecological reasons) shall be established to protect the nest until a qualified biologist has determined that the nest is no longer active and/or the young have fledged;
- 5. Pre-Activity Special-Status Species Survey. Within 30 days of the start of construction, a qualified biologist shall conduct a pre-activity survey of the Project Site for signs of San Joaquin kit fox and American badger, including tracks, scat, or suitable burrows (burrows four inches or greater in diameter). Potential dens shall be tracked for a minimum of four nights with motion-activated cameras to determine if the burrow is actively being used by San Joaquin kit fox or badger. All potential dens shall be avoided by a minimum of 50 feet until they have been determined to be inactive. In the event San Joaquin kit fox is identified within the Project Site, the USFWS, CDFW, and all other appropriate agencies/government entities shall be contacted for further consultation.

In conjunction with the badger and kit fox survey, the qualified biologist will conduct a survey for Northern legless lizard. Hand search methods, including raking, will be used during the survey in areas where legless lizards are expected to be found (e.g., sandy/loose soils, under shrubs/leaf litter, other vegetation, or debris). If observed, the qualified biologist will relocate the lizard to nearby suitable habitat. The qualified biologist will prepare a completion letter-report to document the pre-activity survey results.

6. <u>Oak Tree Removal.</u> If oak tree removal and/or damage is unavoidable due to Project implementation, the County may require mitigation for impacts to mature oak trees.

Paso Robles Peterbilt Project Biological Resources Assessment Report April 2022 (2202-1101)



Mitigation may require preparation of an oak tree protection and replacement plan that would provide guidance for onsite and/or offsite oak tree replacement planting.

#### 7.0 REFERENCES

- Baldwin, Bruce G., Goldman, Douglas H., Keil, David J., Rosatti, Thomas J. 2012. The Jepson Manual: Vascular Plants of California, Second Edition. University of California Press. Berkeley, California.
- California Department of Fish and Wildlife (CDFW). 2022a. California Natural Diversity Database (CNDDB) Rare Find Paso Robles, Estrella, Creston, Santa Margarita, Atascadero, Morro Bay North, York Mountain, and Adelaida.7.5-minute U.S. Geological Survey (USGS) quadrangles.
- ----- 2022b. Special Animals List. State of California Natural Resources Agency Department of Fish and Wildlife Biogeographic Data Branch California Natural Diversity Database (CNDDB). October 2021.
- Calflora. 2022. Information on California plants for education, research and conservation. [web application]. 2022. Berkeley, California: The Calflora Database [a non-profit organization]. Available: <a href="https://www.calflora.org/">https://www.calflora.org/</a> (Accessed March 2022).
- California Native Plant Society, Rare Plant Program. 2022. Inventory of Rare and Endangered Plants of California (online edition, v8-03 0.39). Website http://www.rareplants.cnps.org [accessed March 2022].
- San Luis Obispo County. San Luis Obispo County Municipal Code; Title 22 –Land Use Ordinance; Article 5 Site Development Standards; Title 22; Chapter 22.56 Tree Preservation and Chapter 22.58 Oak Woodland Ordinance.
- Sawyer, John O., Keeler-Wolf, Todd, Evens, Julie. 2009. A Manual of California Vegetation Second Edition. California Native Plant Society. Berkeley, California.
- Stebbins, Robert C. 2003. A Field Guide to Western Reptiles and Amphibians, Third Edition. Houghton Mifflin Company. New York, NY.
- United States Fish and Wildlife Service (USFWS). 2022a. Critical Habitat Portal. Retrieved from <a href="https://ecos.fws.gov/ecp/report/table/critical-habitat.html">https://ecos.fws.gov/ecp/report/table/critical-habitat.html</a>.
- ----- 2022b. National Wetlands Inventory (NWI). Wetlands Mapper. Retrieved from <a href="https://www.fws.gov/wetlands/data/Mapper.html">https://www.fws.gov/wetlands/data/Mapper.html</a>.

# **APPENDIX A**

**Site Photographs** 





Photo 1. Representative view of Wild oats and annual brome grassland vegetation within the BSA.



Photo 2. Representative view of valley oak tree and Ornamental vegetation within the BSA.



Photo 3. Ruderal area adjacent to Theater Drive.



Photo 4. Representative view of vegetated soil/gravel stockpile feature within the BSA.



Photo 5. Fenced drainage basin within the BSA.



Photo 6. View of storm drain and culvert to direct flow from Nutwood Circle into shallow drainage basin located off-site (north) of the Project Site.

# **APPENDIX B**

**Plant List** 

# List of Plant Species Observed Paso Robles Peterbilt Biological Resources Assessment, Paso Robles, CA

# **Attachment 9**

				Wetland	<i>-</i>	llacii	ment
FAMILY	Scientific Name	Common Name	Habit	Indicator Status	Native Status	Cal-IPC Rating	Listing Status
ARALIACEAE	Hedera helix	English ivy	PV	FACU		High	
ASTERACEAE	Baccharis pilularis	Coyote brush	S	-	N		
	Centaurea melitensis	Tocalote	AH	-		Moderate	
	Heterotheca grandiflora	Telegraph weed	AH	-			
	Hypocharus glabra	Smooth cat's ear	AH	-		Limited	
	Silybum marianum	Milk thistle	A/PH	-		Limited	
	Uropappus lindleyi	Silverpuffs	AH	-	N		
BORAGINACEAE	Amsinckia intermedia	Common fiddleneck	AH	-	N		
BRASSICACEAE	Brassica nigra	Black mustard	AH	-		Moderate	
	Raphanus sativus	Wild radish	AH	-		Limited	
CONVOLVULACEAE	Convolvulus arvensis	Bindweed	PH	-			
CUPRESSACEAE	Hesperocyparis macrocarpa*	Monterey cypress	Т	-	N		1B.2
FABACEAE	Vicia benghalensis	Mediterranean vetch	AH/V	-			
FAGACEAE	Quercus agrifolia*	Coast live oak	Т	-	N		
	Quercus lobata	Valley oak	Т	FACU	N		
GERANIACEAE	Erodium cicutarium	Redstem filaree	AH	-		Limited	
MALVACEAE	Malva parviflora	Cheese-weed	AH	-			
POACEAE	Avena barbata	Slender wild oats	AG	-		Moderate	
	Avena fatua	Wild oats	AG	-		Moderate	
	Bromus diandrus	Ripgut grass	AG	-		Moderate	
	Bromus hordeaceus	Soft chess	AG	FACU		Limited	
	Bromus madritensis ssp. rubens	Red brome	AG	-		High	
	Festuca myuros	Rattail fescue	AG	FACU		Moderate	
	Hordeum murinum ssp. leporinum	Barley	AG	FACU			
POLYGONACEAE	Rumex crispus	Curly dock	PH	FAC		Limited	
PINACEAE	Pinus radiata*	Monterey pine	Т	-	N		
	Larix sp.*	Larch	Т	-			
RUBIACEAE	Galium aparine	Bedstraw	AH	FACU	N		

Notes:

Scientific nomenclature follows Baldwin (2012).

N - Native species

Habit definitions:

AG - Annual grass.

AH - Annual herb.

F - Fern

PG - Perennial grass.

<sup>\*</sup> Planted as landscape tree

# List of Plant Species Observed Paso Robles Peterbilt Biological Resources Assessment, Paso Robles, CA

# Attachment 9

PH - Perennial herb.

PV - Perennial vine.

S - Shrub

T - Tree

Wetland indicator status (Lichvar and Kartesz, 2016):

OBL (Obligate Wetland Plants) - Almost always occur in wetlands.

FACW (Facultative Wetland Plants) - Usually occur in wetland, but may occur in non-wetlands.

FAC (Facultative Wetland Plants) - Occur in wetlands and non-wetlands.

FACU (Facultative Upland Plants) - Usually occur in non-wetlands, but may occur in wetlands.

UPL (Upland Plants) - Almost always occur in non-wetlands.

#### Cal-IPC (California Invasive Plant Council) Ratings:

High - These species have severe ecological impacts on physical processes, plant and animal communities, and vegetation structure. Most are widely distributed ecologically. Moderate - These species have substantial and apparent-but generally not severe-ecological impacts on physical processes, plant and animal communities, and vegetation Limited - These species are invasive but their ecological impacts are minor on a statewide level or there was not enough information to justify a higher score.

#### Listing Status:

FE - Federally endangered

FT - Federally threatened

SE - State endangered

ST - State threatened

CNPS (California Native Plant Society) Ranking System; CRPR (California Rare Plant Rank):

1A - Plants presumed extirpated in California and either rare or extinct elsewhere

1B - Plants rare, threatened, or endangered in California and elsewhere

2A - Plants presumed extirpated in California, but common elsewhere

2B - Plants, rare, threatened, or endangered in California, but more common elsewhere

3 - Plants about which more information is needed - a review list

4 - Plant of limited distribution - a watch list

#### **CRPR Threat Ranks:**

0.1 - Seriously threatened in California

0.2 - Moderately threatened in California

0.3 - Not very threatened in California

# **APPENDIX C**

Wildlife List

# Wildlife Species Observed within the BSA 2805 Theatre Drive, Paso Robles, California

	2805 Theatre Driv	e, Paso Robles, Califor	Aţ	tachme
Common Name	Scientific Name	Residence Status	Protected Status	Habitat
Reptiles				
Western fence lizard	Sceloporus occidentalis	R		G, D, P, S, M
Birds	·			
Acorn woodpecker	Melanerpes formicivorus	R	М	Р
California scrub-jay	Aphelocoma californica	R	M	R, G, P
House finch	Haemorhous mexicanus	R	М	P, D, M
Mourning dove	Zenaida macroura	R	M	P, D, M
Northern mockingbird	Mimus polyglottos	R	M	S, G, D, M
Red-tailed hawk	Buteo jamaicensis	R	M	G, P, M
Turkey vulture	Cathartes aura	R	M	P, M
Yellow-rumped warbler	Setophaga coronata	R	M	Р
Mammals				
Botta's pocket gopher	Thomomys bottae	R		R, G, P
California ground squirrel	Otospermophilus beecheyi	R		G, M, P

#### Notes

Fauna observed by visualizations, indirect signs (tracks, scat, skeletal remains, burros, etc.), and/or auditory cues.

	Protected Status	Typical Habitat
Residence Status	FE - Federal	A - Aquatic
R - Permanent resident	FT - Federal threatened species	D - Developed areas
W - Winter resident	FC - Federal candidate species	G - Grassland
B - Summer resident	M - Migratory Bird Treaty Act	M - Multiple habitats
	SE - State endangered species	P - Woodland
	ST - State threatened species	R - Riparian
	CS - Candidate species for CESA	W - Wetland
	CSC - California Species of Special Concern	C - Coastal lagoons, shores, oceans
	CFP - California Fully Protected Species	O - Rock outcrops
	BCC - Bird of Conservation Concern (USFWS)	S - Scrub

Updated November 2021 Page 1

# **APPENDIX D**

**CNDDB Results** 



#### California Department of Fish and Wildlife



**California Natural Diversity Database** 

#### **Query Criteria:**

Quad<span style='color:Red'> IS </span>(Templeton (3512056)<span style='color:Red'> OR </span>Paso Robles (3512066)<span style='color:Red'> OR </span>Estrella (3512065)<span style='color:Red'> OR </span>Creston (3512055)<span style='color:Red'> OR </span>Atascadero (3512046)<span style='color:Red'> OR </span>Atascadero (3512046)<span style='color:Red'> OR </span>Atascadero (3512046)<span style='color:Red'> OR </span>Atascadero (3512046)<span style='color:Red'> OR </span>Adelaida (3512067))<br/>
/><span style='color:Red'> OR </span>Adelaida (3512067))<br/>
/><span style='color:Red'> OR </span>Aclaida (3512067))<br/>
/><span style='color:Red'> OR </span>Scrub<span style='color:Red'> OR </span>Scrub<span style='color:Red'> OR </span>Bel-color:Red'> OR </span>Bel-co

				Elev.		E	Elem	ent C	cc. F	Rank	s	Population	on Status		Presence	!
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	А	В	С	D	х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Abies bracteata bristlecone fir	G2G3 S2S3	None None	Rare Plant Rank - 1B.3 IUCN_NT-Near Threatened SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden USFS_S-Sensitive		80 S:1	0	0	0	0	0	1	1	0	1	0	0
Agelaius tricolor tricolored blackbird	G1G2 S1S2	None Threatened	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_EN-Endangered NABCI_RWL-Red Watch List USFWS_BCC-Birds of Conservation Concern	684 1,036	955 S:3		0	0	0	0	3	1	2	3	0	0
Agrostis hooveri Hoover's bent grass	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive USFS_S-Sensitive	1,000 1,000	31 S:1	0	0	0	0	0	1	1	0	1	0	0
Ammodramus savannarum grasshopper sparrow	G5 S3	None None	CDFW_SSC-Species of Special Concern IUCN_LC-Least Concern	984 984	27 S:1	0	0	1	0	0	0	0	1	1	0	0
Anniella pulchra Northern California legless lizard	G3 S3	None None	CDFW_SSC-Species of Special Concern USFS_S-Sensitive	80 1,263	383 S:10		1	0	0	0	9	9	1	10	0	0
Antirrhinum ovatum oval-leaved snapdragon	G3 S3	None None	Rare Plant Rank - 4.2	720 720	16 S:1	0	0	0	0	0	1	1	0	1	0	0



## California Department of Fish and Wildlife



				Elev.		E	Elem	ent O	cc. F	Ranks	5	Population	on Status		Presence	
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	Х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Antrozous pallidus pallid bat	G4 S3	None None	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_LC-Least Concern USFS_S-Sensitive WBWG_H-High Priority	175 1,050	420 S:2	0	1	0	0	0	1	1	1	2	0	0
Aquila chrysaetos golden eagle	G5 S3	None None	BLM_S-Sensitive CDF_S-Sensitive CDFW_FP-Fully Protected CDFW_WL-Watch List IUCN_LC-Least Concern USFWS_BCC-Birds of Conservation Concern	720 1,340	324 S:2	1	1	0	0	0	0	1	1	2	0	0
Arctostaphylos luciana Santa Lucia manzanita	G2 S2	None None	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_UCSC-UC Santa Cruz USFS_S-Sensitive	2,700 2,700	10 S:1	0	0	0	0	0	1	1	0	1	0	0
Arctostaphylos pilosula Santa Margarita manzanita	G2? S2?	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	955 1,400	58 S:4		0	0	0	0	3	2	2	4	0	0
Ardea herodias great blue heron	G5 S4	None None	CDF_S-Sensitive IUCN_LC-Least Concern	996 996	156 S:1	0	0	0	0	0	1	0	1	1	0	0
Astragalus didymocarpus var. milesianus Miles' milk-vetch	G5T2 S2	None None	Rare Plant Rank - 1B.2	1,250 1,250	16 S:3	0	0	0	0	0	3	3	0	3	0	0
Atractelmis wawona Wawona riffle beetle	G3 S1S2	None None		231 231	80 S:1	0	0	0	0	0	1	0	1	1	0	0
Batrachoseps minor lesser slender salamander	G1 S1	None None	CDFW_SSC-Species of Special Concern IUCN_DD-Data Deficient USFS_S-Sensitive	895 1,376	8 S:7	0	0	0	0	0	7	1	6	7	0	0



## California Department of Fish and Wildlife



		1											<b>0</b> 1 1		_	
				Elev.			Elem	ent C	CC. F	Ranks	3	Population	on Status		Presence	· •
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Bombus caliginosus obscure bumble bee	G4? S1S2	None None	IUCN_VU-Vulnerable	1,200 1,200	181 S:1	0	0	0	0	0	1	1	0	1	0	0
Bombus crotchii Crotch bumble bee	G3G4 S1S2	None None		900 1,300	437 S:3	0	0	0	0	0	3	3	0	3	0	0
Branchinecta lynchi vernal pool fairy shrimp	G3 S3	Threatened None	IUCN_VU-Vulnerable	725 1,125	795 S:6	0	2	3	1	0	0	4	2	6	0	0
Buteo regalis ferruginous hawk	G4 \$3\$4	None None	CDFW_WL-Watch List IUCN_LC-Least Concern USFWS_BCC-Birds of Conservation Concern	995 995	107 S:1	0	1	0	0	0	0	0	1	1	0	0
Calochortus obispoensis San Luis mariposa-lily	G2 S2	None None	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	1,300 1,700	46 S:3	0	1	0	0	0	2	0	3	3	0	0
Calochortus simulans La Panza mariposa-lily	G2 S2	None None	Rare Plant Rank - 1B.3 SB_CRES-San Diego Zoo CRES Native Gene Seed Bank SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	1,000 1,600	109 S:14	0	5	2	3	0	4	4	10	14	0	0
Calycadenia villosa dwarf calycadenia	G3 S3	None None	Rare Plant Rank - 1B.1 SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	984 1,130	59 S:4	0	2	0	0	0	2	4	0	4	0	0
Camissoniopsis hardhamiae Hardham's evening-primrose	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive USFS_S-Sensitive	1,100 1,600	22 S:7	3	3	0	0	0	1	6	1	7	0	0
Carex obispoensis San Luis Obispo sedge	G3? S3?	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	1,600 2,500	29 S:3	1	0	0	0	0	2	2	1	3	0	0



# California Department of Fish and Wildlife



				Elev.		E	Elem	ent C	CC. F	Rank	5	Population	on Status		Presence	
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Castilleja densiflora var. obispoensis	G5T2	None	Rare Plant Rank - 1B.2	75	69	0	1	2	0	0	4	3	4	7	0	0
San Luis Obispo owl's-clover	S2	None		1,580	S:7											
Caulanthus lemmonii Lemmon's jewelflower	G3 S3	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	1,000 1,000	91 S:4	0	0	0	0	0	4	4	0	4	0	0
Charadrius nivosus nivosus western snowy plover	G3T3 S2	Threatened None	CDFW_SSC-Species of Special Concern NABCI_RWL-Red Watch List USFWS_BCC-Birds of Conservation Concern	10 10	138 S:2	0	1	1	0	0	0	0	2	2	0	0
Chorizanthe breweri Brewer's spineflower	G3 S3	None None	Rare Plant Rank - 1B.3 BLM_S-Sensitive USFS_S-Sensitive	1,000 2,500	45 S:7	2	0	0	0	0	5	4	3	7	0	0
Chorizanthe rectispina straight-awned spineflower	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive USFS_S-Sensitive	1,000 1,900	38 S:10	2	1	1	0	0	6	7	3	10	0	0
Cicindela hirticollis gravida sandy beach tiger beetle	G5T2 S2	None None		10 10	34 S:2	0	0	0	0	1	1	2	0	1	0	1
Cirsium fontinale var. obispoense Chorro Creek bog thistle	G2T2 S2	Endangered Endangered	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_SBBG-Santa Barbara Botanic Garden	1,000 1,000	22 S:1	0	0	0	0	0	1	1	0	1	0	0
Cirsium occidentale var. lucianum Cuesta Ridge thistle	G3G4T2 S2	None None	Rare Plant Rank - 1B.2		9 S:1	0	0	0	0	0	1	1	0	1	0	0
Coelus globosus globose dune beetle	G1G2 S1S2	None None	IUCN_VU-Vulnerable	10 10	50 S:2	0	0	0	0	1	1	1	1	1	1	0



## California Department of Fish and Wildlife



				Elev.		E	Eleme	ent O	cc. F	Ranks	5	Population	on Status		Presence	
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Corynorhinus townsendii Townsend's big-eared bat	G4 S2	None None	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_LC-Least Concern USFS_S-Sensitive	1,000 1,000	635 S:1	0	0	1	0	0	0	0	1	1	0	0
Danaus plexippus pop. 1 monarch - California overwintering population	G4T2T3 S2S3	Candidate None	WBWG_H-High Priority USFS_S-Sensitive	15 40	383 S:2	0	1	1	0	0	0	1	1	2	0	0
Delphinium parryi ssp. blochmaniae dune larkspur	G4T2 S2	None None	Rare Plant Rank - 1B.2	40	27 S:1	0	0	0	0	0	1	1	0	1	0	0
Delphinium parryi ssp. eastwoodiae Eastwood's larkspur	G4T2 S2	None None	Rare Plant Rank - 1B.2	900 900	15 S:2	0	0	0	0	0	2	2	0	2	0	0
Delphinium umbraculorum umbrella larkspur	G3 S3	None None	Rare Plant Rank - 1B.3 BLM_S-Sensitive USFS_S-Sensitive		95 S:3	0	0	0	0	0	3	3	0	3	0	0
Dudleya abramsii ssp. bettinae Betty's dudleya	G4T2 S2	None None	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden	170 820	14 S:7	0	3	1	1	0	2	4	3	7	0	0
<b>Dudleya abramsii ssp. murina</b> mouse-gray dudleya	G4T2 S2	None None	Rare Plant Rank - 1B.3 BLM_S-Sensitive SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden	330 1,600	36 S:3	0	0	0	0	0	3	1	2	3	0	0
<b>Dudleya blochmaniae ssp. blochmaniae</b> Blochman's dudleya	G3T2 S2	None None	Rare Plant Rank - 1B.1 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden	30 562	81 S:8	0	1	0	0	0	7	3	5	8	0	0
Elanus leucurus white-tailed kite	G5 S3S4	None None	BLM_S-Sensitive CDFW_FP-Fully Protected IUCN_LC-Least Concern	1,165 1,240	180 S:2	0	2	0	0	0	0	0	2	2	0	0



## California Department of Fish and Wildlife



				Elev.		E	Eleme	ent O	cc. F	anks	,	Populatio	on Status		Presence	
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Emys marmorata western pond turtle	G3G4 S3	None None	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_VU-Vulnerable USFS_S-Sensitive	10 1,464	1404 S:27	2	14	4	0	0	7	10	17	27	0	0
Eriastrum luteum yellow-flowered eriastrum	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive USFS_S-Sensitive	860 1,900	34 S:12	3	1	1	0	0	7	6	6	12	0	0
Erigeron blochmaniae Blochman's leafy daisy	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive SB_SBBG-Santa Barbara Botanic Garden	15 15	36 S:1	0	0	1	0	0	0	0	1	1	0	0
Eucyclogobius newberryi tidewater goby	G3 S3	Endangered None	AFS_EN-Endangered IUCN_VU-Vulnerable	20 20	127 S:1	0	0	0	0	0	1	1	0	1	0	0
Extriplex joaquinana San Joaquin spearscale	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden		127 S:1	0	0	0	0	0	1	1	0	1	0	0
Fritillaria ojaiensis Ojai fritillary	G3 S3	None None	Rare Plant Rank - 1B.2 SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	1,200 1,200	49 S:1	0	0	0	0	0	1	1	0	1	0	0
Helminthoglypta walkeriana Morro shoulderband (=banded dune) snail	G1 S1S2	Threatened None	IUCN_CR-Critically Endangered	10 10	14 S:1	0	1	0	0	0	0	1	0	1	0	0
Horkelia cuneata var. puberula mesa horkelia	G4T1 S1	None None	Rare Plant Rank - 1B.1 USFS_S-Sensitive	820 875	103 S:3	0	0	0	0	0	3	3	0	3	0	0
Horkelia cuneata var. sericea Kellogg's horkelia	G4T1? S1?	None None	Rare Plant Rank - 1B.1 SB_UCSC-UC Santa Cruz USFS_S-Sensitive	600 1,140	58 S:3	0	0	0	0	0	3	3	0	3	0	0
Icaricia icarioides moroensis  Morro Bay blue butterfly	G5T2 S2	None None		25 80	12 S:2	0	0	0	0	0	2	2	0	2	0	0
Juncus luciensis Santa Lucia dwarf rush	G3 S3	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive USFS_S-Sensitive	984 984	37 S:3	0	0	0	0	0	3	3	0	3	0	0



## California Department of Fish and Wildlife



				Elev.			Elem	ent O	cc. F	Ranks	S	Population	on Status		Presence	
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	A	В	С	D	Х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Layia jonesii Jones' layia	G2 S2	None None	Rare Plant Rank - 1B.2 USFS_S-Sensitive	200 522	25 S:8	0	0	0	0	0	8	3	5	8	0	0
Lepidium jaredii ssp. jaredii Jared's pepper-grass	G2G3T1T2 S1S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive SB_SBBG-Santa Barbara Botanic Garden		12 S:1	0	0	0	0	0	1	1	0	1	0	0
Linderiella occidentalis California linderiella	G2G3 S2S3	None None	IUCN_NT-Near Threatened	968 1,076	508 S:5	0	4	0	0	0	1	0	5	5	0	C
Malacothamnus palmeri var. palmeri Santa Lucia bush-mallow	G3T2Q S2	None None	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	850 1,000	10 S:2	0	0	0	0	0	2	2	0	2	0	0
Meconella oregana Oregon meconella	G2G3 S2	None None	Rare Plant Rank - 1B.1	1,200 1,200	9 S:1	0	0	0	0	0	1	1	0	1	0	0
Monardella palmeri Palmer's monardella	G2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive USFS_S-Sensitive	1,600 1,600	24 S:2	0	0	0	0	0	2	2	0	2	0	0
Monolopia gracilens woodland woollythreads	G3 S3	None None	Rare Plant Rank - 1B.2		68 S:1	0	0	0	0	0	1	1	0	1	0	0
Navarretia fossalis spreading navarretia	G2 S2	Threatened None	Rare Plant Rank - 1B.1 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_CRES-San Diego Zoo CRES Native Gene Seed Bank	1,100 1,100	82 S:1	0	0	0	0	0	1	1	0	1	0	0
Navarretia nigelliformis ssp. radians shining navarretia	G4T2 S2	None None	Rare Plant Rank - 1B.2 BLM_S-Sensitive	700 1,571	102 S:12	0	0	5	0	0	7	6	6	12	0	0
Neotoma macrotis luciana  Monterey dusky-footed woodrat	G5T3 S3	None None	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_DD-Data Deficient	988 1,700	8 S:3	2	0	0	0	0	1	3	0	3	0	0



# California Department of Fish and Wildlife

# Attachmen 9

				Elev.		E	Eleme	ent O	cc. F	Ranks	5	Population	on Status		Presence	
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	Х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Northern Interior Cypress Forest Northern Interior Cypress Forest	G2 S2.2	None None		2,400 2,400	22 S:1	0	0	0	0	0	1	1	0	1	0	(
Oncorhynchus mykiss irideus pop. 9 steelhead - south-central California coast DPS	G5T2Q S2	Threatened None	AFS_TH-Threatened	200 400	41 S:3	0	1	0	0	0	2	3	0	3	0	(
Perognathus inornatus psammophilus Salinas pocket mouse	G2G3T2? S1	None None	CDFW_SSC-Species of Special Concern	1,220 1,225	9 S:3	2	0	0	0	0	1	3	0	3	0	(
Phrynosoma blainvillii coast horned lizard	G3G4 S3S4	None None	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_LC-Least Concern	25 25	784 S:1	0	1	0	0	0	0	1	0	1	0	(
Plagiobothrys uncinatus hooked popcornflower	G2 S2	None None	Rare Plant Rank - 1B.2 USFS_S-Sensitive	1,780 1,780	14 S:1	0	0	0	0	0	1	1	0	1	0	(
Polyphylla nubila Atascadero June beetle	G1 S1	None None		800 900	4 S:3	0	0	0	0	0	3	3	0	3	0	(
Progne subis purple martin	G5 S3	None None	CDFW_SSC-Species of Special Concern IUCN_LC-Least Concern	915 915	71 S:1	0	1	0	0	0	0	0	1	1	0	(
Pyrgulopsis taylori San Luis Obispo pyrg	G1 S1	None None		880 880	5 S:1	0	0	0	0	0	1	1	0	1	0	(
Rana boylii foothill yellow-legged frog	G3 S3	None Endangered	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_NT-Near Threatened USFS_S-Sensitive	1,010 1,010	2476 S:1	0	0	0	0	1	0	1	0	0	0	
Rana draytonii California red-legged frog	G2G3 S2S3	Threatened None	CDFW_SSC-Species of Special Concern IUCN_VU-Vulnerable	10 1,684	1671 S:21	4	10	1	3	1	2	11	10	20	1	(
Senecio aphanactis chaparral ragwort	G3 S2	None None	Rare Plant Rank - 2B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_CRES-San Diego Zoo CRES Native Gene Seed Bank	536 536	98 S:1	0	0	0	0	0	1	0	1	1	0	(



### **California Department of Fish and Wildlife**



				Elev.		Е	Eleme	ent O	cc. F	anks	;	Population	on Status		Presence	!
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	А	В	С	D	х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
Sidalcea hickmanii ssp. anomala Cuesta Pass checkerbloom	G3T1 S1	None Rare	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_SBBG-Santa Barbara Botanic Garden USFS_S-Sensitive	2,500 2,500	4 S:1	1	0	0	0	0	0	0	1	1	0	
Spea hammondii western spadefoot	G2G3 S3	None None	BLM_S-Sensitive CDFW_SSC-Species of Special Concern IUCN_NT-Near Threatened	764 1,591	1422 S:21	2	4	9	2	0	4	9	12	21	0	(
Streptanthus albidus ssp. peramoenus most beautiful jewelflower	G2T2 S2	None None	Rare Plant Rank - 1B.2 SB_CalBG/RSABG- California/Rancho Santa Ana Botanic Garden SB_UCBG-UC Botanical Garden at Berkeley USFS_S-Sensitive		103 S:2	0	0	0	0	0	2	2	0	2	0	
Suaeda californica California seablite	G1 S1	Endangered None	Rare Plant Rank - 1B.1		18 S:1	0	0	0	1	0	0	0	1	1	0	
Taricha torosa Coast Range newt	G4 S4	None None	CDFW_SSC-Species of Special Concern	965 1,700	88 S:9		3	0	1	0	4	3	6	9	0	(
<b>Taxidea taxus</b> American badger	G5 S3	None None	CDFW_SSC-Species of Special Concern IUCN_LC-Least Concern	670 1,055	594 S:16	14	2	0	0	0	0	14	2	16	0	(
Trimerotropis occulens Lompoc grasshopper	G1G2 S1S2	None None	IUCN_EN-Endangered	900 900	8 S:1	0	0	0	0	1	0	1	0	0	1	(
<b>Valley Oak Woodland</b> Valley Oak Woodland	G3 S2.1	None None		1,060 2,000	91 S:6	0	0	0	0	0	6	6	0	6	0	(
Vireo bellii pusillus least Bell's vireo	G5T2 S2	Endangered Endangered	IUCN_NT-Near Threatened NABCI_YWL-Yellow Watch List	660 710	503 S:2		0	0	0	0	1	1	1	2	0	(



### California Department of Fish and Wildlife



				Elev.		Element Occ. Ranks					5	Population Status		Presence		
Name (Scientific/Common)	CNDDB Ranks	Listing Status (Fed/State)	Other Lists	Range (ft.)	Total EO's	Α	В	С	D	Х	U	Historic > 20 yr	Recent <= 20 yr	Extant	Poss. Extirp.	Extirp.
	G4T2 S2	Endangered Threatened		658 1,049	1020 S:17	2	0	0	1	0	14	16	1	17	0	0

# CULTURAL RESOURCES INVENTORY AUTOMOTEMENT 9 AT 2805 THEATRE DRIVE, PASO ROBLES, SAN LUIS OBISPO COUNTY, CALIFORNIA

[APN: 009-851-022]



## Prepared for:

Coast Counties Peterbilt 1740 No. 4<sup>th</sup> Street San Jose, CA 95116

Prepared by:

Nancy Farrell Cultural Resource Management Services 829 Paso Robles Street Paso Robles, California 93446

Templeton 7.5' Quadrangle

May, 2022



#### **INTRODUCTION**

At the request of Craig Archer, Cultural Resource Management Services (CRMS) has conducted a literature and records search and intensive archaeological survey of a parcel at 2805 Theatre Drive, Paso Robles. This will be the new business location of the Central Coast Peterbilt dealership. The purpose of this investigation is to identify any cultural resources present on the parcel that may be affected by the proposed construction. This work was completed in order to comply with the requirements of the California Environmental Quality Act (CEQA) and the County of San Luis Obispo (Figure 1, 2, and 3).

CEQA requires lead agencies to evaluate proposed projects for their potential to impact archaeological resources (Public Resources Code Section 21082, 21083.2, and 21084.1, and California Code of Regulations 15064.5). According to the CEQA Guidelines, "historical resources" include buildings, structures, objects, districts, or sites that may possess prehistoric or historical archaeological, architectural, cultural, or scientific importance. CEQA states that if a project will have a significant effect on important cultural resources, then alternative plans or mitigation measures need to be developed. were conducted to identify and evaluate any significant prehistoric or historic cultural resources that might be impacted by the proposed construction (Exhibit A).

In addition, as part of an early participation notice, letters were sent to Native American tribes, organizations and individuals. The list of recipients was provided by the Native American Heritage Commission (NAHC), and is comprised of those groups and individuals thought to have a cultural interest in this area, notifying them of the proposed project, inviting them to consult, and requesting information or concerns regarding the proposed project. A Sacred Lands Search was conducted at the Native American Heritage Commission (NAHC). Concurrent with that search, Native Americans and Native American groups cited by the NAHC were contacted. There was one responses to the letters written, noted specifically in Exhibit B.




Figure 1: Vicinity Map (No Scale)




Figure 2: Portion of USGS 7.5' Quadrangle-Templeton, CA




Figure 3: Assessor's Parcel Map-Parcel Shown In Red Outline

#### **ENVIRONMENTAL CONTEXT**

The project area consists of a ± 7 acre property at the southern corporate limit of of the City of El Paso de Robles, California, west of Highway 101 (Figure 1). Paso Robles lies on a terrace above the western bank of the Salinas River that grades into the hilly flanks of the Santa Lucia Range.

#### Climate

The weather pattern is characterized by hot, dry summers and cool, moist winters. Every several years, extreme frosts occur during winter months, but generally the area experiences 300 to 325 frost-free days per year. Such a setting is eminently suitable for human habitation.

#### Geology and Pedology

The Paso Robles area presents a complex geologic picture, underlain by the 4.3 million year old Paso Robles Formation. Sandstones, siltstone, diatomite and conglomerates are characteristic rocks. Beds of fossil pecten and oyster shells from the 5-7 million year old Santa Margarita Formation are also present in some locations (Chipping 1987:VIII-7). The grey-brown soil of the project area is Lockwood shaly loam (Lindsey 1983: 45), deep well-drained soils that formed in material weathered from sedimentary rocks.

#### **Water Sources**

Annual rainfall ranges from 12 to 20 inches. Today, the Salinas River, a half-mile to the east, flows at the surface only during seasons of heavy rainfall, but the river flow was more abundant and regular during the time of prehistoric human occupation of the area. The surface flow has been reduced to a minimum in recent years by the many municipal and private wells which draw water from the river for residential and agricultural use, as well as the construction of the Santa Margarita Dam in the early 1940s. There are natural springs in the area, both warm sulphur springs and fresh water (Chapman *et al.* 1980: 15).

#### Vegetation

The regional vegetation is melange of oak savanna, oak woodland and chaparral plant communities with a riparian component. Commonly occurring species are: Valley

oak (*Quercus lobata*), interior live oak (*Quercus wizlizenii*), chamise (*Adenostoma fasciculatum*), California lilac (*Ceanothus spp.*) and coyote brush (*Baccharis pilularis*). Along the creeks is a riparian community where western sycamore (*Platanus racemosa*), willow (*Salix sp.*), cottonwood (*Populus fremontii*), White alder (*Alnus Rhombifolia*), Poison oak (*Toxicodendron diversilobum*), Blackberry (*Rubus ursinus*), Poison hemlock (*Conium maculatum*), and elderberry (*Sambucus mexicana*) are common. On the project property, vegetation now consists primarily of a few specimens of valley oak, California poppies and a variety of weedy forbs and grasses.

#### **Fauna**

Fauna commonly occurring in the surrounding area include black-tailed deer (*Odocoileus hemionus columbianus*), coyote (*Canis latrans*), black-tailed jackrabbit (*Lepus californicus*), cottontail rabbit (*Sylvilagus* spp.), black bear (*Ursus americanus*) and historically, grizzly bear (*Ursus horribilis*) and tule elk (*Cervus elaphus nannoides*). A number of ground squirrels (*Spermophilus* spp.), the western gray squirrel (*Sciurus griseus*), gophers (*Thomomys* spp.), mice (*Microtus* spp. and *Peromyscus* spp.), and a variety of reptiles and amphibians are also present.

Common birds in the area include red-tailed hawk (*Buteo jamaicensis*), California scrub jay (*Aphelocoma coerulescens*), mourning dove (*Zenaida macroura*), western meadowlark (*Sturnella neglecta*), mockingbird (*Mimus polyglottos*) and turkey vulture (*Cathartes aura*), acorn woodpecker (*Melanerpes formicuvorus*), and valley quail (*Lophortyx californicus*).

#### **CULTURAL BACKGROUND**

## **Archaeological Background**

Archaeological evidence indicates that the San Luis Obispo County region was occupied as early as 8000-9000 years ago, as indicated by radiocarbon dates from excavations at Diablo Canyon (Greenwood 1972), Edna Valley (Fitzgerald 2000), Cambria (Gibson 1979) and Paso Robles (Stevens *et al.* 2004). The cultural history of this region has until recently been placed within the sequence that has been defined for the Santa Barbara region, where far more archaeological investigations had taken place. The first regional chronology was proposed by D.B. Rogers (1929) and was based on his

excavation of coastal sites around Santa Barbara. This three-part sequence of Early Oak Grove or Millingstone Culture, Intermediate or Hunting People and a late Canaliño Culture is still considered generally valid in terms of broad cultural patterns (Fitzgerald and Jones 1998).

Researchers on the Central Coast have continued to refine the chronological framework and several alternative schemes have been proposed, primarily based on sites in the Central Valley, Central Coast and Channel Islands (*cf.* Moratto 1984: 125; King 1990; Erlandson and Jones, 2002; Jones *et al.* 2007). The following chronology for the San Luis Obispo area builds on this work and incorporates extensive investigations carried out on the Pecho Coast, south of San Luis Obispo (Jones and Codding 2019). All dates are radiocarbon calibrated dates:

Paleoindian	10,000 BCE - 8350 BCE
Millingstone/Lower Archaic	8350 BCE - 3500 BCE
Early	3500 BCE - 600 BCE
Middle	600 BCE - 1000 CE
Middle/Late Transition	1000 CE- 1230 CE
Late	1230 CE - 1769 CE
Mission Period	1769 CE - 1830 CE

These periods are based upon shifts in technology that relate to the type and variety of foods consumed, methods of procurement, and social structure. The earliest periods were a time of hunting and gathering, with an emphasis on seed collecting and processing. The tool kit for these periods shows an emphasis on milling equipment and crude cores yielding flaked stone tools. An increased reliance on fishing (evidenced by fishhooks), and on acorns as a dietary staple (mortars and pestles), was indicated later by the addition of new tools.

## Paleoindian (10,000 BCE - 8350 BCE)

Excavations on the northern Channel Islands have yielded radiocarbon dates as early as 12,500 years ago (Erlandson and Braje 2011). There is still very limited information for the Paleoindian period in the Central Coast mainland region. *Millingstone Period* (8350 BC–3500 BC)

More substantive archaeological evidence exists for the Millingstone Period, as evidenced by radiocarbon dates from excavations conducted at Diablo Canyon (Greenwood 1972), Cambria (Gibson 1979) Edna Valley (Fitzgerald *et. al* 1998) and Paso Robles (Stevens *et.al* 2004). It was during this period that permanent settlements with associated cemeteries were established. This basic adaptation persisted until about 3500 BC and was characterized by milling slabs, manos (handstones), rather crude cobble tools and a high density of marine shellfish remains on the coast. Collection of seeds appears to have been important for diet.

## Early Period (3500 BCE - 600 BCE)

Along the coast and in interior areas, the Early period is marked by the appearance of mortars and pestles and contracting-stemmed projectile points (Jones 1993). Other artifacts found with Early period occupations are also found in Millingstone period sites, including Olivella (*Callianax biplicata*) class L beads, large side-notched projectile points, and milling slabs and handstones. Large projectile points and stone knives are indicative of hunting activity. Milling implements consisting of manos and metates were evidence of the processing of seeds, and possibly vegetable foods, dried meats, and fish. Greater numbers of sites are known from the Early period, possibly signaling a population increase. The end of this period is marked by changes in technology with the decrease of manos and metates, a shift in the settlement pattern, and alterations in ornamental style.

## Middle Period (600 BCE - 1000 CE)

Mortars and pestles become larger and more common during this period and small seeds become less important as a staple. Exotic products are adopted. This period heralds the advent of social and political alliances and economic networks to regulate food supplies and their distribution in order to alleviate conditions resulting from regional fluctuations in the harvest. Some villages grew larger and less defensive in nature as populations were integrated into larger political units. The end of this period is marked by dramatic changes in economic, social, and political conditions, evidenced by new habitation sites and larger coastal fishing communities.

The Middle period is well represented at recorded sites along the central coast and increasingly in interior regions as well. The types of artifacts found in Middle period occupations are similar to those from the Early period although a larger number

of bone implements and bead types are known and projectile points tend to be contracting-stemmed types instead of side-notched and square-stemmed (Olsen and Payen 1969; Bennyhoff and Hughes 1987; Jones and Waugh 1995). Excavations at Fort Hunter-Liggett have shown that Middle period occupations in that area resemble those found along the coast (Jones and Haney 1997).

## Middle/Late Transition Period (1000 CE - 1230 CE)

Around 1,000 AD a 300-year period of warmer temperatures and drier climate, the Medieval Climatic Anomaly, caused adverse environmental conditions, particularly intermittent droughts (Raab and Larson 1997). During the Late Period, terrestrial resource production is thought to have decreased significantly, while adaptive responses involving technology and social complexity evolved. Characteristic artifacts include curved shell fishhooks, mortars with attached basket hopper, contracting-stemmed and double side-notched projectile points. The bow and arrow was introduced.

## Late Period (1230 CE - 1769 CE)

This period is marked by a more mobile, dispersed settlement pattern than earlier periods (Jones *et al.* 2015: 15), an increasing dependence on acorns and other storable commodities, and a general diversification of the marine and terrestrial foods consumed. Late period assemblages from the interior south coast ranges are distinguished by a suite of new bead types, small side-notched and triangular arrow points, and hopper mortars as well as many artifact types found in earlier periods (Olsen and Payen 1969). At Fort Hunter Liggett, Late period occupations also included small arrow points, new bead types, as well as bedrock mortars and unshaped pestles (Jones 2000; Haney *et al.* 2002). The Late period assemblages from a wide area of the central coast and interior regions appear superficially similar, but this was probably a time of continued cultural differentiation due to higher population densities.

## Mission Period (1769 CE - 1830 CE)

Glass trade beads, square nails and bottle glass begin to appear in the archaeological matrix (Meighan 1979; Moratto 1984: 273).

## **Ethnographic Overview**

At the time of European contact, the Paso Robles region was primarily occupied by a branch of the northern-most Chumash, the Obispeño (Kroeber 1925). This group inhabited coastal and inland areas between Malibu and the vicinity of San Simeon (Kroeber 1925; Gibson 1983). Also present in the region historically were the Migueleño Salinan (Greenwood 1978). The Salinan were bordered by the Esselen and Costanoan to the north, Yokuts to the east and the Chumash to the south. Examination of mission records reveals that members of the Salinan Nation inter-married into the northern portion of San Luis Obispo County, including the Paso Robles area. The exact boundary of these two groups has not been well established and is the subject of continuing research on the part of ethno-historians, archaeologists, and some Salinan and Chumash descendants.

The economies of the Salinan and the Chumash, as observed at the time of European contact, were based upon an annual cycle of gathering and hunting (Geiger and Meighan 1976). Vegetal foods, especially acorns, provided the bulk of the diet. Acorns were stored in large willow-twig granaries until needed, then ground in a stone mortar. The tannic acid present in the acorn meal was leached out with water, and the result was cooked into a gruel. Other important plant foods included wild grass and other hard seeds, roots and corms, and various fruits and berries. Major animal foods included an assortment of terrestrial mammals, marine and freshwater fish, shellfish, birds, as well as reptiles and insects. It is unclear to what extent people living inland ventured to the coast and vice versa, but it is likely that people were mobile enough to take advantage of plant and animal foods when and where they occurred. Diets would have varied from season to season, and from year to year, depending on what was available and accessible.

Stone, bone, wood, plant fibers and shell all provided materials for the production of tools. Hunting of animals and birds was accomplished with snares, traps, spears, darts, and the during the Late Period, bow and arrow. Stone work included projectile points, knives, scrapers, choppers and awls. Pecked and ground stone objects included bowl mortars, pestles, metates, basket mortars, stone bowls, notched pebble net sinkers, and steatite arrow shaft straighteners. Ornaments were made of steatite and serpentine. Bone and shell tools were also manufactured; especially bone awls and C-

shaped fishhooks. Shell beads of mussel and abalone were the basis of the Salinan "currency", with value being assigned based on the color or the shell (Hester 1978: 502).

## **Historic Overview**

European contact in the San Luis Obispo County region may have begun as early as 1587 with the visit of Pedro de Unamuno to Morro Bay, although some scholars have questioned this based on the ambiguity of Unamuno's descriptions (Mathes 1968). A visit in 1595 by Sebastian Rodriguez Cermeño is better documented (Wagner 1924). The earliest well-documented descriptions come from accounts by members of Gaspar de Portola's land expedition, which passed through the region in 1769 (Squibb 1984). No large villages, such as those seen along the Santa Barbara channel, were reported by early travelers in the San Luis Obispo region.

Permanent Spanish settlement of the region began with the founding of Mission San Antonia de Padua (near King City) in 1771 and San Luis Obispo de Tolosa (in San Luis Obispo) in 1772. Twenty-five years later, Mission San Miguel Archangel was founded in the heart of southern Salinan territory. The mission properties of San Miguel mission were extensive and included an outlying rancho station, Las Gallinas, near present day Paso Robles (Ohles 1997).

As elsewhere, induction into the mission system had a devastating effect on the local inhabitants, requiring them to live and work at the mission and to a great extent abandon their former lifeways. The inadvertent introduction of European diseases, the consequent high mortality rate, and the pressure of overwhelming social change decimated the population. By 1805, most native villages had been abandoned, and the populace had either fled or moved into the mission system (Gibson 1983). The natives who had survived the Spanish colonization period, went on to build and staff the rancheros of the Mexican and American periods which followed. By the beginning of the 20<sup>th</sup> Century, the Chumash and Salinan had been integrated into American society (Gibson 1983; King 1984, 1990).

In 1822, Mexico attained independence of Spain and California became a Mexican territory. The Secularization Act, passed by the Mexican congress in 1833, provided for the immediate break-up of the missions and the transfer of mission lands to settlers and Indians. Work toward this end began in 1834 under Governor Figueroa.

Grants were made to individuals by the governor on the recommendation of the local *alcalde* of the Mission (Shumway 2007). During the years from 1840 to 1846, a series of land grants were made from the lands of Mission San Miguel by the governors of Mexican California. Most of these were used for grazing huge cattle herds. Even after the acquisition of California by the United States the ranchos continued to thrive until the drought of 1863 - 1864. This drought was ruinous to many of the ranchos. Tens of thousands of acres changes hands as lands sold for less than their assessed value (Angel 1883; Morrison & Haydon 1917). The new owners were most often North Americans who arrived on the heels of the drought as land prices plummeted.

The project area was a portion of the 26,000 acre rancho El Paso de los Robles, granted May 12, 1844 to Pedro Navarez by Mexican Governor Manuel Micheltorena. In 1848 the Treaty of Guadalupe Hidalgo marked an end to the Mexican American war and California became a territory of the United States. Statehood was attained in 1850 and in 1851 the Land Act, passed by Congress, meant that the rancheros now had to prove ownership of their land. A patent on the El Paso de los Robles was obtained July 20, 1866 by Petronillo Rios. Prior to the patent, however, the parcel had been sold in two separate transactions, first to Daniel and James Blackburn on September 21, 1858. The second portion was sold July 9, 1861 to Lazarus Godchaux. They immediately began making improvements to the hot sulphur springs which had been used by local inhabitants for generations. The location had long been a rest stop for travelers on the El Camino Real. In 1864 the El Paso de Robles Hotel with attendant mineral hot spring bathhouse, was built. By the 1870s, the Paso Robles Hot Springs was a well known destination for people seeking the famous curative powers of the springs (Sawyer 1915).

The West Coast Land Co. was incorporated on March 27, 1886. The immediate objective was to develop 64,000 acres of land, comprised of the ranchos Santa Ysabel, El Paso de Robles, Eureka, and the unsold portion of Huer Huero that had been purchase over the preceding decade. The purchases were based upon the expectation that the Southern Pacific Railroad coastal line between San Francisco and Los Angeles through San Luis Obispo County would bring prosperity to the region (Nicholson 1980). A town plan for Paso Robles, on the western side of the Salinas River, was commissioned, and on November 17, 1886, two weeks after the first train arrived in "town" a Grand Auction was held, resulting in the sale of 228 lots. The town plan was completed by 1887 and the town was incorporated as a city in 1889. The trickle of settlers became a

flood and Paso Robles became a major export center for cattle, grain, dairy products, stone fruit, walnuts, and almonds. Throughout the later part of the nineteenth and the twentieth century, the economy of the Paso Robles region was largely agricultural. Cattle ranches, dairies, almond and other fruit orchards, and large tracts devoted to dry land grain production comprised the rural landscape. This resulted in the clearing of much of the Oak woodland, including the present project area (Rossi 1979: 258). During the mid twentieth century, Paso Robles was known as "The Almond Capital of the World." Much of the region around Paso Robles

In 1882, York Mountain Vineyard opened, eventually becoming one of the first bonded wineries on the Central Coast. Agriculture has continued to be the mainstay of the region up to the present, with increasing emphasis on viticulture and wine-making. The proliferation of wineries in the last 30 years has also lead to tourism once again becoming a major component of the local economy.

## MAP AND RECORDS SEARCH RESULTS

Prior to the field survey, a records and literature search was conducted at the Central Coast Information Center, Museum of Natural History, Santa Barbara, which is the regional clearinghouse for archaeological site information for San Luis Obispo County under agreement with the California Office of Historic Preservation (OHP). The search also included inventories for the State Historic Property Data Files, National Register of Historic Places, National Register of Determined Eligible Properties, California Historical Landmarks, California Points of Historic Interest, California OHP Archaeological Determinations of Eligibility, and the CalTrans State and Local Bridge Surveys.

Seven cultural resource studies have been conducted within a 1/4 mile radius of the project area (Bonner 2004; Clift and Farrell 2001; Farrell 1998; Gibson 1973; Girado and Orfila 2008; Singer 2004, 2006). No prehistoric archaeological sites or historic properties have been identified within the same radius.

## SUMMARY OF NATIVE AMERICAN OUTREACH

A letter was sent on March 6, 2022, to the Project Analyst at the Native American Heritage Commission. The letter explained the proposed project and asked him to conduct a Sacred Lands Search and forward to CRMS any names and addresses of those who may have knowledge of cultural resources within the study area, or who would like to comment on the project.

On April 24, 2022 a letter dated the same day, was received from Cody Campagne, Project Analyst, indicating that the Sacred Lands Search conducted at the Native American Heritage Commission (NAHC) yielded no evidence of Sacred Lands with the project. A list of interested Native American individuals and groups was included. Letters, explaining the project and soliciting comments were sent to each of the Native Americans and groups listed (Exhibit B). On Aril 25, 2022, letters were written to the Native Americans and groups listed by the NAHC explaining the project, and asking for their comments.

#### RESULTS OF FIELD INVESTIGATION

A field reconnaissance of the project area was made on April 20, 2022 by Nancy Farrell and Ron Rose of CRMS. The entire surface was inspected by walking parallel transects at two meter intervals. Mineral soil visibility was variable but generally good (50%). Additionally, the abundant ground burrow spoil piles provided additional visibility No evidence of prehistoric or historic artifacts, features, or other indications of significant cultural resources were found during the survey. (Figure 4, 5, 6, 7, and 8). There was evidence of a previous water hookup and a telephone pole, no evidence of a building structure was found. An examination of aerial photos from the 1970s yielded no additional information. There was a sewer manhole. A check with the City Wastewater Treatment Department showed no sewer hookup in that location. Further examination with the cover removed showed that the manhole was never developed, but abandoned. Apparently a previous property owner had some plans for future development. Also on the property is a fenced detention basin approximately 80 feet square. This detention may be used for the present development or abandoned.




Figure 4: Portion of Templeton USGS Quadrangle. Red Dot Is Location of Abandoned Manhole. Black Polygon Is Location of Existing Detention Basin. 1979 Quadrangle Shows A Structure of Some Kind Indicated In Black Next To Abandoned Manhole.



**Figure 5: Overview of Subject Parcel-View To East** 



Figure 6: Overview of Subject Parcel-View Northeast



Figure 7: Overview of Subject Parcel-View To South



Figure 8: Overview of Subject Property-View To West

## **CONCLUSION AND RECOMMENDATIONS**

Since no evidence of significant cultural resources was located on the subject property, no further archaeological investigations are recommended at this time. While it is unlikely that subsurface remains are present, the nature of surface survey does not preclude the possible existence of such remains. If prehistoric or historic cultural materials are encountered during any phase of property grading or development the work should be halted until a qualified archaeologist can make an assessment of the resources and proper mitigation measures be formulated, if necessary.

## REFERENCES CITED

Angel, Myron

1883 *History of San Luis Obispo County, California*. Thompson & West, Oakland. Facsimile Reproduction, Valley Publishers, Fresno. 1979.

Bennyhoff, J. A., and R. E. Hughes

1987 Shell Beads and Ornament Exchange Networks Between California and the Western Great Basin. *American Museum of Natural History Anthropological Papers* 64 (2).

Bonner, W.

2004 Cultural Resource Records Search and Site Visit for Cingulat Telecommunications Facility Candidate VY-553-01 (Hwy 101 and 46). Michael Brandman Associates

Brown, A. K.

1967 The Aboriginal Population of the Santa Barbara Channel. *University of California Archaeological Survey Reports* 69: 1-99. Berkeley.

Chapman, Rodger, Gordon W. Chase, and Les G. Youngs

1980 Geophysical Survey, Paso Robles Geothermal Area, California Part of the Resource Assessment of Low-and Moderate-Temperature Geothermal Resource Areas in California. Submitted to U.S. Department of Energy, Division of Geothermal Energy. California Department of Conservation, Division of Mines and Conservation.

Chipping, David

1987 The Geology of San Luis Obispo County: A Brief Description and Field Guide.

Clift, Gregory and Nancy Farrell

2001 Phase 1 Archaeological Inventory for the Graff Groundwater well site near Ramada Drive, Templeton, San Luis Obispo county, California. Cultural Resource Management Services.

Dart, Louisiana Clayton

1978 *Vignettes of History in San Luis Obispo County.* Mission Federal Savings. San Luis Obispo, California.

Erlandson, Jon and Todd Braje

From Asia to the Americas by Boat? Paleogeography, paleoecology, and stemmed points of the Northwest Pacific. *Quaternary International* 239: 28-37.

Erlandson Jon M. and Terry L. Jones, editors

2002 Catalysts to Complexity, Late Holocene Societies of the California Coast. Perspectives in California Archaeology, Volume 6. Cotsen Institute of Archaeology, UCLA.

Farrell, Nancy

1998 Phase 1 Cultural Resources Survey of the Boatman Property (APN 009-851-007 & 009) Paso Robles, California. Cultural Resources Management Services

## Fitzgerald, Richard T.

2000 Cross Creek: An Early Holocene/Millingstone Site. *California State Water Project, Coastal Branch Series Paper No.* 12. San Luis Obispo County Archaeological Society.

## Fitzgerald, Richard T. and Terry L. Jones

Interpretive Synthesis of Subsurface Archaeological Investigations for the Coastal Branch Phase II Project. Appendix G in Archaeological Data Recovery at CA-SLO-1797, the Cross Creek Site, San Luis Obispo County, California, Coastal Branch, Phase II Project. Submitted to California Department of Water Resources. Garcia and Associates, San Anselmo.

## Geiger, M. and Clement Meighan

1976 As the Padres Saw Them: California Indian Life and Customs as Reported by the Franciscan Missionaries, 1813 -1815. Santa Barbara Mission Archive Library. Santa Barbara.

## Gibson, Robert O.

- 1973 Archaeological Element of Environmental Impact Report for the Proposed Development of the Durand Property, San Luis Obispo County, California.
- 1979 Preliminary Inventory and Assessment of Indian Cultural Resources at Lodge Hill, Cambria, San Luis Obispo County, California. On file at the Central Coastal Information Center.
- 1981 Archaeological Element of Environmental Impact Report for the Holsted Subdivision, Parcel Map CO-80-24 Paso Robles, CA.
- 1983 Ethnogeography of the Salinan People: A Systems Approach. Master's Thesis, California State University, Hayward.
- 1990 Results of Phase One Archaeological Surface Survey on Tract 1865, Paso Robles.

## Girado, Amy and Rebecca Orfila

2008 Archaeological and Historical Investigations of the CAL FIRE Paso Robles Fire Station, San Luis Obispo, California. Center for Archeological Research.

#### Greenwood, Roberta S.

- 1972 9000 Years of Prehistory at Diablo Canyon, San Luis Obispo County, California. San Luis Obispo County Archaeological Society Occasional Paper 2, San Luis Obispo.
- 1978 Obispeño and Purismeño Chumash. In *Handbook of North American Indians, Vol. 8, California*. Smithsonian Institution, Washington, DC.

## Haney, Jefferson W, Terry L. Jones, and Jennifer M. Farquar

2002 Phase II Archaeological Investigation of CA-MNT-879 Fort Hunter Liggett, Monterey County, California. Report submitted to U.S. Army Corps of Engineers, Sacramento District.

#### Hester, Thomas Roy

1978 Salinan. In *Handbook of North American Indians*, Vol. 8, California. Smithsonian Institution, Washington DC.

Jones, Deborah, Terry Jones, Kacey Hadick, William Hildebrandt & Patricia Mikkelsen
2015 Archaeological Investigations for the Los Osos Wastewater Project, San Luis Obispo
County, California.

Jones, Terry L.

1993 Big Sur: A Keystone in Central California Cultural History. *Pacific Coast Archaeological Society Quarterly* 29(1):1-78.

2000 Archaeological Evaluations at CA-MNT-237 and CA-MNT-519, Fort Hunter- Liggett, Monterey County, California. Report submitted to U.S. Army Corps of Engineers, Sacramento District.

Jones Terry L. and Brian Codding

2019 Foragers on America's Western Edge, The Archaeology of California's Pecho Coast. The University of Utah Press, Salt Lake City.

Jones, Terry L., and Jefferson W. Haney

1997 Archaeological Evaluation of CA-MNT-521, Fort Hunter Liggett, Monterey County, California. Report submitted to U.S. Army Corps of Engineers, Sacramento District.

Jones, Terry, Nathan Stevens, Debbie Jones, Richard Fitzgerald, and Mark Hylkema.

The Central Coast: A Midlatitude Milieu. In *California Prehistory: Colonization, Culture, and Complexity*, edited by Terry Jones and Kathryn Klar. AltaMira Press in cooperation with the Society for California Archaeology, Plymouth, United Kingdom.

Jones, Terry L. and Georgie Waugh

1995 *Central California Prehistory: A View from Little Pico Creek. Perspectives in California Archaeology, Vol.* 3. Institute of Archaeology, University of California, Los Angeles.

Jones, Terry, Nathan Stevens, Deborah A. Jones, Richard T. Fitzgerald and Mark Hylkema 2007 The Central Coast: A Midlatitude Milieu, in *California Prehistory, Colonization, Culture* and Complexity, edited by Terry L. Jones and Kathryn A. Klar, pp 125-146. Altamira Press, Lanhma, MD.

Jones, Terry L. and Georgie Waugh

1995 Central California Prehistory: A View from Little Pico Creek. *Perspectives in California Archaeology, Vol.* 3. Institute of Archaeology, University of California, Los Angeles.

King, Chester

Appendix I: Ethnohistoric Background. In *Archaeological Investigations on the San Antonio Terrace, Vandenberg Air Force Base, California*. Report on file at Central Coastal Information Center, University of California, Santa Barbara.

1990 The Evolution of Chumash Society: A Comparative Study of Artifacts Used in Social System maintenance in the Santa Barbara Channel Region Before A.D. 1804. Garland Publishing, New York.

Krieger, Daniel E.

1988 San Luis Obispo County. Windsor Publications Inc., Northridge, California.

Kroeber, Alfred

1925 Handbook of the Indians of California. Facsimile edition, California Book Company, 1953.

Lindsey, Wesley C.

1983 Soil Survey of San Luis Obispo County, California. Paso Robles Area. United States Department of Agriculture.

Mathes, W. M.

1968 *Sebastián Vizcaino and Spanish Expansion in the Pacific Ocean, 1580-1630.* California Historical Society, San Francisco.

Meighan, Clement

1979 Glass Trade Beads in California. Ms. on file at Lowie Museum of Anthropology. University of California, Berkeley.

Moratto, Michael

1984 California Archaeology. Academic Press, Inc. New York.

Morrison, Annie L and John H. Haydon

1917 History of San Luis Obispo County and Environs, California. Historic Record Company, Los Angeles.

Nicholson, Loren

1980 Rails Across the Ranchos. Valley Publishers. Fresno, California.

Ohles, Wallace V.

1997 The Lands of Mission San Miguel. Lord Dancer Press, Clovis California.

Olsen, W. H., and L. A. Payen

1969 Archaeology of the Grayson Site. *California Department of Parks and Recreation Archaeological Report No.* 12. Sacramento.

Rabb, L. Mark, and Daniel O. Larson

1997 Medieval Climatic Anomaly and Punctuated Cultural Evolution in Coastal Southern California. *American Antiquity* 62: 319-336.

Rogers, David B.

1929 *Prehistoric Man of the Santa Barbara Coast, California*. Santa Barbara Museum of Natural History Special Publication 1, Santa Barbara.

Rossi, Randall Steven

1979 Land Use and Vegetation Change in the Oak Woodland-Savanna of Northern San Luis Obispo County, California (174-1978). PhD Dissertation, University of California, Berkeley.

Sawyer, Frank W.

1915 Paso Robles Hot Springs California. Sunset Publishing House, San Francisco.

Shumway, Burgess McK.

2007 *California Ranchos, Patented Private Land Grants Listed by County.* 2<sup>nd</sup> Edition, edited by Michael Burgess and Mary Wickizer Burgess. The Borgo Press.

Singer, Clay A.

2004 Cultural Resources Survey and Impact Assessment for a 40 +/- Acre Property Located on Theater Drive in the City of Paso Robles, San Luis Obispo County, California. C.A. Singer & Associates, Inc.

2006 Cultural resources survey and impact assessment for a 5 acre property on Ramada Drive near the Town of Templeton in San Luis Obispo [APN 040-151-013]. C.A. Singer & Associates, Inc.

Stevens, Nathan, Richard T. Fitzgerald, Nancy Farrell, Mark A. Giambastiani, Jennifer M. Farquar, and Dayna Tinsley

2004 Archaeological Test Excavations at Santa Ysabel Ranch, Paso Robles, San Luis Obispo County, California. Report submitted to Weyrich Development Company, LLC. Cultural Resource Management Services, Paso Robles.

## Squibb, Paul

1984 Captain Portola in San Luis Obispo County in 1769. Tabula Rasa Press. Morro Bay, California.

## Wagner, H.R.

1924 The Voyage to California of Sebastian Rodriguez Cermeño in 1595. *California Historical Society Quarterly* 3 (1): 3-24.

## **EXHIBIT A**

Records and Literature Search Central Coast Information Center Museum of Natural History Santa Barbara. CA

# California Historical Resource Information System

## Central Coast Information Center

Santa Barbara Museum of Natural History

2559 Puesta del Sol Santa Barbara, CA 93105

PHONE (805) 682-4711 ext. 181

FAX (805) 682-3170 EMAIL ccic@sbnature2.org

# **Attachment 9**

2	n	13	v	-	ø	w	'n	9
· 3		,	r	5	ι	ъ.	r	s

Records Search # 22-066

Nancy Farrell Cultural Resource Management Services 829 Paso Robles St. Paso Robles, CA 93446

Re: Coast Counties Peterbilt

The Central Coast Information Center received your record search request for the project area referenced above, located on the Templeton USGS 7.5" quad(s). The following reflects the results of the records search for the project area and a one quarter mile radius:

As indicated on the data request form, the locations of reports and resources are provided in the following format: ■ custom GIS maps □ shapefiles □ hand-drawn maps □ none

Resources within project area:	0.
Resources within 1/4 mile radius;	0
Reports within project area:	2; SL-00022, SL-05188
Reports within % mile radius:	5; SL-03641, SL-04555, SL-05757, SL-05808, SL-06130

Resource Database Printout (list):	□ enclosed	☐ not requested	nothing listed
Resource Database Printout (details):	□ enclosed	□ not requested	nothing listed
Resource Digital Database Records:	☐ enclosed	not requested	☐ nothing listed
Report Database Printout (list):	enclosed	☐ not requested	☐ nothing listed
Report Database Printout (details):	☐ enclosed	■ not requested	nothing listed
Report Digital Database Records:	□ enclosed	■ not requested	☐ nothing listed
Resource Record Copies:	enclosed	□ not requested	nothing listed
Report Copies:	□ enclosed	■ not requested	□ nothing listed
OHP Historic Properties Directory:	□ enclosed	not requested	nothing listed
Archaeological Determinations of Eligibility:	□ enclosed	☐ not requested	■ nothing listed

The following sources of information are available at <a href="http://ohp.parks.ca.gov/?page\_id=28065">http://ohp.parks.ca.gov/?page\_id=28065</a>. Some of these resources used to be available through the CHRIS but because they are now online, they can be accessed directly. The Office of Historic Preservation makes no guarantees about the availability, completeness, or accuracy of the information provided through the sources listed below.

California State Lands Commission Shipwreck Database	Caltrans Historic Bridge Inventory
U.S. Geological Survey Historic Topographic Maps	Rancho Plat Maps
National Park Service National Register of Historic Places Nominations	Natural Resource Conservation Service Soil Survey Maps
US Bureau of Land Management General Land Office Records	California Historical Landmerks Listing (by county)
Five Views: An Ethnic Historic Site Survey for California (1988)	Historical Soil Survey Maps

Please forward a copy of any resulting reports from this project to the office as soon as possible. Due to the sensitive nature of archaeological site location data, we ask that you do not include resource location maps and resource location descriptions in your report if the report is for public distribution. If you have any questions regarding the results presented herein, please contact the office at the phone number listed above.

The provision of California Historical Resources Information System (CHRIS) data via this records search response does not in any way constitute public disclosure of records otherwise exempt from disclosure under the California Public Records Act or any other law, including, but not limited to, records related to archeological site information maintained by or on behalf of, or in the possession of, the State of California, Department of Parks and Recreation, State Historic Preservation Officer, Office of Historic Preservation, or the State Historical Resources Commission.

Due to processing delays and other factors, not all of the historical resource reports and resource records that have been submitted to the Office of Historic Preservation are available via this records search. Additional information may be available through the federal, state, and local agencies that produced or paid for historical resource management work in the search area. Additionally, Native American tribes have historical resource information not in the CHRIS Inventory, and you should contact the California Native American Heritage Commission for information on local/regional tribal contacts.

Should you require any additional information for the above referenced project, reference the record search number listed above when making inquiries. Requests made after initial invoicing will result in the preparation of a separate invoice.

Thank you for using the CHRIS.

Sincerely.

Brian Barbier Coordinator

## **EXHIBIT B**

Letter to NAHC Response From NAHC Letter To Native Americans and Groups Response From Native Americans and Groups



# Cultural Resource Management Services

Paso Robles, CA 93446 Phone 805-237-3838

March 16, 2022

Mr. Steven Quinn Associate Governmental Program Analyst California Native American Heritage Commission 1550 Harbor Blvd., Suite 100 West Sacramento, CA 95691

RE: Phase I Inventory Survey, Commercial Building

2805 Theatre Drive, Paso Robles, CA, APN: 009-851-022

Dear Mr. Quinn:

The owners of the property described above intends to construct a new commercial building on the identified parcel.

Cultural Resource Management Services (CRMS) has been retained, to prepare a Phase I surface survey as well as provide an early participation notice to interested Native Americans and Native American groups relative to the proposed construction project.

Please review the sacred lands files for any Native American Sacred resources or sites that may be within or adjacent to the area of potential effect (APE). Please verify that any sacred sites in the vicinity are not in the APE. The project area is within the corporate limits of the city of Paso Robles, San Luis Obispo county, and is identified on the attached portion of the USGS Templeton 7.5' Quadrangle. The study area falls within,, Township 27 South and Range 12 East MDM. The project location is depicted as a salmon colored polygon. As the area was part of a Rancho, there are no section lines.

Page Two March 16, 2022 Steven Quinn


Also provide a list, including names and addresses, of Native American individuals and organizations who may have knowledge of cultural resources in the project area; or who may have a concern or wish to comment on the project.

If you have any questions contact me at the phone number or address shown, or by email <a href="mailto:ronrose@crms.com">ronrose@crms.com</a>. We look forward to your reply.

Best regards,

Ron Rose Vice President

Encl: Portion of USGS 7.5' Quadrangle, Templeton, CA



Portion of USGS 7.5' Quadrangle, Templeton, CA





## NATIVE AMERICAN HERITAGE COMMISSION

April 24, 2022

Ron Rose

Cultural Resource Management Services

Cara Miranda Laura Miranda

Via Email to: ronrose@crms.com

VCSCHARGESH Reginald Pagaling Charach Re: Phase I Survey, Commercial Building 2805 Theatre Drive, Paso Robles, CA Project, San Luis Obispo County

PARLHOLENTARIAS Bussell Affebery Dear Mr. Rose:

Figure Security

A record search of the Native American Heritage Commission (NAHC) Sacred Lands File (SLF) was completed for the information you have submitted for the above referenced project. The results were negative. However, the absence of specific site information in the SLF does not

Sara Dulschke Mikana results were <u>negative</u>. However, the absence of specific site information in the SLF does not indicate the absence of cultural resources in any project area. Other sources of cultural resources should also be contacted for information regarding known and recorded sites.

Colonisticnisk William Mungary Paleto/White Mountain Aurochia Aftached is a list of Native American tribes who may also have knowledge of cultural resources in the project area. This list should provide a starting place in locating areas of potential adverse impact within the proposed project area. I suggest you contact all of those indicated; if they cannot supply information, they might recommend others with specific knowledge. By contacting all those listed, your organization will be better able to respond to claims of failure to consult with the appropriate tribe. It a response has not been received within two weeks at notification, the Commission requests that you follow-up with a telephone call or small to ensure that the project information has been received.

Countainer
Isaac Bojorquez
Citione-Costonoco

Columbiolife Buffy McQuillen Yokaya Pomo, Youl Nambal

If you receive notification of change of addresses and phone numbers from tribes, please notify me. With your assistance, we can assure that our lists contain current information.

Countries

If you have any questions or need additional information, please contact me at my email address: Cody.Compagne@nahc.co.gov.

Wayne Nelson Luceno

Sincerely,

Communicies Stanley Rockigüez Lucreyady

Cody Campagne

Cultural Resources Analyst

Raymond C. Hitchcock

Attachment

Miwak/Menan

MANC HEADQUARTERS

1330 Harbor Boylevard Seite 100 What Sociamentia. Collomia 93691 [916] 373-3710. pubs Briatic cassay. MARC.ca.gov

Page 1 of 1



## **Cultural Resource Management**

829 Paso Robles Street Paso Robles, CA 93446 Phone 805-237-3838 Fax 805-237-3849

April 25, 2022

RE: Phase I Archaeological Inventory Survey, APN: 009-851-022

2805 Theatre Drive, Paso Robles, CA

## XXXXXXXXXXXX:

The owners of the property described above intend to construct a new commercial building on the property described above.

Cultural Resource Management Services (CRMS) has been retained, to prepare a Phase I surface survey as well as provide an early participation notice to interested Native Americans and Native American groups relative to the proposed construction project.

The project area is within the corporate limits of the city of Paso Robles, San Luis Obispo county, and is identified on the attached portion of the USGS Templeton 7.5' Quadrangle. The study area falls within,, Township 27 South and Range 12 East MDM. The project location is depicted as a salmon colored polygon. As the area was part of a Rancho, there are no section lines.

The Native American Heritage Commission has indicated that no Sacred Sites exist either on the property or in the near vicinity. If you have knowledge of the area, please share that information with me in your comments. If you have any questions contact me at the phone number or address shown, or by email <a href="mailto:ronrose@crms.com">ronrose@crms.com</a>. We look forward to your reply.

Best regards,

Ron Rose Vice President

Encl: Portion of USGS 7.5' Quadrangle, Templeton, CA

Salinan

Chumash

Chumash

Yokut

Yokut

The letter on the previous page was sent to the following individuals and groups. XXXX substituted for address and sale of the substituted for address and sale of the

#### Native American Heritage Commission Native American Contact List San Luis Obispo County 4/24/2022

Chumash

Chumash

Chumash

Chumash

Chumash

Chumash

Barbareno/ Ventureno Band of

Mission Indians

Brenda Guzman. 58 N. Ann Street, #8 Ventura, CA, 93001

Phone: (209) 601 - 4676. brendamguzman@gmail.com

Barbareno/ Ventureno Band of

Mission Indians Annette Ayala

188 S. Santa Rosa Street

Ventura, CA, 93001 Phone: (805) 515 - 9844 annetteayala78@yahoo.com

Barbareno/ Ventureno Band of

Mission Indians

Patrick Tumamait, 992 El Camino Corto Ojal, CA, 93023

Phone: (805) 216 - 1253

Barbareno/Ventureno Band of

Mission Indians

Julie Tumamait-Stenslie, Chairperson 385 North Poli Ave

Ojai, CA, 93023 Phone: (805) 546 - 6214

itumamait@hotmail.com

Chumash Council of

Bakersfield

Julio Quair, Chairperson 729 Texas Street

Bakersfield, CA, 93307 Phone: (661) 322 - 0121

chumashtribe@sbcglobal.net

Northern Chumash Tribal

Council

Violet Walker, Chairperson P.O. Box 6533

Los Osos, CA, 93412 Phone: (760) 549 - 3532

violetsagewalker@gmail.com

Salinan Tribe of Monterey, San Luis Obispo Counties

Patti Dunton, Tribal Administrator

7070 Morro Road, Suite A Atascadero, CA, 93422 Phone: (805) 464 - 2650

info@salmantribe.com

San Luis Obispo County Chumash Council

1030 Ritchie Road

Grover Beach, CA, 93433

Santa Ynez Band of Chumash Indians

Kenneth Kahn, Chairperson

P.O. Box 517

Santa Ynez, CA, 93460 Phone: (805) 688 - 7997

Fax: (805) 686-9578 kkahn@santaynezchumash.org

Tule River Indian Tribe

Joey Garfield, Tribal Archaeologist Yokut

P. O. Box 589 Porterville, CA, 93258

Phone: (559) 783 - 8892 Fax: (559) 783-8932

joey.garfield@tulerivertribe-

nsn.gov

Tule River Indian Tribe

Kern Vera, Environmental

Department P. O. Box 589 Porterville, CA, 93258

Phone: (559) 783 - 8892

Fax: (559) 783-8932 kerri vera@rulerivertribe-nsn.gov

Tule River Indian Tribe

Neil Peyron, Chairperson

P.O. Box 589

Porterville, CA, 93258 Phone: (559) 781 - 4271

Fax: (559) 781-4610

neil peyron@rtulerivertribe-nsn gov

This let is current only as of the date of this document. Distribution of this let does not releave any person of statutery responsibility as defined in Section 7050,5 of the Health and Safety Code. Section 5097,54 of the Public Resource Section 5097,51 of the Public Resource Code.

This list is only applicable for contacting local Notice Americans, with regard to cultival resources assessment for the proposed Phase I Survey, Commercial Earling 2806, Throtte Deve. Pero Relates CA Project, San Les Obeşo County.

#### Native American Heritage Commission Native American Contact List San Luis Obispo County 4/24/2022

#### Xolon-Salinan Tribe

Donna Haro, Tribal Headwoman P, O. Box 7045 Salinan Spreckels, CA, 93962 Phone: (925) 470 - 5019 dhxolonaakletse@gmail.com

#### Xolon-Salinan Tribe

Karen White, Chairperson
P. O. Box 7045
Spreckels, CA, 93962
Phone: (831) 238 - 1488
xolon.salinan.heritage@gmail.com

#### yak tityu tityu yak tilhini -Northern Chumash Tribe

Mona Tucker, Chairperson 660 Camino Del Rey Arroyo Grande, CA, 93420 Phone: (805) 748 - 2121 olivas.mona@gmail.com

Chumash

This list is current only as of the date of this document. Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 5097.94 of the Public Resource Section 5097.98 of the Public Resources Code.

This list is only applicable for confacting focal Native Americans with regard to cultural resources assessment for the proposed Phase I Survey. Commercial Building 2805 Thisatre Drive. Pase Robles, CA Project, San Luis Obispo County.

PROJ-2022-002195 04/24/2022 01:46 PM 2 of 2

## RESPONSE TO LETTER WRITTEN

April 2, 2022 response from Julie Tumamait-Stenslie

Ron

I will defer any comments to Mona Tucker

Thanks

Julie

## **Environmental Noise Assessment**

# Peterbilt Service and Sales Center

Paso Robles, California

BAC Job # 2022-088

Prepared For:

City of Paso Robles

Attn: Katie Banister 1000 Spring Street Paso Robles, CA 93446

Prepared By:

**Bollard Acoustical Consultants, Inc.** 

Dario Gotchet, Principal Consultant

September 15, 2022



## Introduction

The proposed Peterbilt Service and Sales Center (project) is located at 2805 Theatre Drive in Paso Robles, California (APN: 009-851-022). The project proposes the development of a service center for semi-trucks, a retail parts department, and a dealership. The site amenities would include offices for employees, a lounge area for customers, an outdoor display area, and customer parking. The project area with aerial imagery is shown in Figure 1. The project site plan is presented in Figure 2.

Due to the proximity of the proposed project to existing residential uses, Bollard Acoustical Consultants, Inc. (BAC) was retained by the City of Paso Robles to prepare an assessment of potential noise impacts associated with the project. Specifically, the purposes of this assessment are to quantify noise levels associated with proposed on-site operations, to assess state of compliance of those noise levels with applicable City of Paso Robles noise standards, and if necessary, to recommend measures to reduce noise levels to acceptable limits at the nearest existing residential uses.

## Noise Fundamentals and Terminology

Noise is often described as unwanted sound. Sound is defined as any pressure variation in air that the human ear can detect. If the pressure variations occur frequently enough (at least 20 times per second), they can be heard, and thus are called sound. Measuring sound directly in terms of pressure would require a very large and awkward range of numbers. To avoid this, the decibel scale was devised. The decibel scale allows a million-fold increase in pressure to be expressed as 120 dB. Another useful aspect of the decibel scale is that changes in levels (dB) correspond closely to human perception of relative loudness. Appendix A contains definitions of Acoustical Terminology. Figure 3 shows common noise levels associated with various sources.

The perceived loudness of sounds is dependent upon many factors, including sound pressure level and frequency content. However, within the usual range of environmental noise levels, perception of loudness is relatively predictable, and can be approximated by weighing the frequency response of a sound level meter by means of the standardized A-weighing network. There is a strong correlation between A-weighted sound levels (expressed as dBA) and community response to noise. All noise levels reported in this section are in terms of A-weighted levels in decibels.


Community noise is commonly described in terms of the "ambient" noise level, which is defined as the all-encompassing noise level associated with a given noise environment. A common statistical tool to measure the ambient noise level is the average, or equivalent, sound level ( $L_{eq}$ ) over a given time period (usually one hour). The  $L_{eq}$  is the foundation of the Day-Night Average Level noise descriptor (DNL or  $L_{dn}$ ), and shows very good correlation with community response to noise.



Project Border (Approximate)

Residential Parcel Boundaries

△ Long-Term Ambient Noise Survey Location




Peterbilt Service & Sales Center
Paso Robles, California

Project Area


Figure 1







CNG Vehicle Repair Station (Covered Outdoor Bay)



Peterbilt Service & Sales Center
Paso Robles, California

Project Site Plan

Figure 2






Figure 3
Common Noise Levels Associated with Various Sources

The Day-Night Average Level (DNL or L<sub>dn</sub>) is based upon the average noise level over a 24-hour day, with a +10-decibel weighting applied to noise occurring during nighttime (10:00 p.m. to 7:00 a.m.) hours. The nighttime penalty is based upon the assumption that people react to nighttime noise exposures as though they were twice as loud as daytime exposures. Because DNL represents a 24-hour average, it tends to disguise short-term variations in the noise environment. DNL-based noise standards are commonly used to assess noise impacts associated with traffic, railroad, and aircraft noise sources.

## Existing Ambient Noise Environment in the Project Vicinity

The existing ambient noise environment in the immediate project vicinity is defined primarily by traffic on U.S. Highway 101 and Theatre Avenue, and to a lesser extent by nearby commercial operations. To generally quantify the existing ambient noise environment in the immediate project vicinity, BAC conducted long-term (24-hour) noise level measurements on the project site from Monday, June 6, 2022, to Tuesday, June 7, 2022. The noise survey location, identified on Figure 1, was selected to be generally representative of the ambient noise level environment at the nearest residential uses located immediately south of the project site. Photographs of the noise level survey location are provided in Appendix B.

A Larson-Davis Laboratories (LDL) Model LxT precision integrating sound level meter was used to complete the ambient noise level survey. The meter was calibrated immediately before and after use with an LDL Model CAL200 acoustical calibrator to ensure the accuracy off the measurements. The equipment used meets all pertinent specifications of the American National Standards Institute for Type 1 sound level meters (ANSI S1.4). The results of the long-term ambient noise survey are shown numerically and graphically in Appendices C and D (respectively) and are summarized in Table 1.

Table 1
Summary of Long-Term Ambient Noise Measurement Results<sup>1</sup>

		_	Ave	erage Mea	sured Ho	urly Nois	e Levels	(dB)
		DNL	Daytime <sup>3</sup>		Evening <sup>4</sup>		Nighttime <sup>5</sup>	
Site Description <sup>2</sup>	Date	(dB)	Leq	L <sub>max</sub>	$L_{eq}$	L <sub>max</sub>	Leq	L <sub>max</sub>
South end of project parcel near residential uses	6/6/22 – 6/7/22	59	54	64	53	64	52	62

- <sup>1</sup> Detailed summaries of the noise monitoring results are provided in Appendices C and D.
- <sup>2</sup> Long-term ambient noise monitoring location is identified on Figure 1.
- <sup>3</sup> Daytime: 7:00 a.m. to 7:00 p.m.
- <sup>4</sup> Evening: 7:00 p.m. to 10:00 p.m.
- <sup>5</sup> Nighttime: 10:00 p.m. to 7:00 a.m.

Source: Bollard Acoustical Consultants, Inc. 2022.

## Criteria for Acceptable Noise Exposure

## City of Paso Robles Municipal Code

Section 21.60.060 of the City of Paso Robles Municipal Code establishes exterior and interior noise standards that would be applicable to project on-site operations. That code section has been reproduced below.

#### 21.60.060 - Exterior and interior noise standards:

A. The noise standards contained in Table 2 (below), unless otherwise specifically indicated in this chapter, shall apply to all noise-sensitive exterior and interior areas within Paso Robles.

B. It is unlawful for any person at any location within the city to create any noise which causes the noise levels on an affected property, when measured in the designated sensitive exterior or interior location, to exceed the noise standards specified below in Table 2.

Table 2
Exterior Noise Standards for Locally Regulated (Non-Transportation) Noise Sources

		Exterior	· Areas¹	Interior	Spaces <sup>2</sup>
Receiving Land Use	Period <sup>3</sup>	L <sub>eq</sub> <sup>4</sup>	L <sub>max</sub> <sup>5</sup>	$L_{eq}^4$	L <sub>max</sub> <sup>5</sup>
	Day	55	75	45	60
Residential	Evening	50	70	40	55
	Night	45	65	35	45
	Day			45	60
Mixed Use Residential	Evening			40	55
	Night			35	45
Transient Ladeine Heavitales 9 Nursing	Day	60	75	45	60
Transient Lodging Hospitals <sup>6</sup> & Nursing	Evening	55	75	40	55
Homes	Night	50	70	35	45
Hataura Taran Cantan C.D. Assa	Day	60	80	45	60
Uptown Town Center S.P. Area	Evening	55	75	40	55
(UTCSP) Residential	Night	50	70	35	45
	Day	55	75	35	40
Theaters & Auditoriums	Evening	50	70	35	40
	Night			35	40
Chumber Mesting Halls Libraries	Day	55	75	45	55
Churches, Meeting Halls, Libraries	Evening	50	70	40	55
Cabaala <sup>7</sup>	Day			40	55
Schools <sup>7</sup>	Evening			40	55
Office (Due for eight)	Day	60	80	45	60
Office/Professional	Evening	55	75	45	60
0	Day	60	80	50	60
Commercial/Retail Buildings	Evening	55	75	50	60
Discourse de Davids atta	Day	55	75		
Playgrounds, Parks, etc.	Evening	55	75		
Landard Article	Day	60	80	50	60
Industrial	Evening	55	75	50	60

#### Specific Notes:

- 1. Noise sensitive areas are defined acoustic terminology section.
- 2. Interior noise level standards are applied within noise-sensitive areas of the various land uses, as defined in the acoustic terminology section, with windows and doors closed.
- 3. Daytime hours = 7 am 7 pm, Evening hours = 7 pm 10 pm, Nighttime hours = 10 pm 7 am.
- 4. Leq = Average or "Equivalent" noise level during the worst-case hour in which the building is in use.
- 5. Lmax = Highest measured sound level occurring during a given interval of time (Typically 1 hour).
- 6. Hospitals are often noise-generating uses. The exterior noise level standards for hospitals are applicable only at clearly identified areas designated for outdoor relaxation by either hospital staff or patients.
- 7. Exterior areas of school uses are not typically noise-sensitive. As a result, the standards for schools are focused on the interior office and classroom spaces.

#### General Notes Applicable to All Noise Standards and Land Uses:

- a. Where the noise source in question consists of speech or music, or is impulsive in nature, or contains a pure tone, the noise standards of this table are reduced by 5 dB.
- b. Where ambient noise levels exceed the noise level standards shown above, the noise standards shall be increased in 5 dB increments to encompass the ambient.
- c. Reductions in the noise standards for noise sources identified in general note "A" above shall be applied after any increases warranted by elevated ambient conditions prescribed in general note "B", subject to verification through a noise study.

Source: City of Paso Robles Municipal Code, Section 21.60.060.

### **Noise Level Criteria Applied to the Project**

The nearest noise-sensitive receptors to the project site have been identified as residences to the south within the Los Robles Mobile Home Estates. These residential uses are shown on Figure 1. Based on the proposed uses of the project (i.e., commercial services and sales), it is reasonably assumed that hours of operation for the business would be limited to daytime and evening hours only. Based on the information above, the City's exterior and interior daytime and evening noise level limits for residential uses shown in Table 2 would be applicable to the project. However, pursuant to the footnote "b" contained in Table 2, where ambient noise levels exceed the exterior noise level standards shown in Table 2, the exterior noise standards shall be increased in 5 dB increments to encompass the ambient.

Based on the results from the BAC ambient noise level survey at the nearest residential uses to the south (Table 1), and pursuant to the adjustment criteria contained in Table 2, the following exterior noise level limits shown in Table 3 were applied to project on-site operations and assessed at the nearest residential uses to the south of the project. Satisfaction of the City's noise level standards at the closest residential uses would ensure compliance with the City's noise level limits at residential uses located farther away.

Table 3

Municipal Code Exterior Noise Level Standards Applied to the Project

	age Mea oise Lev		•		nadjust Standar										
Day	rtime	Eve	ning	Day	time	Eve	ning	Day	time	Eve	ning	Day	time	Eve	ning
L <sub>eq</sub>	L <sub>max</sub>	$L_{eq}$	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>	$L_{eq}$	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>	$L_{eq}$	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>	$L_{eq}$	L <sub>max</sub>
54	64	53	64	55	75	50	70	No	No	Yes	No	55	75	55	70

- Average measured hourly noise levels at the nearest residential uses to south (Table 1).
- <sup>2</sup> Unadjusted City of Paso Robles Municipal Code exterior noise level limits for residential uses (Table 2).
- <sup>3</sup> Determination based on a comparison of measured ambient noise level data and the City's noise standards.
- Adjusted noise standards in red pursuant to footnote b of Table 2.

Source: City of Paso Robles Municipal Code Section 21.60.060 and BAC.

The exterior noise level limits shown in Table 3 were applied at the outdoor areas (i.e., backyards) of the nearest residential uses to the south. Additionally, the City's (unadjusted) interior noise level limits for residential uses presented in Table 2 were also applied to the project.

### **Evaluation of Project-Generated Operations Noise**

As mentioned previously, the project proposes the development of a service center for semi-trucks, a retail parts department, and a dealership. The site amenities would include offices for employees, a lounge area for customers, an outdoor display area, and customer parking.

The most significant noise sources associated with normal project operations will likely consist of air compressors and pneumatic tools associated with the service department (within the building), and on-site truck circulation. In addition, activities occurring within a covered outdoor

Bollard Acoustical Consultants, Inc. (BAC)

maintenance area for compressed natural gas (CNG) vehicles have also been identified as a primary noise source. The locations of the on-site truck circulation route, service department and CNG maintenance area are shown on Figure 2. Analyses of noise exposure associated with the above-identified on-site activities at the nearest residential uses to the south are presented in the following section.

### **On-Site Truck Circulation Noise**

It is expected that most of the on-site truck circulation will be associated with the service department. The project site plan indicates that the trucks will enter and exit the property via one access point on Theatre Drive. Once on the project property, the trucks will head west towards the service department near the rear of the building. The location of the on-site circulation route, which include truck turnaround areas indicated in the site plan, is illustrated on Figure 2.

Heavy truck arrivals and departures, and on-site truck circulation, will occur at low speeds. To quantify the noise generation of slow moving trucks, BAC utilized single-event passby noise test results for slow-moving heavy trucks conducted at the West El Camino truck stop in Sacramento, California. The passby measurements were conducted at a reference distance of 50 feet at a location suitable for isolation of individual passby events. According to BAC file data, single-event heavy truck passby noise levels are approximately 74 dB L<sub>max</sub> and 83 dB SEL at a reference distance of 50 feet.

Because the City of Paso Robles Municipal Code noise standards are provided in terms of both hourly average (Leq) noise levels and individual maximum (Lmax) noise levels, it is necessary to identify the number of truck movements occurring during a typical busy hour of operations to assess compliance with the Leq-based standards. Based on the project site plan, the truck service department has approximately 10 bays (8 work bench areas, 2 having double bay capacity). Conservatively assuming that all 10 truck bays could both fill and empty during a worst-case busy hour, the project would generate 20 truck passbys during that hour. Based on a conservative estimate of 20 truck passbys during a given worst-case hour and an SEL of 83 per passby, the hourly average noise level generated by heavy truck passbys computes to 60 dB Leq at a reference distance of 50 feet during a worst-case busy hour of service operations.

Based on the assumptions and equation provided above, and assuming standard sound wave spreading loss (-6 dB per doubling of distance), worst-case on-site truck circulation noise exposure at the nearest residential uses to the south was calculated and the results of those calculations are presented in Table 4.

Table 4
Predicted Worst-Case On-Site Truck Circulation Noise Levels at Nearest Residential Uses

		Predicted Noise Levels (dB)			
Residential APN <sup>1</sup>	Distance (ft) <sup>2</sup>	$L_{eq}$	L <sub>max</sub>		
040-133-020	200	51	62		
040-133-022	215	51	61		
040-133-024	280	49	59		
Applied Day	time Noise Standards (dB) <sup>3</sup>	55	75		
Applied Eve	ning Noise Standards (dB) <sup>3</sup>	55	70		

<sup>&</sup>lt;sup>1</sup> Residential parcels are shown on Figures 1 and 2.

Source: Bollard Acoustical Consultants. Inc. 2022.

As indicated in Table 4, worst-case project on-site truck circulation noise level exposure is predicted to satisfy the applied City of Paso Robles Municipal Code exterior daytime and evening noise level limits at the nearest residential uses. In addition, standard residential construction (e.g., stucco siding, STC-27 windows, door weather-stripping, exterior wall insulation, composition plywood roof), typically results in an exterior to interior noise reduction of approximately 25 dB with windows and doors closed. Given this exterior-to-interior noise reduction typically achieved from standard residential construction, and based on the predicted exterior noise levels in Table 4, project on-site truck circulation noise level exposure is expected to be well below the Municipal Code interior daytime and evening noise level standards within the interior areas of the nearest residences.

Based on the analysis provided above, project on-site truck circulation noise level exposure is expected to satisfy the applied City of Paso Robles Municipal Code exterior and interior noise level criteria *provided* the following specific measure is implemented by the project:

1. All on-site truck circulation should be limited to daytime and/or evening hours only (i.e., no operations during nighttime hours).

### **Service Department Equipment Noise**

The project site plans indicate the truck service/repair department will be located within the west end of the proposed building. The site plans further indicate that the service portion of the building will have a total of 10 bay doors, distributed evenly between the north and south sides of the building. The proposed building and service department are shown in Figure 2.

To quantify noise levels associated with service department equipment, BAC utilized file data collected for an automobile repair facility (Red Rocket Automotive Repair Facility in Sacramento, California – 2013). Specific noise sources quantified in the noise level data included an air compressor, air hammer, impact wrench, hydraulic lift, and an oil pump. The results of the reference noise level measurements are contained below in Table 5.

<sup>&</sup>lt;sup>2</sup> Distances scaled from nearest on-site truck circulation to backyard of residences using the provided site plan.

<sup>&</sup>lt;sup>3</sup> Applied noise standards based on BAC noise survey and City adjustment criteria.

Table 5
Reference Noise Levels Collected at the Red Rocket Repair Facility in Sacramento, CA (2013)

Equipment	Measurement Distance (ft)	L <sub>eq</sub> While in Use (dB)	Minutes Per Hour Used (est.) <sup>1</sup>	Computed Hourly L <sub>eq</sub> (dB)	Measured L <sub>max</sub> (dB)
Compressor	30	73	15	67	75
Air hammer	30	92	5	81	95
Impact wrench	30	75	10	67	82
Hydraulic lift	30	81	10	73	84
Oil pump	15	70	10	62	71

<sup>&</sup>lt;sup>1</sup> The number of minutes in any given hour each noise source would be in operation was estimated from previous BAC observations at automobile repair facilities, as noise-producing equipment is not in constant use.

Source: Bollard Acoustical Consultants, Inc. 2013.

Based on the reference noise measurements for the equipment in Table 5, and assuming standard sound wave spreading loss (-6 dB per doubling of distance), equipment noise exposure at the nearest residential uses to the south was calculated and the results of those calculations are presented below in Tables 6 and 7. The data shown in Table 6 reflect predicted equipment noise levels at the nearest residential uses to the south with service department bay doors on the south and west sides of the building in the open position. Predicted equipment noise levels presented in Table 7 include consideration of the sound transmission loss that would be provided by the bay doors on the south and west sides of the building in the closed position during operations and have been adjusted by -15 dB.

According to the provided site plans, the air compressor for the service department is proposed to be located above the covered outdoor CNG vehicle maintenance area on the west side of the building (i.e., equipment will not be located within the building). As a result, no adjustment for service department bay door or building facade transmission loss was applied to air compressor noise level exposure at the nearest residential uses in Table 7.

Table 6
Predicted Service Department Equipment Noise Levels at Nearest Residential Uses – Bay Doors Open

			Predicted Equipment Noise Levels (dB)										
		Comp	Compressor <sup>3</sup> Air Hammer Impact Wrench Hydraulic Li						ulic Lift	Oil Pump		Combined <sup>3</sup>	
Residential APN <sup>1</sup>	Distance (ft) <sup>2</sup>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>
040-133-020	280	48	56	62	76	48	63	54	65	37	46	63	76
040-133-022	330	46	54	60	74	46	61	52	63	35	44	61	74
040-133-024	415	44	52	58	72	44	59	50	61	33	42	59	72
							Ар	plied Day	time Nois	e Standa	rds (dB) <sup>4</sup>	55	75
Applied Evening Noise Standards (dB) <sup>4</sup>								rds (dB) <sup>4</sup>	55	70			

<sup>&</sup>lt;sup>1</sup> Residential parcels are shown on Figures 1 and 2.

Source: Bollard Acoustical Consultants, Inc. 2022.

Table 7
Predicted Service Department Equipment Noise Levels at Nearest Residential Uses – Bay Doors Closed

			Predicted Equipment Noise Levels (dB) <sup>3</sup>										
		Comp	Compressor Air Hammer			Impact Wrench Hydraulic Lift		Oil Pump		Combined⁴			
Residential APN <sup>1</sup>	Distance (ft) <sup>2</sup>	L <sub>eq</sub>	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>	Leq	L <sub>max</sub>	L <sub>eq</sub>	L <sub>max</sub>
040-133-020	280	48	56	47	61	33	48	39	50	22	31	51	61
040-133-022	330	46	54	45	59	31	46	37	48	20	29	49	59
040-133-024	415	44	52	43	57	29	44	35	46	<20	27	47	57
							Ар	plied Day	time Nois	e Standaı	rds (dB)⁵	55	75
							Ар	plied Eve	ning Nois	e Standaı	rds (dB) <sup>5</sup>	55	70

<sup>&</sup>lt;sup>1</sup> Residential parcels are shown on Figures 1 and 2.

Source: Bollard Acoustical Consultants. Inc. 2022.

<sup>&</sup>lt;sup>2</sup> Distances scaled from the nearest work area within service department to backyard of residences using the provided site plan.

<sup>&</sup>lt;sup>3</sup> Calculated combined Leq and highest predicted Lmax noise levels from all equipment.

Applied noise standards based on BAC noise survey and City adjustment criteria.

<sup>&</sup>lt;sup>2</sup> Distances scaled from the nearest work area within service department to backyard of residences using the provided site plan.

<sup>&</sup>lt;sup>3</sup> Predicted equipment noise levels with consideration of bay doors on south and west sides of service department in the closed position during equipment operations. No sound transmission loss adjustment for bay doors/building facade applied to predicted air compressor noise levels.

<sup>&</sup>lt;sup>4</sup> Calculated combined Leg and highest predicted Lmax noise levels from all equipment.

<sup>&</sup>lt;sup>5</sup> Applied noise standards based on BAC noise survey and City adjustment criteria.

Bollard Acoustical Consultants, Inc. (BAC)

As indicated in Table 6, noise levels associated with air hammer equipment operations with bay doors in the *open* position could exceed the applied City of Paso Robles Municipal Code exterior daytime and evening noise level limits at the nearest residential uses. Noise from all other sources is predicted to be satisfactory with the City standards. With service department bay doors in the *closed* position, all equipment noise levels are predicted to satisfy the applied Municipal Code exterior daytime and evening noise level limits at the nearest residential uses to the south. Additionally, given the exterior to interior noise reduction typically achieved from standard residential construction (approximately 25 dB with windows and doors closed), service department equipment noise level exposure is expected to satisfy the Municipal Code interior daytime and evening noise level standards within the interior areas of the nearest residences – both with building bay doors in the open and closed positions.

Based on the analysis provided above, project service department equipment noise level exposure is expected to satisfy the applied City of Paso Robles Municipal Code exterior and interior noise level criteria *provided* the following specific measures are implemented by the project:

- 1. All service department operations should be limited to daytime and/or evening hours only (i.e., no operations during nighttime hours).
- 2. Operations within the service department area of the building should occur with south and west side bay doors in the closed position while air hammer usage is occurring. Additionally, service technicians and management should be aware of equipment use during the brief periods in which air hammer usage is occurring to reduce to the potential for an exceedance of the applied Municipal Code noise level criteria at the closest residential uses.

### **CNG Vehicle Maintenance Area Equipment Noise**

An analysis of service department equipment noise level exposure was presented in the previous section. Based on the reference noise measurements in Table 5, and assuming standard sound wave spreading loss (-6 dB per doubling of distance), CNG vehicle maintenance area equipment noise exposure at the nearest residential uses to the south was calculated and the results of those calculations are presented in Table 8. It should be noted that not all of the equipment identified in Table 5 was utilized in the analysis of CNG vehicle maintenance area noise exposure. Rather, this analysis focuses on assumed equipment usage within the outdoor CNG vehicle maintenance area.

Table 8
Predicted CNG Vehicle Maintenance Area Equipment Noise Levels at Nearest Residential Uses

			Predicted Equipment Noise Levels (dB)							
Residential		Comp	Compressor		Wrench	Oil I	Pump	Combined <sup>3</sup>		
APN <sup>1</sup>	Distance (ft) <sup>2</sup>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	Leq	L <sub>max</sub>	
040-133-020	260	48	56	48	63	37	46	51	63	
040-133-022	300	47	55	47	62	36	45	50	62	
040-133-024	385	45	53	45	60	34	43	48	60	
		Applied Daytime Noise Standards (dB) <sup>4</sup>						55	75	
			-	55	70					

<sup>&</sup>lt;sup>1</sup> Residential parcels are shown on Figures 1 and 2.

Source: Bollard Acoustical Consultants, Inc. 2022.

The Table 8 data indicate noise levels associated with outdoor CNG vehicle maintenance area equipment are predicted to satisfy the applied City of Paso Robles Municipal Code exterior daytime and evening noise level limits at the nearest residential uses. In addition, given the exterior to interior noise reduction typically achieved from standard residential construction (approximately 25 dB with windows and doors closed), CNG vehicle maintenance equipment noise level exposure is expected to satisfy the Municipal Code interior daytime and evening noise level standards within the interior areas of the nearest residences.

Based on the analysis provided above, project CNG vehicle repair equipment noise level exposure is expected to satisfy the applied City of Paso Robles Municipal Code exterior and interior noise level criteria *provided* the following specific measures are implemented by the project:

- 1. All operations within the outdoor CNG vehicle maintenance area should be limited to daytime and/or evening hours only (i.e., no operations during nighttime hours).
- 2. To reduce the potential for an exceedance of the applied City of Paso Robles Municipal Code noise criteria at the nearest residential uses, air hammers or hydraulic lifts should not be used or installed in the outdoor CNG vehicle maintenance area.

### **Public Address System**

It is unclear at the time of writing this report whether the project will include a public address (PA) system. However, the loudness of a PA system is highly dependent on variables that include system power output, speaker distance and directionality relative to receiver, and volume level. Thus, it is difficult to quantify project PA system noise exposure with reasonable levels of precision.

Based on the experience of BAC with PA systems, the loudness of the system is typically set above ambient conditions to be clearly heard by its recipients. However, because the Municipal

<sup>&</sup>lt;sup>2</sup> Distances scaled from CNG vehicle maintenance area to backyard of residences using the provided site plan.

<sup>&</sup>lt;sup>3</sup> Calculated combined Leq and highest predicted Lmax noise levels from all equipment.

<sup>&</sup>lt;sup>4</sup> Applied noise standards based on BAC noise survey and City adjustment criteria.

Bollard Acoustical Consultants, Inc. (BAC)

Code noise level criteria applicable to this project are based on measured ambient conditions, such a configuration would likely exceed acceptable Municipal Code noise level limits.

For BAC to quantify noise associated with a PA system with a high level of precision (should one be proposed), a specific analysis prepared by a sound system designer would be required. Specifically, specifications for the system including overall noise level exposure at certain distances with consideration of speaker directionality would be needed. In absence of such specifications from a sound designer, it is the recommendation of BAC that the professional installer of the PA system (should one be proposed), ensure through analysis and testing that the equipment does not exceed 65 dB  $L_{max}$  at the nearest residential property lines. An overall PA system noise level of 65 dB  $L_{max}$  at the nearest residential property lines would avoid the potential for an exceedance of the Municipal Code's daytime and evening maximum noise level standards at those locations.

### Conclusions and Recommendations

This analysis concludes that noise generated by on-site truck circulation is expected to satisfy the applied City of Paso Robles daytime and evening exterior and interior noise level limits at the nearest residential uses to the south of the project. This analysis further concludes that equipment noise levels from service department and CNG vehicle maintenance activities are expected to satisfy the applied City of Paso Robles daytime and evening exterior and interior noise level limits at the nearest residential uses to the south of the project *provided* that the following specific measures are implemented by the project:

- On-site truck circulation, service department operations, and outdoor CNG vehicle maintenance area activities should be limited to daytime and/or evening hours only (i.e., no operations during nighttime hours).
- 2. Operations within the service department area of the building should occur with south and west side bay doors in the <u>closed</u> position at all times while air hammer usage is occurring. Additionally, service technicians and management should be aware of equipment use during the brief periods in which air hammer usage is occurring to reduce to the potential for an exceedance of the applied Municipal Code noise level criteria at the closest residential uses.
- To reduce the potential for an exceedance of the applied Municipal Code noise level criteria at the nearest residential uses, air hammers or hydraulic lifts should not be used or installed in the outdoor CNG vehicle maintenance area.

Finally, it is unclear at the time of writing this report whether the project will include a public address (PA) system. Should one be proposed, it is the recommendation of BAC that the professional installer of the PA system ensure through analysis and testing that the equipment does not exceed 65 dB  $L_{max}$  at the nearest residential property lines. An overall PA system noise level of 65 dB  $L_{max}$  at the nearest residential property lines would avoid the potential for an exceedance of the Municipal Code's daytime and evening maximum noise level standards at those locations.

## **Attachment 9**

Bollard Acoustical Consultants, Inc. (BAC)

These conclusions are based on the data and assumptions cited herein and on the site plan shown in Figure 2. Any substantive revisions to the project site plan or proposed operations could cause actual noise levels to vary relative to those predicted herein. BAC is not responsible for such revisions.

This concludes BAC's environmental noise assessment for the proposed Peterbilt Service and Sales Center in Paso Robles, California. Please contact BAC at (530) 537-2328 or <a href="mailto:info@bacnoise.com">info@bacnoise.com</a> with any questions regarding this assessment.

### Attachment 9

# Appendix A Acoustical Terminology

**Acoustics** The science of sound.

Ambient Noise The distinctive acoustical characteristics of a given space consisting of all noise sources

audible at that location. In many cases, the term ambient is used to describe an existing

or pre-project condition such as the setting in an environmental noise study.

**Attenuation** The reduction of an acoustic signal.

**A-Weighting** A frequency-response adjustment of a sound level meter that conditions the output

signal to approximate human response.

Decibel or dB Fundamental unit of sound. A Bell is defined as the logarithm of the ratio of the sound

pressure squared over the reference pressure squared. A Decibel is one-tenth of a

Bell.

CNEL Community Noise Equivalent Level. Defined as the 24-hour average noise level with

noise occurring during evening hours (7 - 10 p.m.) weighted by a factor of three and

nighttime hours weighted by a factor of 10 prior to averaging.

**Frequency** The measure of the rapidity of alterations of a periodic signal, expressed in cycles per

second or hertz.

**IIC** Impact Insulation Class (IIC): A single-number representation of a floor/ceiling partition's

impact generated noise insulation performance. The field-measured version of this

number is the FIIC.

Ldn Day/Night Average Sound Level. Similar to CNEL but with no evening weighting.

**Leq** Equivalent or energy-averaged sound level.

**L**max The highest root-mean-square (RMS) sound level measured over a given period of time.

**Loudness** A subjective term for the sensation of the magnitude of sound.

Masking The amount (or the process) by which the threshold of audibility is for one sound is

raised by the presence of another (masking) sound.

**Noise** Unwanted sound.

Peak Noise The level corresponding to the highest (not RMS) sound pressure measured over a

given period of time. This term is often confused with the "Maximum" level, which is the

highest RMS level.

RT<sub>60</sub> The time it takes reverberant sound to decay by 60 dB once the source has been


removed.

STC Sound Transmission Class (STC): A single-number representation of a partition's noise

insulation performance. This number is based on laboratory-measured, 16-band (1/3-octave) transmission loss (TL) data of the subject partition. The field-measured version

of this number is the FSTC.









### Legend

A Noise survey location facing north towards project site

Looking towards noise survey location near residential uses (equipment outlined in red)

Noise survey location facing east towards Theatre Drive and U.S. 101

Peterbilt Service & Sales Center Paso Robles, California

Noise Survey Photographs

Appendix B



**Attachment 9** 

## Appendix C

# Long-Term Ambient Noise Monitoring Results Peterbilt Service and Sales Center - Paso Robles, California Monday, June 6, 2022 - Tuesday, June 7, 2022

Hour	Leq	Lmax	L50	L90
2:00 PM	52	68	50	48
3:00 PM	49	61	49	47
4:00 PM	50	63	49	48
5:00 PM	49	62	48	46
6:00 PM	53	66	53	49
7:00 PM	54	65	53	50
8:00 PM	52	62	51	48
9:00 PM	53	66	52	48
10:00 PM	51	60	50	46
11:00 PM	50	70	47	41
12:00 AM	47	58	45	41
1:00 AM	48	60	45	41
2:00 AM	45	59	43	39
3:00 AM	48	62	45	39
4:00 AM	52	64	50	44
5:00 AM	56	64	55	53
6:00 AM	55	64	55	52
7:00 AM	57	64	57	54
8:00 AM	56	63	55	53
9:00 AM	55	62	54	52
10:00 AM	55	65	54	51
11:00 AM	51	58	51	48
12:00 PM	55	69	52	49
1:00 PM	53	67	53	50


		Statistical Summary									
	Daytime	e (7 a.m	- 7 p.m.)	Evening (7 p.m 10 p.m.)			Nighttime (10 p.m 7 a.m.)				
	High	Low	Average	High	Low	Average	High	Low	Average		
Leq (Average)	57	49	54	54	52	53	56	45	52		
Lmax (Maximum)	69	58	64	66	62	64	70	58	62		
L50 (Median)	57	48	52	53	51	52	55	43	48		
L90 (Background)	54	46	50	50	48	48	53	39	44		

Computed CNEL, dB	59
% Daytime Energy	59%
% Evening Energy	13%
% Nighttime Energy	28%

GPS Coordinates	35°34'38.28"N
GF3 Cooldinates	120°41'56.68"W



Appendix D
Long-Term Ambient Noise Monitoring Results
Peterbilt Service and Sales Center - Paso Robles, California
Monday, June 6, 2022 - Tuesday, June 7, 2022



Computed CNEL = 59 dB





## **Attachment 9**

### **MEMORANDUM**

Date: July 22, 2022

To: David Athey and Kristin Ferravanti, City of Paso Robles

From: Joe Fernandez and Korinne Tarien, CCTC

Subject: 2805 Theatre Drive Peterbilt Dealership Transportation Analysis

This memorandum summarizes the trip generation, safety, and vehicle miles traveled (VMT) evaluation of the 34,552 square foot building proposed at 2805 Theatre Drive in the City of Paso Robles. The building would be used for retail and services for semi-trucks and includes an on-site dealership. The site plan is shown on **Figure** 1

The proposed project is expected to have a less-than-significant impact to VMT.

We recommend the driveway widths be reduced to meet City standards and that the Theatre Drive improvements are constructed to accommodate two travel lanes, bike lanes, and a center left turn lane. We also recommend parking on Nutwood Circle be restricted on both sides of the road from the curb return to 20 feet west.

### TRIP GENERATION

The proposed project does not conform to standard uses in the Institute of Transportation Engineers' Trip Generation Manual. Accordingly, new traffic counts were conducted at a similar facility operated by the applicant in Salinas. Like the proposed project, the Salinas facility is located near US 101 and offers similar services in a similar sized building. **Table 1** below summarizes the trip counts collected at the Salinas facility, with detailed count sheets attached.

Elvee Drive Trip Generation Daily AM Peak Hour PM Peak Hour Out Land Use **Total Total Total** In In Out Peterbilt - Salinas 178 28 13 41 19 26 45 Source: Metro Traffic Data, CCTC, 2022.

Table 1: Peterbilt Trip Generation (Elvee Drive, Salinas)

The collected data shows that the Salinas facility generates approximately 178 daily, 41 AM, and 45 PM peak hour trips. It is assumed that the proposed project would generate a similar number of trips with fewer than 50 peak hour trips. These trips are likely to be roughly evenly split between the north and the south, gaining access to US 101 via the SR 46W and Main Street interchanges.

### **CEQA ANALYSIS**

Vehicle miles traveled (VMT) were analyzed consistent with recently mandated changes to the California Environmental Quality Act (CEQA) and state Office of Planning and Research (OPR) guidance. The City's 2022 Transportation Impact Analysis (TIA) Guidelines Supplement provide VMT and safety thresholds consistent with OPR guidance. Office and industrial projects may have a significant impact if the work VMT per employee exceeds 85 percent of the regional average. Work VMT captures home-based-work attractions (trips from homes to workplaces).

The SLOCOG Travel Demand Model was applied to estimate VMT. Project employees were estimated using typical square footage per employee from industry standard sources, then were added to the model. **Table 2** summarizes the VMT results.

Table 2: Regional VMT Analysis

Regional VMT Analysis									
Regional VIII Analysis									
	Regional	Regional							
Scenario	Employees	Work VMT							
2020 No Project	117,335	1,595,867							
2020 With Project	117,373	1,596,553							
Change from No Project 38 686									
1. Work VMT is attracted to workpla	ces (sum of hom	ne-based-work							
	50/ 6 : 1								

1. Work VMT is attracted to workplaces (sum of home-based-work attractions). Threshold calculated as 85% of regional average. Source: SLOCOG TDM, CCTC, 2022

The regional average work VMT per employee is 13.60 (1,595,867/117,335). A threshold of 85% of this level corresponds to 11.56 work VMT per employee. The project is forecast to have a work VMT per employee of 3.3, well below the threshold. This is due to the provision of jobs in a housing-rich area. Therefore, the project would have a less-than-significant impact to VMT.

Projects may also have a significant impact if they exacerbate an existing high-priority or similar safety location, introduce a design feature that substantially increases hazards, or propose features that do not meet City design standards.

Collision data was obtained from the Statewide Integrated Traffic Records System (SWITRS) for Templeton CHP and City police on Theatre Drive in the vicinity of the project between 2017 and 2021. One injury collision occurred near Ranch Paso Road when a bicycle was traveling the wrong way. No collisions occurred at or near Nutwood Circle. There are no observed collision patterns and no recommendations.

### SITE ACCESS AND ON SITE CIRCULATION

The project proposes two driveways one on Theater Drive and one on Nutwood Circle. The proposed driveway on Theatre Drive is 50 feet wide, larger than a standard commercial driveway. City Standard Drawing C-9 specifies a maximum driveway width of 30 feet. We recommend both driveways meet City Standards.

The project will be required to complete frontage improvements on Theatre Drive as currently shown on the site plan in **Figure 1**. The City and County Bike Plans include future Class II bike lanes on Theatre Drive. We recommend the Theatre Drive frontage improvements be designed to accommodate two travel lanes, bike lanes, and a center left turn lane. Parking is not recommended on Theatre Drive. We also recommend parking on Nutwood Circle be restricted on both sides of the road from the curb return to 20 feet west consistent with the California Manual on Uniform Traffic Control Devices (CAMUTCD).

Please let us know if you have any questions.


### **ATTACHMENTS**

Site Plan Figure

Salinas Peterbilt Counts

Figure 1 - Site Plan

## **Attachment 9**





Peterbilt Paso Robles



NUMBER OF LANES

### Metro Traffic Data Inc.

310 N. Irwin Street - Suite 20 Hanford, CA 93230

800-975-6938 Phone/Fax www.metrotrafficdata.com

## Attachment 24 Hour Count Report


Prepared For:

Central Coast Transportation Consulting 895 Napa Avenue, Suite A-6 Morro Bay, CA 93442

LOCATION	Elvee Dr @ Peterbilt Western Driveway	LATITUDE	36.6673123
COUNTY	Monterey	LONGITUDE	-121.6312846
COLLECTION DATE _	Thursday, June 2, 2022	WEATHER	Clear

			Inbound	i			Outbound				
Hour	1st	2nd	3rd	4th	Total	1st	2nd	3rd	4th	Total	Totals
12:00 AM	0	0	0	0	0	0	0	0	0	0	0
1:00 AM	0	0	0	0	0	0	0	0	0	0	0
2:00 AM	0	0	0	0	0	0	0	0	0	0	0
3:00 AM	0	0	0	0	0	0	0	0	0	0	0
4:00 AM	0	0	0	0	0	0	0	0	0	0	0
5:00 AM	0	0	0	0	0	0	0	0	0	0	0
6:00 AM	0	0	0	0	0	0	0	0	0	0	0
7:00 AM	0	1	0	1	2	1	1	1	1	4	6
8:00 AM	1	1	3	1	6	0	1	0	2	3	9
9:00 AM	0	0	0	0	0	0	0	0	0	0	0
10:00 AM	0	0	0	0	0	0	0	0	0	0	0
11:00 AM	0	0	0	0	0	0	0	0	0	0	0
12:00 PM	0	0	0	0	0	0	0	0	0	0	0
1:00 PM	0	0	0	0	0	0	0	0	0	0	0
2:00 PM	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	1	1	2	2	6	1	0	0	4	5	11
4:00 PM	2	4	0	1	7	3	1	5	2	11	18
5:00 PM	0	1	0	0	1	0	0	0	0	0	1
6:00 PM	0	0	0	0	0	0	0	0	0	0	0
7:00 PM	0	0	0	0	0	0	0	0	0	0	0
8:00 PM	0	0	0	0	0	0	0	0	0	0	0
9:00 PM	0	0	0	0	0	0	0	0	0	0	0
10:00 PM	0	0	0	0	0	0	0	0	0	0	0
11:00 PM	0	0	0	0	0	0	0	0	0	0	0
Total		48.	9%		22		51.	1%		23	
Iotai					4	5					

AM% 33.3% AM Peak 14 8:00 am to 9:00 am AM P.H.F. 0.70 PM% 66.7% PM Peak 32 4:30 pm to 5:30 pm PM P.H.F. 0.67





NUMBER OF LANES

### Metro Traffic Data Inc.

310 N. Irwin Street - Suite 20 Hanford, CA 93230

800-975-6938 Phone/Fax www.metrotrafficdata.com

# Attachment 24 Hour Count Report


Prepared For:

Central Coast Transportation Consulting 895 Napa Avenue, Suite A-6 Morro Bay, CA 93442

LOCATION	Elvee Dr @ Peterbilt Eastern Driveway	LATITUDE	36.666952	
COUNTY	Monterey	LONGITUDE	-121.6301178	
COLLECTION DATE	Thursday, June 2, 2022	WEATHER	Clear	

			Inbound	t				Hourly			
Hour	1st	2nd	3rd	4th	Total	1st	2nd	3rd	4th	Total	Totals
12:00 AM	0	0	0	0	0	0	0	0	0	0	0
1:00 AM	0	0	0	0	0	0	0	0	0	0	0
2:00 AM	0	0	0	0	0	0	0	0	0	0	0
3:00 AM	0	0	0	0	0	0	0	0	0	0	0
4:00 AM	0	0	0	0	0	0	0	0	0	0	0
5:00 AM	0	0	0	0	0	0	0	0	0	0	0
6:00 AM	0	0	0	0	0	0	0	0	0	0	0
7:00 AM	2	5	6	13	26	0	2	5	2	9	35
8:00 AM	5	2	6	2	15	2	2	4	3	11	26
9:00 AM	0	0	0	0	0	0	0	0	0	0	0
10:00 AM	0	0	0	0	0	0	0	0	0	0	0
11:00 AM	0	0	0	0	0	0	0	0	0	0	0
12:00 PM	0	0	0	0	0	0	0	0	0	0	0
1:00 PM	0	0	0	0	0	0	0	0	0	0	0
2:00 PM	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	5	3	2	10	5	1	6	2	14	24
4:00 PM	4	7	0	1	12	5	4	4	2	15	27
5:00 PM	0	1	0	0	1	12	7	0	1	20	21
6:00 PM	0	0	0	0	0	0	0	0	0	0	0
7:00 PM	0	0	0	0	0	0	0	0	0	0	0
8:00 PM	0	0	0	0	0	0	0	0	0	0	0
9:00 PM	0	0	0	0	0	0	0	0	0	0	0
10:00 PM	0	0	0	0	0	0	0	0	0	0	0
11:00 PM	0	0	0	0	0	0	0	0	0	0	0
Total		48.	1%		64		51.	9%		69	
Total					1:	33					

AM% 45.9% AM Peak 98 5:30 am to 6:30 am AM P.H.F. 0.58 PM% 54.1% PM Peak 37 3:00 pm to 4:00 pm PM P.H.F. 0.93



### Mitigation Monitoring and Reporting Plan

Project File No./Name: <b>Peterbilt Sales and Service Center</b> Approving Resolution No.: by: ☐ Planning Commission ☐ City Council	Date: <u>June 20, 2023</u>
The following environmental mitigation measures were either incorporated into the approved plar every mitigation measure listed below has been found by the approving body indicated above to non-significance. A completed and signed checklist for each mitigation measure indicates that it I	lessen the level of environmental impact of the project to a level of
Explanation of Headings:	
Type:	olumn will be initialed and dated. column will be initialed and dated.

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
AES-1. Any lights installed to illuminate the billboard shall be external and shielded so that the light source is not visible from roadways or properties zoned for residential use. The applicant shall use the least amount of light practicable for the purpose of illuminating the sign. The applicant shall provide a photometric plan before issuance of a building permit to demonstrate the proposed lighting will not spill onto any residentially zoned property.	Project	City of Paso Robles Community Development Department (CDD)	X	Field inspection.	Prior to final building inspection / occupancy of the building
<b>AES-2.</b> The freeway-oriented sign shall not exceed 30 feet in height.	Project	CDD	Х	Field inspection.	Prior to final building inspection / occupancy of the building

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
<b>AES-3.</b> Any future freeway-oriented sign for a business developed on the southern portion of the lot shall be collocated on the same sign structure as the freeway-oriented sign for the Peterbilt project.	Cumula tive	CDD	Х		Before planning submittal for undeveloped area
AES-4. The applicant shall provide and maintain landscaping and street trees along the entire length of both street frontages to the satisfaction of the Director of the Community Development Department. Street trees are not required on the remainder portion of the lot.	Project	CDD	Х	Landscaping plan. Field Inspection.	Prior to final building inspection / occupancy of the building
<b>AQ-1.</b> Maintain all construction equipment in proper tune according to manufacturer's specifications.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-2.</b> Fuel all off-road and portable diesel-powered equipment with California Air Resources Board (CARB) certified motor vehicle diesel fuel (non-taxed version suitable for use off-road.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-3. Use diesel construction equipment meeting CARB's Tier 2 certified engines or cleaner off-road heavy-duty diesel engines, and comply with the State off-Road Regulation.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
AQ-4. Use on-road heavy-duty trucks that meet the CARB's 2010 or cleaner certification standard for on-road heavy-duty diesel engines, and comply with the State On-Road Regulation.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-5.</b> All on and off-road diesel equipment shall not idle for more than 5 minutes. Signs shall be posted in the designated queuing areas and or job sites to remind drivers and operators of the 5-minute idling limit.	Project	CDD	X	Notes shown on construction documents. Site inspection of signs.	Prior to issuance of grading permit Prior to issuance of grading permit
AQ-6. All projects with diesel-powered construction activity shall comply with Section 2485 of Title 13 of the California Code of Regulations and the 5-minute idling restriction identified in Section 2449(d)(2) of the California Air Resources Board's In-Use Off-Road Diesel regulation to minimize toxic air pollution impacts from idling diesel engines. The specific requirements and exceptions for the on-road and off-road regulations can be reviewed at the following web sites: arb.ca.gov/sites/default/files/classic/msprog/truck-idling and arb.ca.gov/regact/2007/ordiesl07/frooal.pdf	Project	CDD	X	Notes shown on construction documents. Site inspection of signs.	Prior to issuance of a grading permit
AQ-7. Diesel idling within 1,000 feet of sensitive receptors is not permitted.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
AQ-8. Staging and queuing areas shall not be located within 1,000 feet of sensitive receptors.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-9. The applicant shall post and enforce no idling areas at the site.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of a grading permit
AQ-10. Electrify equipment when feasible.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-11.</b> Substitute gasoline-powered in place of diesel-powered equipment, where feasible.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-12.</b> Use alternatively fueled construction equipment on-site where feasible, such as compressed natural gas (CNG), liquefied natural gas (LNG), propane or biodiesel.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-13. Diesel equipment used to construct the site shall install California Verified Diesel Emission Control Strategies listed at: <a href="http://www.arb.ca.gov/diesel/verdev/vt/cvt.htm">http://www.arb.ca.gov/diesel/verdev/vt/cvt.htm</a> .	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-14.</b> 15% of construction fleet vehicles shall be zero emission vehicles.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-15.</b> The project shall include alternative fuel fleet vehicle(s).	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
<b>AQ-16.</b> The project shall reduce the amount of disturbed area where possible.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-17. The project shall use water trucks or sprinkler systems in sufficient quantities to prevent airborne dust from leaving the site and from exceeding the APCD's limit of 20% opacity for greater than 3 minutes in any 60-minute period. Increased watering frequency is required whenever wind speeds exceed 15 mph. Reclaimed (non-potable) water shall be used whenever possible. When drought conditions exist and water use is a concern, the contractor or builder shall consider use of a dust suppressant that is effective for the specific site conditions to reduce the amount of water used for dust control. Refer to http://www.valleyair.org/busind/comply/PM10/Product s%20Available%20for%20Controlling%20PM10%20Emis sions.htm for a list of potential dust suppressants.	Project	CDD	X	Notes shown on construction documents. Site inspections.	Prior to issuance of grading permit
<b>AQ-18.</b> All dirt stock-pile areas shall be sprayed daily and covered with tarps or other barriers as needed.	Project	CDD	X	Notes shown on construction documents. Site inspections.	Prior to issuance of grading permit
AQ-19. Permanent dust control measures identified in the approved project revegetation and landscape plans shall be implemented as soon as possible following completion of any soil disturbing activities.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
AQ-20. Exposed ground areas that are planned to be reworked at dates greater than one month after initial grading shall be sown with a fast germinating, non-invasive grass seed and watered until vegetation is established.	Project	CDD	X	Notes shown on construction documents.	Prior to issuance of grading permit
<b>AQ-21.</b> All disturbed soil areas not subject to revegetation shall be stabilized using approved chemical soil binders, jute netting, or other methods approved in advance by the APCD.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-22. All roadways, driveways, sidewalks, etc. to be paved shall be completed as soon as possible. In addition, building pads should be laid as soon as possible after grading unless seeding or soil binders are used.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-23. Vehicle speed for all construction vehicles shall not exceed 15 mph on any unpaved surface at the construction site.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-24. All trucks hauling dirt, sand, soil, or other loose materials shall be covered or shall maintain at least two feet of freeboard (minimum vertical distance between top of load and top of trailer) in accordance with CVC Section 23114.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
AQ-25. The applicant shall sweep streets at the end of each day if visible soil material is carried onto adjacent paved roads. Water sweepers with reclaimed water shall be used where feasible. Roads shall be pre-wetted prior to sweeping when feasible.	Project	CDD	X	Notes shown on construction documents. Site Inspections.	Prior to issuance of grading permit
<b>AQ-26.</b> The applicant shall install wheel washers where vehicles enter and exit unpaved roads onto streets or wash off trucks and equipment leaving the site.	Project	CDD	Х	Notes shown on construction documents. Site inspections.	Prior to issuance of grading permit
AQ-27. The contractor or builder shall designate a person or persons whose responsibility is to ensure any to monitor the fugitive dust emissions do not result in a nuisance and to enhance the implementation of the mitigation measures as necessary to minimize dust complaints, and reduce visible emissions below the APCD's limit of 20% opacity for greater than 3 minutes in any 60-minute period, and to prevent transport of dust offsite. Their duties shall include holidays and weekend periods when work may not be in progress (for example, wind-blown dust could be generated on an open dirt lot). The name and telephone number of such persons shall be provided to the APCD Compliance Division prior to the start of any grading, earthwork, or	Project	CDD	X	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
demolition (Contact the Compliance Division at 805-781-5912).					
<b>AQ-28.</b> The applicant shall take additional measures as needed to ensure dust from the project site does not impact areas outside the project boundary.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-29. To prevent 'track out' (sand or soil that adheres to and/or agglomerates on the exterior surfaces of motor vehicles and/or equipment (including tires) that may then fall onto any highway or street as described in CVC Section 23113 and California Water Code 13304), the applicant shall designate access points and require all employees, subcontractors, and others to use them. The applicant shall install and operate a 'track-out prevention device' where vehicles enter and exit unpaved roads onto paved streets. The 'track-out prevention device' can be any device or combination of devices that are effective at preventing track out, located at the point of intersection of an unpaved area and a paved road. Rumble strips or steel plate devices need periodic cleaning to be effective. If paved roadways accumulate tracked out soils, the track-out prevention device may need to be modified.	Project	CDD	X	Notes shown on construction documents.	Prior to issuance of grading permit
AQ-30. All fugitive dust mitigation measures shall be shown on grading and building plans.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
<b>AQ-31.</b> The applicant shall acquire all required APCD permits for portable equipment greater than 50 hp used during construction activities.	Project	CDD and APCD	Х	Submittal with construction documents.	Prior to issuance of grading permit
<b>AQ-32.</b> The applicant shall acquire all required APCD permits for operational stationary diesel engines greater than 50 hp.	Project	CDD and APCD	Х	Submittal with construction documents.	Prior to issuance of grading permit
AQ-33. Before issuance of a building permit, the applicant shall prepare a screening-level health risk assessment with risk screening inputs including:	Project	CDD and APCD	Х	Submittal with construction documents.	Prior to issuance of grading permit
<ul> <li>Daily operational phase trips to the project site;</li> <li>% of daily trips that are diesel trucks and their anticipated make up (i.e. heavy-heavy duty, mediumheavy duty, light-heavy duty);</li> </ul>					
Total daily diesel trips to site;					
Number of days per year project location will be open;					
Total annual diesel trips; and					
Distance from midpoint of truck service center to lot of nearest sensitive receptor.					

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
If the screening assessment is above 10 in a million, a more comprehensive health risk analysis shall be required. Results of the screening and/or the refined health risk assessment shall be provided to the APCD for review and approval.					
<b>AQ-34.</b> Developmental burning of vegetative material is prohibited.	Project	CDD	X		Ongoing
<b>BIO-1.</b> All construction work activities shall be completed during daylight hours (between sunrise and sunset) and outside of rain events.	Project	CDD	Х	Notes shown on construction documents.	Prior to issuance of grading permit
<b>BIO-2.</b> The Project impact area shall be clearly marked or delineated with stakes, flagging, tape, or signage prior to work. Areas outside of work limits shall be considered environmentally sensitive and shall not be disturbed.	Project	CDD	Х	Notes shown on construction documents. Site inspection.	Prior to issuance of grading permit.
<b>BIO-3.</b> All equipment and vehicles shall be checked and maintained daily to prevent spills of fuel, oil, and other hazardous materials. A designated staging area shall be established for vehicle/equipment parking and storage of fuel, lubricants, and solvents. All fueling and	Project	CDD	Х	Notes shown on construction documents. Site Inspection.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
maintenance activities shall take place in the staging area.					
BIO-4. If vegetation removal (i.e., tree trimming/removal activities) is scheduled between February 1 and August 31 (general nesting bird season), nesting bird surveys shall be completed by a qualified biologist within 48 hours prior to start of work. If any active nests are discovered within or adjacent to work limits, an appropriate buffer (i.e., 500 feet for raptors and 250 feet for other birds, or at the discretion of a qualified biologist based on biological or ecological reasons) shall be established to protect the nest until a qualified biologist has determined that the nest is no longer active and/or the young have fledged.	Project	CDD	X	Notes shown on construction documents. Site inspection	Prior to issuance of grading permit
BIO-5. Within 30 days of the start of construction, a qualified biologist shall conduct a pre-activity survey of the Project Site for signs of San Joaquin kit fox and American badger, including tracks, scat, or suitable burrows (burrows four inches or greater in diameter). Potential dens shall be tracked for a minimum of four nights with motion-activated cameras to determine if the burrow is actively being used by San Joaquin kit fox or badger. All potential dens shall be avoided by a minimum of 50 feet until they have been determined to be inactive. In the event San Joaquin kit fox is identified	Project	CDD	X	Notes shown on construction documents.	Prior to issuance of grading permit

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
within the Project Site, the USFWS, CDFW, and all other appropriate agencies/government entities shall be contacted for further consultation.  In conjunction with the badger and kit fox survey, the qualified biologist will conduct a survey for Northern legless lizard. Hand search methods, including raking, will be used during the survey in areas where legless lizards are expected to be found (e.g., sandy/loose soils, under shrubs/leaf litter, other vegetation, or debris). If observed, the qualified biologist will relocate the lizard to nearby suitable habitat. The qualified biologist will prepare a completion letter-report to document the pre-activity survey results.					
<b>BIO-6.</b> If oak tree removal and/or damage is unavoidable due to Project implementation, 25% of the diameter of trees removed shall be replanted on the site.	Project	CDD	Х	Notes shown on construction documents. Site inspection.	Prior to issuance of grading permit and building permit and ongoing during the duration of construction.
<b>CUL-1.</b> In the event that buried or otherwise unknown cultural resources are discovered during construction work in the area of the find shall be suspended and the City of Paso Robles shall be contacted immediately, and appropriate mitigations measures shall be developed by qualified archeologist or historian if necessary, at the developers expense.	Project	CDD	X	Notes on construction documents.	Prior to issuance of grading and building permits.

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
CUL-2. In the event human remains are found on the project site during construction or during archaeological work, the person responsible for the excavation, or his or her authorized representative, shall immediately notify the San Luis Obispo County Coroner's office by telephone. No further excavation or disturbance of the discovery or any nearby area reasonably suspected to overlie adjacent remains (as determined by the qualified archaeologist and/or the Native American monitor) shall occur until the Coroner has made the necessary findings as to origin and disposition. If the Coroner recognizes the remains to be Native American, he or she shall contact the Native American Heritage Commission (NAHC) within 24 hours. The NAHC would make a determination as to the Most Likely Descendent.	Project	SLO County Coroner, Native American Heritage Commission	X	As needed	Ongoing during grading and construction.
<b>GEO-1.</b> The applicant shall provide a soils report for the project.	Project	CDD	Х	Shown on building plans.	Before building permit issuance.
<b>GEO-2.</b> The applicant shall provide a stormwater pollution prevention plan (SWPPP) for the project.	Project	CDD	Х	Shown on building plans.	Before building permit issuance.
<b>GHG-1.</b> The applicant shall submit a plan to reduce greenhouse gas emissions to below the applicable GHG significance threshold (1.9 MTCO <sub>2e</sub> /service population/year or other adopted GHG significance threshold). The plan shall incorporate GHG-reduction	Project	CDD	Х	Ongoing	Plan submitted before building permit issuance. Monitoring ongoing.

F	Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
measi	ures that may include, but are not limited to the					
follow	ving list.					
	e mitigation measures shall be the first priority of HG Reduction Plan, including but not limited to:					
a. b.	Receive electricity from onsite solar, Central Coast Community Energy (3CE) 3Cprime Service, or a combination thereof. Design roof structural members to handle dead					
C.	weight loads of solar-heated water and photovoltaic panels. Install only Energy Star certified or equivalent					
<b>C.</b>	and electrically powered mechanical equipment and appliances (not natural gas).					
d.	Implement on-site circulation design elements in parking lots to reduce vehicle queuing and improve the pedestrian environment.					
e.	Exceed Cal Green standards by 25% for providing on-site bicycle parking: both short-term racks and long-term lockers, or a locked room with standard racks and access limited to bicyclists only.					
f.	Provide improved public transit amenities (e.g.: covered transit turnouts, direct pedestrian access, bicycle racks, covered bench, smart					

	Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
	signage, route information displays, lighting,					
g.	etc.). Require 15% of fleet vehicles to be zero emission vehicles.					
h.	Require fleet vehicle(s) to include alternative fuel vehicles.					
i.	Provide dedicated parking for carpools, vanpools, and/or high-efficiency vehicles to meet or exceed Cal Green Tier 2.					
j.	Provide vanpool, shuttle, mini bus service (alternative fueled preferred).					
k.	Work with SLO Regional Rideshare to educate occupants with alternative transportation and smart commute information (e.g. transportation board, electronic kiosk, new hire packets, web portal, newsletters, social media, etc.).					
1.	Implement programs to reduce employee vehicle miles traveled (e.g. incentives, SLO Regional Rideshare trip reduction program, vanpools, onsite employee housing, alternative schedules (e.g. 9-80s, 4-10s, telecommuting, satellite work sites, etc.).					
m.	Provide a lunchtime shuttle to reduce single occupant vehicle trips and/or coordinate regular food truck visits.					
n.	Provide delivery service in clean fueled vehicles.					

	Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
0.	Implement a "No Idling" vehicle program which includes signage, enforcement, etc.					
p.	Meet or exceed Cal Green Tier 2 standards for providing EV charging infrastructure.					
q.	Install 1 or more level 2 or better EV charging stations.					
r.	Meet or exceed Cal Green Tier 2 standards for building energy efficiency.					
s.	Use battery powered or electric landscape maintenance equipment.					
t.	Use paints and cleaning products that are low-VOC content (e.g., 50 grams/liter VOC content, or less).					
the	ite measures within San Luis Obispo County shall be second priority of the GHG Reduction Plan, including not limited to:					
u.	Work with SLOCOG to create, improve, or expand a nearby 'Park and Ride' lot with car parking and bike lockers in proportion to the size of the project.					
V.	Implement SLO County generated offsets compliant with a protocol approved by the California Air Resources Board (CARB).					

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
Offsite measures within California shall be the third priority of the GHG Reduction Plan, including but not limited to:					
w. Implement California generated offsets compliant with a protocol approved by the California Air Resources Board (CARB).					
Offsite measures within North America shall be the fourth priority of the GHG Reduction Plan, including but not limited to:					
x. Implement North American generated offsets compliant with a protocol approved by the California Air Resources Board (CARB).					
<b>HAZ-1.</b> Operation of the project shall not include diesel or other vehicle fuel dispensing or the painting of vehicles.	Ongoin g	CDD	X	Shown on building plans.	Before building permit issuance.
HAZ-2. The project shall acquire and maintain all required permits and approvals from the SLO County Department of Environmental Health for the handling and storage of hazardous materials.	Ongoin g	SLO County Environmenta I Health Department	X	Required before building permit issuance	Before final building inspection.
<b>N-1.</b> On-site truck circulation, service department operations, and outdoor CNG vehicle maintenance area	Ongoin g	CDD			Ongoing enforcement.

Mitigation Measure PD22-02 / CUP22-16 / RZN22-03 / P22-0017 and CUP23-03 / P23-0019 (Peterbilt and Outfront Media)	Туре	Monitoring Department or Agency	Shown on Plans	Verified Implementation	Timing/Remarks
activities shall be limited to daytime hours only (7am – 7pm).					
<b>N-2.</b> South and west service bay doors shall be in the closed position at all times while air hammer equipment is in use.	Ongoin g	CDD			Ongoing enforcement.
<b>N-3.</b> No air hammers or hydraulic lifts shall be used or installed outside the indoor service area including the outdoor CNG vehicle maintenance area.	Ongoin g	CDD		Shown on building plans.	Before building permit issuance and ongoing enforcement.
<b>N-4.</b> Any amplified public address system shall be designed to not exceed 65dB L <sub>max</sub> at the nearest residential property line.	Project / Ongoin g	CDD		Results of noise analysis and testing of system submitted to City.	Before building permit issuance.

(add additional measures as necessary)

### **Explanation of Headings:**

Type:	Project, ongoing, cumulative
Monitoring Department or Agency:	Department or Agency responsible for monitoring a particular mitigation measure
Shown on Plans:	When a mitigation measure is shown on the plans, this column will be initialed and dated.
Verified Implementation:	When a mitigation measure has been implemented, this column will be initialed and dated.
Remarks:	Area for describing status of ongoing mitigation measure, or for other information.